

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+64.67-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,800 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	103,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	45 CY		
0009	0192000000-N	260	PROOF ROLLING	2 HR		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	600 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	196 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	140 SY		
0014	0335200000-E	305	15" DRAINAGE PIPE	130 LF		
0015	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0016	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0017	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	144 LF		
0019	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	72 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0995000000-E	340	PIPE REMOVAL	50 LF		
0021	1220000000-E	545	INCIDENTAL STONE BASE	135 TON		
0022	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	450 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,735 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	705 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,220 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	185 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	26 TON		
0028	2000000000-N	806	RIGHT OF WAY MARKERS	27 EA		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	700 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	2,300 LF		
0033	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	3 EA		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0037	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,100 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (5)	1,600 LF		
0039	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (59", 14.833', 14')	1 EA		
0040	3649000000-E	876	RIP RAP, CLASS B	600 TON		
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,050 SY		
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	19.25 SF		
0043	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	25 LF		
0044	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	3 EA		
0045	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0046	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,931 LF		
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,008 LF		
0049	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	2,173 LF		
0050	5326200000-E	1510	12" WATER LINE	2,290 LF		
0051	5326600000-E	1510	16" WATER LINE	845 LF		
0052	5558000000-E	1515	12" VALVE	2 EA		
0053	5558600000-E	1515	16" VALVE	1 EA		
0054	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0055	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,035 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	5810000000-E	1530	ABANDON 16" UTILITY PIPE	795 LF		
0057	5836000000-E	1540	24" ENCASEMENT PIPE	200 LF		
0058	5836200000-E	1540	30" ENCASEMENT PIPE	200 LF		
0059	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	100 LF		
0060	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	100 LF		
0061	5872300000-E	1550	TRENCHLESS INSTALLATION OF 30" IN SOIL	100 LF		
0062	5872310000-E	1550	TRENCHLESS INSTALLATION OF 30" NOT IN SOIL	100 LF		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	6,000 LF		
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0065	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,350 TON		
0066	6012000000-E	1610	SEDIMENT CONTROL STONE	1,200 TON		
0067	6015000000-E	1615	TEMPORARY MULCHING	10 ACR		
0068	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0069	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
0070	6024000000-E	1622	TEMPORARY SLOPE DRAINS	700 LF		
0071	6029000000-E	SP	SAFETY FENCE	400 LF		
0072	6030000000-E	1630	SILT EXCAVATION	1,900 CY		
0073	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,100 SY		
0074	6037000000-E	SP	COIR FIBER MAT	100 SY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	625	SY	
0076	6042000000-E	1632	1/4" HARDWARE CLOTH	450	LF	
0077	6070000000-N	1639	SPECIAL STILLING BASINS	4	EA	
0078	6071012000-E	SP	COIR FIBER WATTLE	600	LF	
0079	6071020000-E	SP	POLYACRYLAMIDE (PAM)	200	LB	
0080	6071030000-E	1640	COIR FIBER BAFFLE	700	LF	
0081	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
0082	6084000000-E	1660	SEEDING & MULCHING	10	ACR	
0083	6087000000-E	1660	MOWING	5	ACR	
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
0085	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0086	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	375	LB	
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	11	TON	
0088	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0089	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	
<b>STRUCTURE ITEMS</b>						
0090	8105500000-E	411	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	226	LF	
0091	8105600000-E	411	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	163	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8111000000-E	411	PERMANENT STEEL CASING FOR ***_***" DIA DRILLED PIER (4'-6")	227 LF		
0093	8112730000-N	450	PDA TESTING	2 EA		
0094	8113000000-N	411	SID INSPECTIONS	1 EA		
0095	8115000000-N	411	CSL TESTING	5 EA		
0096	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	20,153 SF		
0097	8161000000-E	420	GROOVING BRIDGE FLOORS	17,636 SF		
0098	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	490.3 CY		
0099	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+64.47-L-)	Lump Sum	L.S.	
0100	8217000000-E	425	REINFORCING STEEL (BRIDGE)	166,400 LB		
0101	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	26,582 LB		
0102	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	167.67 LF		
0103	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,976.83 LF		
0104	8364000000-E	450	HP12X53 STEEL PILES	1,710 LF		
0105	8503000000-E	460	CONCRETE BARRIER RAIL	1,082 LF		
0106	8524000000-E	SP	***" CHAIN LINK FENCE (72")	1,070 LF		
0107	8531000000-E	462	4" SLOPE PROTECTION	330 SY		
0108	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,601 TON		
0109	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,778 SY		
0110	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	

1148/Feb07/Q408095.05/D513332812000/E111

Total Amount Of Bid For Entire Project :

1-17-12  
Z-140

**Contract No.**     **C203142**

**County (ies):**    **Davidson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)