

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,100 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	1,200 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0011	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	16 LF		
0012	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	600 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	105 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	90 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	110 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	15 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
0025	2209000000-E	838	ENDWALLS	1.4 CY		
0026	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0027	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	3 EA		
0030	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0032	3628000000-E	876	RIP RAP, CLASS I	100 TON		
0033	3642000000-E	876	RIP RAP, CLASS A	50 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	570 SY		
0035	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	62 LF		
0036	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9 EA		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	391 SF		
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	106 SF		
0040	4430000000-N	1130	DRUMS	20 EA		
0041	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
0042	4507000000-E	1170	WATER FILLED BARRIER	115 LF		
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,837 LF		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,125 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0052	6029000000-E	SP	SAFETY FENCE	600 LF		
0053	6030000000-E	1630	SILT EXCAVATION	75 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	725 SY		
0055	6037000000-E	SP	COIR FIBER MAT	375 SY		
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	75 SY		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0058	6070000000-N	1639	SPECIAL STILLING BASINS	5 EA		
0059	6071012000-E	SP	COIR FIBER WATTLE	75 LF		
0060	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0061	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0062	6087000000-E	1660	MOWING	0.15 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0067	6111000000-E	SP	IMPERVIOUS DIKE	375 LF		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0070	6120000000-E	SP	CULVERT DIVERSION CHANNEL	415 CY		
0071	6123000000-E	1670	REFORESTATION	0.1 ACR		

CULVERT ITEMS

0072	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+15.00-L-)	Lump Sum	L.S.	
0073	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+15.00-L-)	Lump Sum	L.S.	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	138 TON		
0075	8196000000-E	420	CLASS A CONCRETE (CULVERT)	238.2 CY		
0076	8245000000-E	425	REINFORCING STEEL (CULVERT)	29,719 LB		
1042/Mar05/Q44800.1/D305939732000/E76			Total Amount Of Bid For Entire Project :			

Contract No. **C203080**

County (ies): **Madison**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General