

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	3,800 CY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (20+70.50)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	80 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	750 SY		
0010	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (18", V)	84 LF		
0011	0995000000-E	340	PIPE REMOVAL	68 LF		
0012	1099500000-E	505	SHALLOW UNDERCUT	150 CY		
0013	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	300 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	200 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	470 TON		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	65 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	500 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE	6 LF		
0027	2556000000-E	846	SHOULDER BERM GUTTER	8 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	312.5 LF		
0029	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0035	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,200 SY		
0036	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	82 LF		
0037	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0039	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7 EA		
0040	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	332 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
0042	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,618 LF		
0044	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	70 LF		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	850 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	385 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	305 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.25 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0053	6029000000-E	SP	SAFETY FENCE	100 LF		
0054	6030000000-E	1630	SILT EXCAVATION	460 CY		
0055	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0056	6037000000-E	SP	COIR FIBER MAT	450 SY		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	900		SY
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	520		LF
0059	6070000000-N	1639	SPECIAL STILLING BASINS	6		EA
0060	6071010000-E	SP	WATTLE	225		LF
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	125		LB
0062	6071030000-E	1640	COIR FIBER BAFFLE	140		LF
0063	6071050000-E	SP	*** SKIMMER (1-1/2")	2		EA
0064	6084000000-E	1660	SEEDING & MULCHING	2		ACR
0065	6087000000-E	1660	MOWING	1		ACR
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		LB
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5		TON
0070	6114500000-N	1667	SPECIALIZED HAND MOWING	10		MHR
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18		EA

STRUCTURE ITEMS

0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+70.50-L-)	Lump Sum		L.S.
------	--------------	----	-----------------------------------------------------------------------------------	----------	--	------

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+70.50-L-)	Lump Sum	L.S.	
0074	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	48 LF		
0075	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	24 LF		
0076	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	40.1 LF		
0077	8113000000-N	411	SID INSPECTIONS	1 EA		
0078	8114000000-N	411	SPT TESTING	1 EA		
0079	8115000000-N	411	CSL TESTING	1 EA		
0080	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+70.50-L-)	Lump Sum	L.S.	
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	66.5 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+70.50-L-)	Lump Sum	L.S.	
0083	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,858 LB		
0084	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,563 LB		
0085	8364000000-E	450	HP12X53 STEEL PILES	125 LF		
0086	8391000000-N	450	STEEL PILE POINTS	10 EA		
0087	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	270 LF		
0088	8594000000-E	876	RIP RAP, CLASS B	17 TON		
0089	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	530 TON		
0090	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	658 SY		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,350 LF		

0928/Jan25/Q49900.5/D432580350000/E92

Total Amount Of Bid For Entire Project :

Contract No. **C203086**

County (ies): **Rockingham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General