

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (20+23)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	500 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0008	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	1,500 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	2,600 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	50 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	150 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	108 LF		
0013	0335300000-E	305	18" DRAINAGE PIPE	120 LF		
0014	0335400000-E	305	24" DRAINAGE PIPE	52 LF		
0015	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	108 LF		
0016	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	56 LF		
0017	0995000000-E	340	PIPE REMOVAL	205 LF		
0018	1099500000-E	505	SHALLOW UNDERCUT	250 CY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	500 TON		
0020	1121000000-E	520	AGGREGATE BASE COURSE	278 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0022	1330000000-E	607	INCIDENTAL MILLING	205 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,421 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	782 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	660 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	140 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	5 TON		
0028	2000000000-N	806	RIGHT OF WAY MARKERS	18 EA		
0029	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0030	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0031	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0032	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0033	2077000000-E	815	6" OUTLET PIPE	6 LF		
0034	2253000000-E	840	PIPE COLLARS	1.11 CY		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0036	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0037	2556000000-E	846	SHOULDER BERM GUTTER	355 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3030000000-E	862	STEEL BM GUARDRAIL	512.5 LF		
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0044	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	4 EA		
0045	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	12 EA		
0046	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (5)	1,220 LF		
0047	3579000000-N	866	GENERIC FENCING ITEM 12' CATTLE GATE	2 EA		
0048	3580000000-E	866	GENERIC FENCING ITEM WOVEN WIRE FENCE WITH 1 STRAND ELECTRIC WIRE	150 LF		
0049	3635000000-E	876	RIP RAP, CLASS II	80 TON		
0050	3649000000-E	876	RIP RAP, CLASS B	26 TON		
0051	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	845 SY		
0052	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0053	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	61 LF		
0054	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10 EA		
0056	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	297 SF		
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0058	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0059	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,500 LF		
0060	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,500 LF		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	4,000 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	295 TON		
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	560 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	240 TON		
0065	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0069	6029000000-E	SP	SAFETY FENCE	700 LF		
0070	6030000000-E	1630	SILT EXCAVATION	720 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000 SY		
0072	6037000000-E	SP	COIR FIBER MAT	1,000 SY		
0073	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	220 SY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6042000000-E	1632	1/4" HARDWARE CLOTH	360 LF		
0075	6071010000-E	SP	WATTLE	140 LF		
0076	6071020000-E	SP	POLYACRYLAMIDE (PAM)	140 LB		
0077	6071030000-E	1640	COIR FIBER BAFFLE	130 LF		
0078	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0079	6084000000-E	1660	SEEDING & MULCHING	4.8 ACR		
0080	6087000000-E	1660	MOWING	2 ACR		
0081	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0082	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0083	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0084	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0085	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0086	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0087	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0088	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+23.00-L-)	Lump Sum	L.S.	
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (20+23.00-L-)	Lump Sum	L.S.	
0090	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40.8 CY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+23.00-L-)	Lump Sum	L.S.	
0092	821700000-E	425	REINFORCING STEEL (BRIDGE)	6,520 LB		
0093	836400000-E	450	HP12X53 STEEL PILES	325 LF		
0094	847500000-E	460	TWO BAR METAL RAIL	163.875 LF		
0095	851700000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-10 1/2")	180 LF		
0096	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	340 TON		
0097	862200000-E	876	GEOTEXTILE FOR DRAINAGE	375 SY		
0098	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0099	875310000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,080 LF		

1622/Jan24/Q49659.935/D390186510000/E99

Total Amount Of Bid For Entire Project :

Contract No. **C203032**

County (ies): **Rowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General