

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-M	200	CLEARING & GRUBBING .. HECTARE(S)	Lump Sum	L.S.	
0004	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB- BING	1.2 HA		
0005	0015000000-N	205	SEALING ABANDONED WELLS	4 EA		
0006	0036000000-M	225	UNDERCUT EXCAVATION	22,000 M3		
0007	0038000000-M	SP	SHALLOW UNDERCUT	300 M3		
0008	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	700 MTN		
0009	0134000000-M	240	DRAINAGE DITCH EXCAVATION	2,240 M3		
0010	0141000000-M	240	BERM DITCH CONSTRUCTION	750 M		
0011	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	6,380 M2		
0012	0192000000-N	260	PROOF ROLLING	40 HR		
0013	0195000000-M	SP	SELECT GRANULAR MATERIAL	29,500 M3		
0014	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	31,000 M2		
0015	0199000000-M	SP	TEMPORARY SHORING	233.2 M2		
0016	0241000000-M	SP	GENERIC GRADING ITEM GEOTEXTILE FOR PAVEMENT STAB- ILIZATION	16,500 M2		
0017	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATION, HAULING & DISPOSAL OF CONTAMINATED SOIL	2,500 MTN		
0018	0318000000-M	SP	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,250 MTN		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0320000000-M	SP	FOUNDATION CONDITIONING FABRIC	6,770 M2		
0020	0335000000-M	SP	***MM DRAINAGE PIPE (200MM)	31.2 M		
0021	0335200000-M	SP	375MM DRAINAGE PIPE	2,202 M		
0022	0335300000-M	SP	450MM DRAINAGE PIPE	676.8 M		
0023	0335400000-M	SP	600MM DRAINAGE PIPE	685.2 M		
0024	0335500000-M	SP	750MM DRAINAGE PIPE	373.2 M		
0025	0335600000-M	SP	900MM DRAINAGE PIPE	229.2 M		
0026	0335700000-M	SP	1050MM DRAINAGE PIPE	54 M		
0027	0335800000-M	SP	1200MM DRAINAGE PIPE	132 M		
0028	0335850000-M	SP	****MM DRAINAGE PIPE ELBOWS (375MM)	7 EA		
0029	0335850000-M	SP	****MM DRAINAGE PIPE ELBOWS (450MM)	6 EA		
0030	0343000000-M	SP	375MM SIDE DRAIN PIPE	268.8 M		
0031	0344000000-M	SP	450MM SIDE DRAIN PIPE	14.4 M		
0032	0345000000-M	SP	600MM SIDE DRAIN PIPE	8.4 M		
0033	0354000000-M	SP	****MM RC PIPE CULVERTS, CLASS ***** (375MM, V)	20.4 M		
0034	0366000000-M	SP	375MM RC PIPE CULVERTS, CLASS III	115.2 M		
0035	0384000000-M	SP	750MM RC PIPE CULVERTS, CLASS III	36 M		
0036	0408000000-M	SP	1350MM RC PIPE CULVERTS, CLASS III	121.2 M		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	0448000000-M	SP	****MM RC PIPE CULVERTS, CLASS IV (1500MM)	79.2 M		
0038	0448200000-M	SP	375MM RC PIPE CULVERTS, CLASS IV	1,027.2 M		
0039	0448300000-M	SP	450MM RC PIPE CULVERTS, CLASS IV	462 M		
0040	0448400000-M	SP	600MM RC PIPE CULVERTS, CLASS IV	260.4 M		
0041	0448500000-M	SP	750MM RC PIPE CULVERTS, CLASS IV	45.6 M		
0042	0448600000-M	SP	900MM RC PIPE CULVERTS, CLASS IV	126 M		
0043	0974000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B (UNDER RR) (600MM, 12MM)	13.2 M		
0044	0986000000-M	SP	GENERIC PIPE ITEM 375MM DUCTILE IRON PIPE	135.6 M		
0045	0992000000-M	SP	GENERIC PIPE ITEM ENERGY DISSIPATOR BASIN	2 EA		
0046	0995000000-M	340	PIPE REMOVAL	869.6 M		
0047	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0048	1077000000-M	SP	#57 STONE	60 MTN		
0049	1110000000-M	510	STABILIZER AGGREGATE	500 MTN		
0050	1220000000-M	545	INCIDENTAL STONE BASE	2,000 MTN		
0051	1231000000-M	560	SHOULDER BORROW	9,230 M3		
0052	1275000000-M	600	PRIME COAT	15,531 L		
0053	1330000000-M	607	INCIDENTAL MILLING	980 M2		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 MTN		
0055	2000000000-N	806	RIGHT OF WAY MARKERS	225 EA		
0056	2022000000-M	SP	SUBDRAIN EXCAVATION	2,070 M3		
0057	2033000000-M	SP	SUBDRAIN FINE AGGREGATE	1,035 M3		
0058	2044000000-M	SP	150MM PERFORATED SUBDRAIN PIPE	2,500 M		
0059	2070000000-N	SP	SUBDRAIN PIPE OUTLETS	17 EA		
0060	2077000000-M	SP	150MM OUTLET PIPE (SUBDRAINS)	34 M		
0061	2143000000-M	818	BLOTTING SAND	10 MTN		
0062	2209000000-M	838	ENDWALLS	40.6 M3		
0063	2220000000-M	838	REINFORCED ENDWALLS	26.7 M3		
0064	2253000000-M	840	PIPE COLLARS	0.29 M3		
0065	2264000000-M	840	PIPE PLUGS	0.22 M3		
0066	2275000000-M	SP	FLOWABLE FILL	23 M3		
0067	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	195 EA		
0068	2297000000-M	840	MASONRY DRAINAGE STRUCTURES	3.1 M3		
0069	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	15.97 M		
0070	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
0071	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	10 EA		
0072	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	10 EA		
0073	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	81 EA		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	16 EA		
0075	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	10 EA		
0076	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	6 EA		
0077	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	32 EA		
0078	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	25 EA		
0079	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0080	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	3 EA		
0081	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 450MM)	350 M		
0082	2549000000-M	846	750MM CONCRETE CURB & GUTTER	3,860 M		
0083	2556000000-M	846	SHOULDER BERM GUTTER	521 M		
0084	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	70 M		
0085	2612000000-M	848	150MM CONCRETE DRIVEWAY	1,000 M2		
0086	2619000000-M	850	100MM CONCRETE PAVED DITCH	50 M2		
0087	2647000000-M	852	125MM MONOLITHIC CONCRETE IS- LANDS (SURFACE MOUNTED)	1,760 M2		
0088	3030000000-M	862	STEEL BM GUARDRAIL	1,824.99 M		
0089	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	19.05 M		
0090	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	13 EA		
0092	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	19 EA		
0093	3380000000-M	862	TEMPORARY STEEL BM GUARDRAIL	140.97 M		
0094	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FABRIC	11,330 M		
0095	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	2,310 EA		
0096	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	650 EA		
0097	3533000000-M	866	CHAIN LINK FENCE, ****MM FABRIC (1800MM)	49 M		
0098	3539000000-M	866	METAL LINE POSTS FOR ****MM CHAIN LINK FENCE (1800MM)	14 EA		
0099	3557000000-M	866	ADDITIONAL BARBED WIRE	175 M		
0100	3628000000-M	876	RIP RAP, CLASS I	38 MTN		
0101	3635000000-M	876	RIP RAP, CLASS II	425 MTN		
0102	3649000000-M	876	RIP RAP, CLASS B	1,454 MTN		
0103	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	13,385 M2		
0104	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	7 EA		
0105	4054000000-M	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 M3		
0106	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	250 KG		
0107	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANNEL	919 M		
0108	4096000000-N	904	SIGN ERECTION, TYPE D	8 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4102000000-N	904	SIGN ERECTION, TYPE E	117 EA		
0110	4108000000-N	904	SIGN ERECTION, TYPE F	37 EA		
0111	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	2 EA		
0112	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	3 EA		
0113	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	9 EA		
0114	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	101 EA		
0115	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	7 EA		
0116	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	314 M2		
0117	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	122 M2		
0118	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	91 M2		
0119	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0120	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0121	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	150 DAY		
0122	4430000000-N	1130	DRUMS	469 EA		
0123	4445000000-M	1145	BARRICADES (TYPE III)	264 M		
0124	4450000000-N	1150	FLAGGER	4,800 HR		
0125	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	9 EA		
0126	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	3 EA		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	4480000000-N	1165	TMIA	3 EA		
0128	4485000000-M	1170	PORTABLE CONCRETE BARRIER	143 M		
0129	4490000000-M	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	594 M		
0130	4505000000-M	1170	RESET PORTABLE CONCRETE BAR- RIER (ANCHORED)	110 M		
0131	4516000000-N	1180	SKINNY DRUM	100 EA		
0132	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	881 EA		
0133	4705000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (400MM, 3.1MM)	79 M		
0134	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	328 M		
0135	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	12 EA		
0136	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	74,089 M		
0137	4830000000-M	1205	PAINT PAVEMENT MARKING LINES (400MM)	62 M		
0138	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	392 M		
0139	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	10 EA		
0140	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	82 EA		
0141	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	5 EA		
0142	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,491 EA		
0143	4915000000-M	1264	2.1M U-CHANNEL POSTS	8 EA		
0144	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	8 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	5325600000-M	1510	150MM WATER LINE	163	M	
0146	5325800000-M	1510	200MM WATER LINE	465	M	
0147	5326200000-M	1510	300MM WATER LINE	275	M	
0148	5540000000-M	1515	150MM VALVE	7	EA	
0149	5546000000-M	1515	200MM VALVE	11	EA	
0150	5558000000-M	1515	300MM VALVE	3	EA	
0151	5572200000-M	1515	300MM TAPPING VALVE	1	EA	
0152	5648000000-N	1515	RELOCATE WATER METER	23	EA	
0153	5649000000-N	1515	RECONNECT WATER METER	1	EA	
0154	5672000000-N	1515	RELOCATE FIRE HYDRANT	4	EA	
0155	5691200000-M	1520	150MM SANITARY GRAVITY SEWER	12	M	
0156	5691300000-M	1520	200MM SANITARY GRAVITY SEWER	333	M	
0157	5691400000-M	1520	250MM SANITARY GRAVITY SEWER	67	M	
0158	5691600000-M	1520	400MM SANITARY GRAVITY SEWER	75.8	M	
0159	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	6	EA	
0160	5775000000-M	1525	1200MM DIA UTILITY MANHOLE	5	EA	
0161	5776000000-M	1525	1500MM DIA UTILITY MANHOLE	5	EA	
0162	5781000000-M	1525	UTILITY MANHOLE WALL, 1200MM DIA	7.6	M	
0163	5782000000-M	1525	UTILITY MANHOLE WALL, 1500MM DIA	18.6	M	
0164	5798000000-M	1530	ABANDON ***MM UTILITY PIPE (375MM)	71	M	

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0165	5801000000-M	1530	ABANDON 200MM UTILITY PIPE	406 M		
0166	5802000000-M	1530	ABANDON 250MM UTILITY PIPE	29 M		
0167	5804000000-M	1530	ABANDON 300MM UTILITY PIPE	146 M		
0168	5816000000-N	1530	ABANDON UTILITY MANHOLE	2 EA		
0169	5836000000-M	1540	600MM ENCASEMENT PIPE	12 M		
0170	5836200000-M	1540	750MM ENCASEMENT PIPE	16 M		
0171	5872200000-M	1550	TRENCHLESS INSTALLATION OF 600MM IN SOIL	6 M		
0172	5872210000-M	1550	TRENCHLESS INSTALLATION OF 600MM NOT IN SOIL	6 M		
0173	5872300000-M	1550	TRENCHLESS INSTALLATION OF 750MM IN SOIL	8 M		
0174	5872310000-M	1550	TRENCHLESS INSTALLATION OF 750MM NOT IN SOIL	8 M		
0175	6000000000-M	1605	TEMPORARY SILT FENCE	14,000 M		
0176	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	12,500 MTN		
0177	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	7,500 MTN		
0178	6012000000-M	1610	SEDIMENT CONTROL STONE	6,250 MTN		
0179	6015000000-M	1615	TEMPORARY MULCHING	60 HA		
0180	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	2,425 KG		
0181	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	20.25 MTN		
0182	6024000000-M	1622	TEMPORARY SLOPE DRAINS	1,500 M		
0183	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	67 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0184	6029000000-M	SP	SAFETY FENCE	50 M		
0185	6030000000-M	1630	SILT EXCAVATION	42,500 M3		
0186	6036000000-M	1631	MATTING FOR EROSION CONTROL	180,000 M2		
0187	6037000000-M	SP	COIR FIBER MAT	1,100 M2		
0188	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	3,500 M2		
0189	6042000000-M	1632	6.4MM HARDWARE CLOTH	3,250 M		
0190	6046000000-M	SP	TEMPORARY PIPE FOR STREAM CROSSING	50 M		
0191	6069000000-M	1638	STILLING BASINS	40 M3		
0192	6071012000-M	SP	COIR FIBER WATTLE	2,100 M		
0193	6071020000-M	SP	POLYACRYLAMIDE (PAM)	2,200 KG		
0194	6071030000-M	SP	COIR FIBER BAFFLE	4,000 M		
0195	6071050000-M	SP	***MM SKIMMER (38MM)	86 EA		
0196	6084000000-M	1660	SEEDING & MULCHING	40 HA		
0197	6087000000-M	1660	MOWING	20 HA		
0198	6090000000-M	1661	SEED FOR REPAIR SEEDING	1,200 KG		
0199	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	4 MTN		
0200	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	1,000 KG		
0201	6108000000-M	1665	FERTILIZER TOPDRESSING	59 MTN		
0202	6111000000-M	SP	IMPERVIOUS DIKE	275 M		
0203	6114500000-N	SP	SPECIALIZED HAND MOWING	55 MHR		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0204	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	150 EA		
0205	6120000000-M	SP	CULVERT DIVERSION CHANNEL	140 M3		
0206	6123000000-M	1670	REFORESTATION	4 HA		
0207	6126000000-M	SP	STREAMBANK REFORESTATION	0.1 HA		
0208	7060000000-M	1705	SIGNAL CABLE	1,750 M		
0209	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	30 EA		
0210	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	7 EA		
0211	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	6 EA		
0212	7264000000-M	1710	MESSENGER CABLE (9.52MM)	550 M		
0213	7288000000-M	1715	PAVED TRENCHING (***** (1, 50MM)	20 M		
0214	7300000000-M	1715	UNPAVED TRENCHING (***** (1, 50MM)	550 M		
0215	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	12 EA		
0216	7360000000-N	1720	WOOD POLE	4 EA		
0217	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0218	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	3 EA		
0219	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	14 EA		
0220	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	1,540 M		
0221	7456000000-M	1726	LEAD-IN CABLE (***** (14-2)	4,330 M		
0222	7576000000-N	SP	METAL STRAIN SIGNAL POLE	8 EA		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0223	7613000000-N	SP	SOIL TEST	8 EA		
0224	7614100000-M	SP	DRILLED PIER FOUNDATION	50 M3		
0225	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0226	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0227	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0228	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	15 EA		
0229	7990000000-M	SP	GENERIC SIGNAL ITEM UNPAVED TRENCHING FOR TEMPOR- ARY LEAD IN	150 M		
<p>***** BEGIN SCHEDULE AA ***** ***** (2 ALTERNATES) *****</p>						
0230	0022000000-M	225	UNCLASSIFIED EXCAVATION	405,000 M3		
AA1						
0231	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	39,670 M2		
AA1						
0232	1066000000-M	501	LIME FOR LIME TREATED SOIL	440 MTN		
AA1						
0233	1121000000-M	520	AGGREGATE BASE COURSE	4,545 MTN		
AA1						
0234	1176000000-M	542	SOIL CEMENT BASE	39,670 M2		
AA1						
0235	1187000000-M	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	1,191 MTN		
AA1						
0236	1198000000-M	SP	AGGREGATE FOR SOIL CEMENT BASE	600 MTN		
AA1						
0237	1209000000-M	543	ASPHALT CURING SEAL	53,960 L		
AA1						
0238	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	47,510 MTN		
AA1						
0239	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	31,580 MTN		
AA1						

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0240 AA1	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	32,000 MTN		
0241 AA1	1575000000-M	SP	ASPHALT BINDER FOR PLANT MIX	5,530 MTN		
0242 AA1	2099000000-M	816	SHOULDER DRAIN	5,120 M		
0243 AA1	2110000000-M	816	100MM SHOULDER DRAIN PIPE	5,120 M		
0244 AA1	2121000000-M	816	100MM OUTLET PIPE (SHOULDER DRAINS)	210 M		
0245 AA1	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	30 EA		
0246 AA1	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	25,786 M		
0247 AA1	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	14,060 M		
0248 AA1	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	2,209 M		
0249 AA1	4700000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (300MM, 2.3MM)	703 M		
0250 AA1	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	162 EA		
0251 AA1	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (100MM) (IV)	644 M		
*** OR ***						
0252 AA2	0022000000-M	225	UNCLASSIFIED EXCAVATION	400,000 M3		
0253 AA2	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	48,120 M2		
0254 AA2	1066000000-M	501	LIME FOR LIME TREATED SOIL	530 MTN		
0255 AA2	1121000000-M	520	AGGREGATE BASE COURSE	5,017 MTN		
0256 AA2	1176000000-M	542	SOIL CEMENT BASE	48,120 M2		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0257 AA2	1187000000-M	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	1,444 MTN		
0258 AA2	1198000000-M	SP	AGGREGATE FOR SOIL CEMENT BASE	730 MTN		
0259 AA2	1209000000-M	543	ASPHALT CURING SEAL	65,450 L		
0260 AA2	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	17,700 MTN		
0261 AA2	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	11,800 MTN		
0262 AA2	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,670 MTN		
0263 AA2	1525000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6,790 MTN		
0264 AA2	1575000000-M	SP	ASPHALT BINDER FOR PLANT MIX	2,980 MTN		
0265 AA2	1682000000-M	652	PERMEABLE ASPHALT DRAINAGE COURSE, TYPE P-57	14,030 MTN		
0266 AA2	1847000000-M	710	****MM PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (200MM)	80,945 M2		
0267 AA2	1902000000-N	710	SURFACE TESTING CONCRETE PAVE- MENT	Lump Sum	L.S.	
0268 AA2	1913000000-M	720	CONCRETE SHOULDERS ADJACENT TO ****MM PAVEMENT (200MM)	14,615 M2		
0269 AA2	1914000000-M	SP	CONCRETE SHOULDERS ADJACENT TO ****MM PAVEMENT (WITH DOWELS) (200MM)	5,570 M2		
0270 AA2	1924000000-N	725	FIELD LABORATORY RENTAL, PORT CEM CONC PAVEMENT	Lump Sum	L.S.	
0271 AA2	2099000000-M	816	SHOULDER DRAIN	8,820 M		
0272 AA2	2110000000-M	816	100MM SHOULDER DRAIN PIPE	8,820 M		

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0273 AA2	2121000000-M	816	100MM OUTLET PIPE (SHOULDER DRAINS)	300 M		
0274 AA2	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	50 EA		
0275 AA2	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	7,131 M		
0276 AA2	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	11,591 M		
0277 AA2	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	463 M		
0278 AA2	4700000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (300MM, 2.3MM)	239 M		
0279 AA2	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	115 EA		
0280 AA2	4780000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (200MM) (II)	39 M		
0281 AA2	4785000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (300MM) (II)	464 M		
0282 AA2	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (II)	47 EA		
0283 AA2	4847000000-M	1205	POLYUREA PAVEMENT MARKING LINES (100MM, *****) (HIGHLY REFLECTIVE ELEMENTS)	21,124 M		
0284 AA2	4847110000-M	1205	POLYUREA PAVEMENT MARKING LINES (200MM, *****) (HIGHLY REFLECTIVE ELEMENTS)	1,707 M		
***** END SCHEDULE AA *****						
CULVERT ITEMS						
0285	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+43.400-L-)	Lump Sum	L.S.	

County: Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0286	8126000000-N	414	CULVERT EXCAVATION, STA ***** (20+86.000-L-)	Lump Sum	L.S.	
0287	8126000000-N	414	CULVERT EXCAVATION, STA ***** (35+56.000-L-)	Lump Sum	L.S.	
0288	8133000000-M	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	1,016 MTN		
0289	8196000000-M	420	CLASS A CONCRETE (CULVERT)	1,016.2 M3		
0290	8245000000-M	425	REINFORCING STEEL (CULVERT)	100,768 KG		

1346/Mar15/Q2203905.04/D1056549642000/E290

Total Amount Of Bid For Entire Project :

Contract No. **C202960**

County (ies): **Person**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General