

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	118 CY		
0003	0241000000-E	SP	GENERIC GRADING ITEM REMOVAL OF EXISTING ISLAND	8 SY		
0004	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER GRADING	1.18 SMI		
0005	1220000000-E	545	INCIDENTAL STONE BASE	60 TON		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	13,046 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4-1/2")	118,358 SY		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	20,880 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,195 TON		
0010	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,451 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,690 TON		
0012	1702000000-E	657	SEALING EXISTING PAVEMENT CRACKS & JOINTS	1,125 LB		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	561 TON		
0014	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	205 SY		
0015	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	3 EA		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	38 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	17 EA		
0018	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	76 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4102000000-N	904	SIGN ERECTION, TYPE E	7 EA		
0020	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0021	4510000000-N	SP	LAW ENFORCEMENT	125 HR		
0022	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,210 LF		
0023	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,370 LF		
0024	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,349 LF		
0025	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	180 LF		
0026	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,202 LF		
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	44 EA		
0028	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	178 EA		
0029	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	895 LF		
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,580 LF		
0031	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,529 LF		
0032	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,202 LF		
0033	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	44 EA		
0034	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	178 EA		
0035	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,395 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2 EA		
0037	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,275 EA		
0038	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0039	6000000000-E	1605	TEMPORARY SILT FENCE	84 LF		
0040	6071010000-E	SP	WATTLE	220 LF		
0041	6084000000-E	1660	SEEDING & MULCHING	0.85 ACR		
0042	7060000000-E	1705	SIGNAL CABLE	400 LF		
0043	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	1 EA		
0044	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0045	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,990 LF		
0046	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	6,150 LF		
0047	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		

1040/Mar13/Q257450.03/D185903110000/E47

Total Amount Of Bid For Entire Project :

Contract No. C203327

County (ies): Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General