

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	76,560 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (65+92.50-L-)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	13,960 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,000 CY		
0009	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	6,000 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	9,500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	200 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	620 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	160 LF		
0014	0335300000-E	305	18" DRAINAGE PIPE	680 LF		
0015	0335400000-E	305	24" DRAINAGE PIPE	324 LF		
0016	0335700000-E	305	42" DRAINAGE PIPE	424 LF		
0017	0335800000-E	305	48" DRAINAGE PIPE	84 LF		
0018	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (18")	3 EA		
0020	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	136 LF		
0021	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	36 LF		
0022	0995000000-E	340	PIPE REMOVAL	20 LF		
0023	1099500000-E	505	SHALLOW UNDERCUT	750 CY		
0024	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	2,200 TON		
0025	1121000000-E	520	AGGREGATE BASE COURSE	6,700 TON		
0026	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0027	1275000000-E	600	PRIME COAT	4,120 GAL		
0028	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,340 TON		
0029	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,730 TON		
0030	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	225 TON		
0031	2000000000-N	806	RIGHT OF WAY MARKERS	39 EA		
0032	2209000000-E	838	ENDWALLS	20 CY		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	12 EA		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
0038	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0039	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,760 LF		
0040	2556000000-E	846	SHOULDER BERM GUTTER	160 LF		
0041	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0042	2591000000-E	848	4" CONCRETE SIDEWALK	980 SY		
0043	3030000000-E	862	STEEL BM GUARDRAIL	2,487.5 LF		
0044	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	112.5 LF		
0045	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	6 EA		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0048	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0049	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	17 EA		
0050	3628000000-E	876	RIP RAP, CLASS I	320 TON		
0051	3635000000-E	876	RIP RAP, CLASS II	230 TON		
0052	3649000000-E	876	RIP RAP, CLASS B	1,440 TON		
0053	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	8,225 SY		
0054	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	38.5 SF		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	63		
				LF		
0056	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	6		
				EA		
0057	4102000000-N	904	SIGN ERECTION, TYPE E	11		
				EA		
0058	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224		
				SF		
0059	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96		
				SF		
0060	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	80		
				SF		
0061	4430000000-N	1130	DRUMS	20		
				EA		
0062	4435000000-N	1135	CONES	40		
				EA		
0063	4445000000-E	1145	BARRICADES (TYPE III)	120		
				LF		
0064	4455000000-N	1150	FLAGGER	60		
				DAY		
0065	4516000000-N	1180	SKINNY DRUM	30		
				EA		
0066	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	75		
				EA		
0067	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	860		
				LF		
0068	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	79,546		
				LF		
0069	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	54		
				LF		
0070	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	430		
				LF		
0071	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	90		
				EA		
0072	5672000000-N	1515	RELOCATE FIRE HYDRANT	1		
				EA		
0073	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	1		
				EA		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6000000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
0075	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	655 TON		
0076	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,450 TON		
0077	6012000000-E	1610	SEDIMENT CONTROL STONE	800 TON		
0078	6015000000-E	1615	TEMPORARY MULCHING	40 ACR		
0079	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,200 LB		
0080	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6 TON		
0081	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,000 LF		
0082	6029000000-E	SP	SAFETY FENCE	200 LF		
0083	6030000000-E	1630	SILT EXCAVATION	5,100 CY		
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	27,490 SY		
0085	6037000000-E	SP	COIR FIBER MAT	200 SY		
0086	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,290 SY		
0087	6042000000-E	1632	1/4" HARDWARE CLOTH	675 LF		
0088	6046000000-E	1636	TEMPORARY PIPE FOR STREAM CROSSING	100 LF		
0089	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
0090	6071010000-E	SP	WATTLE	2,000 LF		
0091	6071020000-E	SP	POLYACRYLAMIDE (PAM)	355 LB		
0092	6071030000-E	1640	COIR FIBER BAFFLE	1,100 LF		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6071050000-E	SP	*** SKIMMER (1-1/2")	10 EA		
0094	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	30 ACR		
0096	6087000000-E	1660	MOWING	20 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	400 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	800 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	24 TON		
0101	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
STRUCTURE ITEMS						
0103	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	18.75 LF		
0104	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	30 LF		
0105	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	15.1 LF		
0106	8115000000-N	411	CSL TESTING	1 EA		
0107	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,358 SF		
0108	8161000000-E	420	GROOVING BRIDGE FLOORS	7,170 SF		
0109	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	158.9 CY		

County : Cabarrus, Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (65+90.50 -L-)	Lump Sum	L.S.	
0111	8217000000-E	425	REINFORCING STEEL (BRIDGE)	26,482 LB		
0112	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,287 LB		
0113	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	907.76 LF		
0114	8364000000-E	450	HP12X53 STEEL PILES	418 LF		
0115	8391000000-N	450	STEEL PILE POINTS	19 EA		
0116	8482000000-E	460	THREE BAR METAL RAIL	350.95 LF		
0117	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,462 TON		
0118	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,624 SY		
0119	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
1428/Apr08/Q324851.96/D489825540000/E119			Total Amount Of Bid For Entire Project :			

1-17-12
Z-140

Contract No. **C203209**

County (ies): **Cabarrus/Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)