

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	12 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	42,600 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (397+87.00 LEFT LANE)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (397+87.00 RIGHT LANE)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (660+21.00 LEFT LANE)	Lump Sum	L.S.	
0010	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (660+21.00 RIGHT LANE)	Lump Sum	L.S.	
0011	0036000000-E	225	UNDERCUT EXCAVATION	62,100 CY		
0012	0106000000-E	230	BORROW EXCAVATION	983,600 CY		
0013	0134000000-E	240	DRAINAGE DITCH EXCAVATION	18,700 CY		
0014	0141000000-E	240	BERM DITCH CONSTRUCTION	850 LF		
0015	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	41,500 SY		
0016	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	16,590 SY		
0017	0192000000-N	260	PROOF ROLLING	70 HR		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	65,500 CY		
0019	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	67,600 SY		
0020	0199000000-E	SP	TEMPORARY SHORING	2,473.3 SF		
0021	0220000000-E	SP	ROCK EMBANKMENTS	1,800 TON		
0022	0222000000-E	SP	GEOTEXTILE FOR ROCK EMBANK- MENTS	1,050 SY		
0023	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	2,530 TON		
0024	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	7,960 SY		
0025	0342000000-E	310	*** SIDE DRAIN PIPE (30")	72 LF		
0026	0343000000-E	310	15" SIDE DRAIN PIPE	976 LF		
0027	0344000000-E	310	18" SIDE DRAIN PIPE	651 LF		
0028	0345000000-E	310	24" SIDE DRAIN PIPE	820 LF		
0029	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	4 EA		
0030	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (18")	3 EA		
0031	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,836 LF		
0032	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,472 LF		
0033	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,996 LF		
0034	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,124 LF		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	204	LF	
0036	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	600	LF	
0037	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	796	LF	
0038	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	344	LF	
0039	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	176	LF	
0040	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	196	LF	
0041	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	4,204	LF	
0042	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	1,184	LF	
0043	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	564	LF	
0044	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	1,160	LF	
0045	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	192	LF	
0046	0453000000-E	310	*** PIPE END SECTION (15")	4	EA	
0047	0453000000-E	310	*** PIPE END SECTION (18")	5	EA	
0048	0453000000-E	310	*** PIPE END SECTION (24")	2	EA	
0049	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	292	LF	
0050	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	10	EA	
0051	0995000000-E	340	PIPE REMOVAL	2,700	LF	

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0053	1077000000-E	SP	#57 STONE	980 TON		
0054	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0055	1115000000-E	SP	GEOTEXTILE FOR PAVEMENT STA- BILIZATION	12,900 SY		
0056	1121000000-E	520	AGGREGATE BASE COURSE	178,910 TON		
0057	1220000000-E	545	INCIDENTAL STONE BASE	6,476 TON		
0058	1275000000-E	600	PRIME COAT	123,000 GAL		
0059	1330000000-E	607	INCIDENTAL MILLING	780 SY		
0060	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,530 TON		
0061	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	7,000 TON		
0062	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	54,290 TON		
0063	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	54,000 TON		
0064	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,080 TON		
0065	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	6,310 TON		
0066	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	1,300 TON		
0067	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	500 TON		
0068	2020000000-N	806	CONTROL OF ACCESS MARKERS	15 EA		
0069	2022000000-E	815	SUBDRAIN EXCAVATION	1,142.4 CY		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	3,400 SY		
0071	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	571.2 CY		
0072	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	3,400 LF		
0073	2070000000-N	815	SUBDRAIN PIPE OUTLET	7 EA		
0074	2077000000-E	815	6" OUTLET PIPE	42 LF		
0075	2209000000-E	838	ENDWALLS	26 CY		
0076	2220000000-E	838	REINFORCED ENDWALLS	14 CY		
0077	2253000000-E	840	PIPE COLLARS	0.447 CY		
0078	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	151 EA		
0079	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	7 CY		
0080	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	161 LF		
0081	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0082	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	14 EA		
0083	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	108 EA		
0084	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	28 EA		
0085	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	13 EA		
0086	2556000000-E	846	SHOULDER BERM GUTTER	7,760 LF		
0087	2612000000-E	848	6" CONCRETE DRIVEWAY	110 SY		
0088	2619000000-E	850	4" CONCRETE PAVED DITCH	30 SY		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	5,880 SY		
0090	3030000000-E	862	STEEL BM GUARDRAIL	10,450 LF		
0091	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0092	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0093	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0094	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	8 EA		
0095	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	22 EA		
0096	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	8 EA		
0097	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	16 EA		
0098	3360000000-E	863	REMOVE EXISTING GUARDRAIL	825 LF		
0099	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	2,150 LF		
0100	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
0101	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	65,980 LF		
0102	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	4,112 EA		
0103	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	1,115 EA		
0104	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	1,690 LF		
0105	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	150 EA		
0106	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	8 EA		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	3557000000-E	866	ADDITIONAL BARBED WIRE	6,800 LF		
0108	3565000000-E	866	DOUBLE GATES, **** HIGH, *** WIDE, *** OPENING (47" HIGH, 10' WIDE, 20' OPENING)	3 EA		
0109	3565000000-E	866	DOUBLE GATES, **** HIGH, *** WIDE, *** OPENING (47" HIGH, 6' WIDE, 12' OPENING)	1 EA		
0110	3565000000-E	866	DOUBLE GATES, **** HIGH, *** WIDE, *** OPENING (47" HIGH, 8' WIDE, 16' OPENING)	2 EA		
0111	3578000000-N	SP	GENERIC FENCING ITEM METAL GATE POSTS FOR 47" WOVEN WIRE FENCE, DOUBLE GATE	12 EA		
0112	3595000000-E	869	RELAPPING GUARDRAIL	725 LF		
0113	3628000000-E	876	RIP RAP, CLASS I	690 TON		
0114	3649000000-E	876	RIP RAP, CLASS B	1,700 TON		
0115	3651000000-E	SP	BOULDERS	20 TON		
0116	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	10,500 SY		
0117	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0118	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4,292 LF		
0119	4096000000-N	904	SIGN ERECTION, TYPE D	20 EA		
0120	4102000000-N	904	SIGN ERECTION, TYPE E	163 EA		
0121	4108000000-N	904	SIGN ERECTION, TYPE F	57 EA		
0122	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	51 EA		
0123	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	3,006 SF		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	352 SF		
0125	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	421 SF		
0126	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0127	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0128	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	240 DAY		
0129	4430000000-N	1130	DRUMS	850 EA		
0130	4435000000-N	1135	CONES	100 EA		
0131	4445000000-E	1145	BARRICADES (TYPE III)	1,500 LF		
0132	4455000000-N	1150	FLAGGER	520 DAY		
0133	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0134	4480000000-N	1165	TMA	2 EA		
0135	4485000000-E	1170	PORTABLE CONCRETE BARRIER	480 LF		
0136	4510000000-N	SP	LAW ENFORCEMENT	48 HR		
0137	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,136 EA		
0138	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	167,860 LF		
0139	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	40,671 LF		
0140	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	13,511 LF		
0141	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	311 LF		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	782 LF		
0143	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0144	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	248 EA		
0145	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	9,244 LF		
0146	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	498,132 LF		
0147	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	352 LF		
0148	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	94 LF		
0149	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,574 LF		
0150	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8 EA		
0151	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	40 EA		
0152	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	12,252 LF		
0153	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	68 LF		
0154	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,745 EA		
0155	5325300000-E	1510	3" WATER LINE	112 LF		
0156	5325400000-E	1510	4" WATER LINE	223 LF		
0157	5325600000-E	1510	6" WATER LINE	2,438 LF		
0158	5325800000-E	1510	8" WATER LINE	17,050 LF		
0159	5326000000-E	1510	10" WATER LINE	4,400 LF		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160	5540000000-E	1515	6" VALVE	6 EA		
0161	5546000000-E	1515	8" VALVE	25 EA		
0162	5552000000-E	1515	10" VALVE	5 EA		
0163	5643100000-E	1515	3/4" WATER METER	11 EA		
0164	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0165	5649000000-N	1515	RECONNECT WATER METER	2 EA		
0166	5666000000-E	1515	FIRE HYDRANT	7 EA		
0167	5801000000-E	1530	ABANDON 8" UTILITY PIPE	17,917 LF		
0168	5802000000-E	1530	ABANDON 10" UTILITY PIPE	4,448 LF		
0169	5815000000-N	1530	REMOVE WATER METER	13 EA		
0170	5815500000-N	1530	REMOVE FIRE HYDRANT	5 EA		
0171	5835600000-E	1540	12" ENCASEMENT PIPE	399 LF		
0172	5835700000-E	1540	16" ENCASEMENT PIPE	898 LF		
0173	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	1,822 LF		
0174	5912000000-N	SP	GENERIC UTILITY ITEM RELOCATION OF WATER BOOSTER PUMP STATION	Lump Sum	L.S.	
0175	6000000000-E	1605	TEMPORARY SILT FENCE	130,000 LF		
0176	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	7,700 TON		
0177	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	22,125 TON		
0178	6012000000-E	1610	SEDIMENT CONTROL STONE	13,400 TON		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0179	6015000000-E	1615	TEMPORARY MULCHING	200 ACR		
0180	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	7,500 LB		
0181	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	31.5 TON		
0182	6024000000-E	1622	TEMPORARY SLOPE DRAINS	10,100 LF		
0183	6029000000-E	SP	SAFETY FENCE	11,600 LF		
0184	6030000000-E	1630	SILT EXCAVATION	49,100 CY		
0185	6036000000-E	1631	MATTING FOR EROSION CONTROL	140,000 SY		
0186	6037000000-E	SP	COIR FIBER MAT	12,000 SY		
0187	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,200 SY		
0188	6042000000-E	1632	1/4" HARDWARE CLOTH	4,350 LF		
0189	6045000000-E	SP	*** TEMPORARY PIPE (18")	120 LF		
0190	6046000000-E	1636	TEMPORARY PIPE FOR STREAM CROSSING	40 LF		
0191	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	550 SY		
0192	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0193	6071012000-E	SP	COIR FIBER WATTLE	23,100 LF		
0194	6071020000-E	SP	POLYACRYLAMIDE (PAM)	17,000 LB		
0195	6071030000-E	1640	COIR FIBER BAFFLE	21,450 LF		
0196	6071050000-E	SP	*** SKIMMER (1-1/2")	60 EA		
0197	6071050000-E	SP	*** SKIMMER (2")	5 EA		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0198	6071050000-E	SP	*** SKIMMER (2-1/2")	2 EA		
0199	6084000000-E	1660	SEEDING & MULCHING	200 ACR		
0200	6087000000-E	1660	MOWING	100 ACR		
0201	6090000000-E	1661	SEED FOR REPAIR SEEDING	2,950 LB		
0202	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	11 TON		
0203	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	5,950 LB		
0204	6108000000-E	1665	FERTILIZER TOPDRESSING	179 TON		
0205	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0206	6114500000-N	1667	SPECIALIZED HAND MOWING	100 MHR		
0207	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	200 EA		
0208	6120000000-E	SP	CULVERT DIVERSION CHANNEL	180 CY		
0209	6123000000-E	1670	REFORESTATION	9 ACR		
0210	6126000000-E	SP	STREAMBANK REFORESTATION	0.7 ACR		
0246	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
CULVERT ITEMS						
0211	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (713+35.00-L-)	Lump Sum	L.S.	
0212	8126000000-N	414	CULVERT EXCAVATION, STA ***** (713+35.00-L-)	Lump Sum	L.S.	
0213	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	245 TON		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0214	8196000000-E	420	CLASS A CONCRETE (CULVERT)	284.5 CY		
0215	8245000000-E	425	REINFORCING STEEL (CULVERT)	34,438 LB		
STRUCTURE ITEMS						
0216	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (397+87.00-LREV-LTLN)	Lump Sum	L.S.	
0217	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (397+87.00-LREV-RTLN)	Lump Sum	L.S.	
0218	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (660+21.00-L-LTLN)	Lump Sum	L.S.	
0219	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (660+21.00-L-RTLN)	Lump Sum	L.S.	
0220	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (660+21.00-L-LTLN)	Lump Sum	L.S.	
0221	8112730000-N	450	PDA TESTING	6 EA		
0222	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (397+87.00-LREV-LTLN)	Lump Sum	L.S.	
0223	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (397+87.00-LREV-RTLN)	Lump Sum	L.S.	
0224	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (660+21.00-L-LTLN)	Lump Sum	L.S.	
0225	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	108,356 SF		
0226	8161000000-E	420	GROOVING BRIDGE FLOORS	97,012 SF		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0227	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	798.8 CY		
0228	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (397+87.00-LREV-LTLN)	Lump Sum	L.S.	
0229	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (397+87.00-LREV-RTLN)	Lump Sum	L.S.	
0230	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (660+21.00-L-LTLN)	Lump Sum	L.S.	
0231	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (660+21.00-L-RTLN)	Lump Sum	L.S.	
0232	8217000000-E	425	REINFORCING STEEL (BRIDGE)	119,855 LB		
0233	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,255.66 LF		
0234	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	9,673.34 LF		
0235	8364000000-E	450	HP12X53 STEEL PILES	3,270 LF		
0236	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	14,990 LF		
0237	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24X0.50)	300 LF		
0238	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	1,125 LF		
0239	8392000000-N	450	PIPE PILE PLATES	19 EA		
0240	8393000000-N	450	PILE REDRIVES	131 EA		
0241	8503000000-E	460	CONCRETE BARRIER RAIL	5,594.7 LF		
0242	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,528 TON		
0243	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	1,697 SY		

County : Cumberland, Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0244	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0245	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0943/Apr30/Q3614775.047/D971376942000/E246			Total Amount Of Bid For Entire Project :			

Contract No. C203087

County (ies): Cumberland - Sampson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General