



PROJECT SPECIAL PROVISIONS
Utility Construction

All proposed utility construction shall meet the applicable requirements of the NC Department of Transportation’s “Standard Specifications for Roads and Structures” dated January 2012.

Division 15 of the Standard Specifications is revised as follows:

Page 15-1, Insert New Paragraph After Paragraph 2 of Section 1500-2

The water and sewer lines along this project belong to the City of Hendersonville. Below is listed the utility owner with contact information along this project. Any work on these lines must be coordinated through the Engineer and the utility owner before commencement of any work.

City of Hendersonville – Mr. Dennis Frady – (828) 697-3073

Page 15-2, Revise Last Sentence of Paragraph 3 of Section 1500-7

Provide the Utility Owner and Engineer with 2 copies of surveyed As-Builts of both the water and sewer systems constructed.

Page 15-3, Insert New Paragraph After Paragraph 1 of Section 1500-9

Contractor shall notify the City of Hendersonville 7 business days in advance of performing any tie-in work. Contractor shall notify all affected customers 24 hours in advance of service interruptions. Contractor shall notify all affected critical facilities (i.e. hospitals, schools, medical facilities, etc.) 72 hours or more in advance of service interruption.

Page 15-2, Revise The Second Sentence in Paragraph 2 of Section 1500-9

The maximum interruption time for the City of Hendersonville water service is four (4) hours. Any additional time needed shall be approved by the City and the Engineer prior to beginning work.

Division 10 of the Standard Specifications is revised as follows:

Page 10-57, Replace Paragraph 1 of Subsection A of Section 1034-4

All ductile iron pipe shall be Class 350 unless otherwise specified and shall be lined with cement mortar not less than 1/16 inch thick conforming to ANSI Specification A21.4.

Page 10-58, Replace Paragraph 1 of Section 1036-5

All ductile iron pipe shall be Class 350 unless otherwise specified and shall be lined with cement mortar not less than 1/16 inch thick conforming to ANSI Specification A21.4.

Compensation:

No direct payment will be made for utility construction work required by the preceding provisions, which are general requirements applying to utility construction, and all of the requirements stated will be considered incidental work, paid for at the contract unit prices of the various utility items included in the contract.

PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Duke Power Company
- B) Media Communications
- C) AT&T
- D) PSNC Energy

The conflicting facilities will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be performed by the Utility Owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications for Roads and Structures.

Utilities Requiring Adjustments:

A) Duke Power Company

- 1. See "Utilities By Others Plans" for utility conflicts.
- 2. All utility relocation work is scheduled to be completed by December 1, 2013.
- 3. Contact Mr. Bob Mabry – (828) 698-2055

B) Media Communications

- 1. All utility relocation work is scheduled to be completed by December 1, 2014.
- 2. Contact Mr. Chris McCall – (828) 692-3278

C) AT&T

- 1. See "Utilities By Others Plans" for utility conflicts.
- 2. All utility relocation work is scheduled to be completed by December 1, 2014.
- 3. Contact Mr. Scott Addington – (828) 258-7138

D) PSNC Energy

1. See "Utilities By Others Plans" for utility conflicts.
2. PSNC will be installing new lines at the following locations and will require the Contractor to clear to the right of way limits before installing. PSNC will require two (2) weeks notice and a total of sixty (60) days of construction time to complete the relocations listed below:
 - 8" Steel, -L- Sta. 65+00+/- to Sta. 106+00+/-
Sheets UO-6 to UO-9
3. The Contractor is to give PSNC a minimum of two (2) weeks to make any adjustments in the areas where the existing lines are to remain in place and adjustments are needed to avoid storm drainage, water, or sewer lines.
4. All other areas in which relocations/adjustments are warranted, the Contractor is to give a minimum one (1) week notice.
5. All other utility relocation work not listed above is to be completed by the Date of Availability.
6. Contact Mr. Kenneth Owenby – (828) 670-3527