

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	2,381 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	570 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	32.44 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	335 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	29,937 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	12,121 SY		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	8,351 TON		
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	25,005 TON		
0010	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	6,489 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,300 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	5,963 TON		
0013	1771000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #6M STONE	93,429 SY		
0014	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	56 EA		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	22 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	34 EA		
0017	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0018	4510000000-N	SP	LAW ENFORCEMENT	32 HR		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	164,300 LF		
0020	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	254,400 LF		
0021	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,932 LF		
0022	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,350 LF		
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,312 LF		
0024	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	42 EA		
0025	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	307 EA		
0026	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	85,900 LF		
0027	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	905 LF		
0028	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	196 LF		
0029	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,230 EA		
0030	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0031	6000000000-E	1605	TEMPORARY SILT FENCE	2,886 LF		
0032	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	387 TON		
0033	6012000000-E	1610	SEDIMENT CONTROL STONE	196 TON		
0034	6071010000-E	SP	WATTLE	580 LF		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		

1438/Apr09/Q705993.44/D120992130000/E35

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203331**

**County (ies):**    **Mecklenburg**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General