

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+69.91)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,700 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	2,700 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	2,800 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	719 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	50 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	540 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	56 LF		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	92 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	80 LF		
0015	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0016	0995000000-E	340	PIPE REMOVAL	55 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	140 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	15 TON		
0019	1330000000-E	607	INCIDENTAL MILLING	140 SY		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	620 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	390 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	590 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	81 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0026	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	1,000 SY		
0027	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	168 CY		
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0029	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
0030	2077000000-E	815	6" OUTLET PIPE	12 LF		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	187 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	350 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0038	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,287 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0040	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	462 SY		
0042	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0043	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	66 LF		
0044	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0045	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	7 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0049	4430000000-N	1130	DRUMS	45 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0051	4450000000-N	1150	FLAGGER	1,920 HR		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	60 EA		
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,050 LF		
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,050 LF		
0055	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	600 LF		
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,400 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	29 EA		
0058	5325600000-E	1510	6" WATER LINE	834 LF		
0059	5540000000-E	1515	6" VALVE	2 EA		
0060	5800000000-E	1530	ABANDON 6" UTILITY PIPE	760 LF		
0061	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	540 LF		
0062	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	60 LF		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	3,500 LF		
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	295 TON		
0065	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0066	6012000000-E	1610	SEDIMENT CONTROL STONE	235 TON		
0067	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0068	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0069	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0070	6024000000-E	1622	TEMPORARY SLOPE DRAINS	450 LF		
0071	6029000000-E	SP	SAFETY FENCE	1,300 LF		
0072	6030000000-E	1630	SILT EXCAVATION	310 CY		
0073	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0074	6037000000-E	SP	COIR FIBER MAT	545 SY		
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	765 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6071010000-E	SP	WATTLE	100 LF		
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0078	6071030000-E	1640	COIR FIBER BAFFLE	125 LF		
0079	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0081	6087000000-E	1660	MOWING	2 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0086	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0088	6129000000-E	1670	WETLAND REFORESTATION	0.27 ACR		
0089	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.27 ACR		
0090	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.27 ACR		

**STRUCTURE ITEMS**

0091	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+69.91-L-)	Lump Sum	L.S.	
0092	8112730000-N	450	PDA TESTING	1 EA		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,543 SF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	5,567 SF		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	107 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+69.91-L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,306 LB		
0098	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	726.53 LF		
0099	8364000000-E	450	HP12X53 STEEL PILES	875 LF		
0100	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	1,050 LF		
0101	8393000000-N	450	PILE REDRIVES	14 EA		
0102	8468000000-E	460	ONE BAR METAL RAIL	279.95 LF		
0103	8517000000-E	460	1'-**"X *****" CONCRETE PARA- PET (1'-2"X2'-6")	295.11 LF		
0104	8590000000-E	876	RIP RAP, CLASS ** (I)	310 TON		
0105	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	344 SY		
0106	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0107	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	

0830/May08/Q75856.15/D473219750000/E107

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203081**

**County (ies):**    **Martin**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General