



TEMPORARY SIGN COVERINGS

DESCRIPTION

The work covered by this special provision consists of the Contractor temporarily covering existing signs (Ground Mounted) as required in the plans or by the Engineer; that will need to be temporarily covered for the handling of traffic during the closure of Downing St.

CONSTRUCTION METHODS

Signs which are to be temporarily covered shall be covered in their entirety unless otherwise specified by the Traffic Control Plans or by the Engineer. Signs to be covered in their entirety shall be covered with exterior grade plywood or other material approved by the engineer. These coverings shall cover the entire face of the sign panel. Non-metal washers or other spacing devices shall be used to keep the plywood covering material from direct contact with the sign panel. Similar provisions shall be made for other approved covering materials. The covering material shall be installed in such a manner that the sign panel will not be defaced. The use of highly reflective covers of inappropriate color, such as, sheet metal covers or any other material that might be misleading to motorists shall not be permitted. No blacking out of any portion of the word message will be allowed. The covering material shall be maintained in a neat and workmanlike manner during its use.

Any damage to a sign by the temporary covering process shall be repaired by the contractor at no cost to the Department.

METHOD OF MEASUREMENT

The quantity of temporary sign coverings to be paid for will be 8 Type A signs and 1 Type D sign or the actual number of signs temporarily covered satisfactorily as approved by the engineer.

BASIS OF PAYMENT

The work covered in this special provision will be paid for at the contract unit price per each for "Temporary Sign Coverings (Type A & Type D)."

Such price and payment will be full compensation for drilling required holes, providing the necessary mounting hardware, providing covering material, covering the signs, and all other materials, labor, tools, and incidentals necessary to complete the work.

Payment will be made under:

- Temporary Sign Coverings Type "A" (Ground Mounted).....Each
- Temporary Sign Coverings Type "D" (Ground Mounted).....Each