

County : Avery, Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	3,988 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	1,035 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	39.88 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	70,828 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	19,488 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	2,654 SY		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,730 TON		
0009	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,794 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	14,276 TON		
0011	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	3,483 TON		
0012	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,909 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,800 TON		
0014	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	17 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	9 EA		
0017	4366000000-E	SP	GENERIC SIGNING ITEM WORK ZONE ADVANCE/GENERAL WARNING SIGNING	2,396.24 SF		
0018	4510000000-N	SP	LAW ENFORCEMENT	160 HR		

County : Avery, Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	899,812 LF		
0021	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,348 LF		
0022	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	874 LF		
0023	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	16 EA		
0024	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	86 EA		
0025	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,432 EA		
0026	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0027	6084000000-E	1660	SEEDING & MULCHING	15.15 ACR		
0028	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	100 LF		
0029	7288000000-E	1715	PAVED TRENCHING (***** (3, 2")	200 LF		
0030	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	100 LF		
0031	7300000000-E	1715	UNPAVED TRENCHING (***** (3, 2")	200 LF		
0032	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4 EA		
0033	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	900 LF		
0034	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	400 LF		

Contract No. **C203400**

County (ies): **Avery & Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General