

## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PAT MCCRORY GOVERNOR ANTHONY J. TATA SECRETARY

August 6, 2013

Addendum No. 1

RE: Contract ID C203404
WBS # 41665.4B
State Funded
Carteret County
Bridge #35 On US-70 Across Ward Creek And Bridge #39
On US-70 Across Oyster Creek

August 20, 2013 Letting

To Whom It May Concern:

Reference is made to the plans furnished to you on this project.

The following revisions have been made to the plans:

- On Sheet No.S-2: the 11<sup>th</sup> note in the first column of the general notes was revised to require epoxy coated bar supports in the barrier rail.
- On Sheet No.S-8: Ten additional pairs of required 2 ½" dowel holes were added to be in agreement with the dowel placement shown on sheet S-13.
- On Sheet No.S-9: The following two notes were added:

"PRESTRESSED CONCRETE CORED SLAB UNITS ARE DESIGNED FOR 0 PSI TENSION IN THE PRECOMPRESSED TENSILE ZONE UNDER ALL LOADING CONDITIONS".

"PRESTRESSED CONCRETE CORED SLAB UNITS SHALL CONTAIN CALCIUM NITRITE CORROSION INHIBITOR IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS."

- On Sheet No.S-27: the 11<sup>th</sup> note in the first column of the general notes was revised to require epoxy coated bar supports in the barrier rail.
- On Sheet No.S-33: Ten additional pairs of required 2 ½" dowel holes were added to be in agreement with the dowel placement shown on sheet S-38.
- On Sheet No.S-34: The following two notes were added:

"PRESTRESSED CONCRETE CORED SLAB UNITS ARE DESIGNED FOR 0 PSI TENSION IN THE PRECOMPRESSED TENSILE ZONE UNDER ALL LOADING CONDITIONS".

"PRESTRESSED CONCRETE CORED SLAB UNITS SHALL CONTAIN CALCIUM NITRITE CORROSION INHIBITOR IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS."

Please void Sheet Nos. S-2, S-8, S-9, S-27, S-33 and S-34 in your plans and staple the revised Sheet Nos. S-2, S-8, S-9, S-27, S-33 and S-34 thereto.

Sincerely,

R. A. Garris, PE Contract Officer

RAG/jag Attachments

cc: Mr. Ron Hancock, PE

Mr. John Rouse, PE

Ms. D. M. Barbour, PE

Mr. J. V. Barbour, PÈ

Mr. R.E. Davenport, PE

Project File (2)

Mr. Ray Arnold, PE

Ms. Natalie Roskam, PE

Mr. Ronnie Higgins

Mr. Larry Strickland

Ms. Marsha Sample

Ms. Lori Strickland