

**PROJECT SPECIAL PROVISIONS**  
**GEOENVIRONMENTAL**

**CONTAMINATED SOIL (10-12-2012)**

The Contractor's attention is directed to the fact that soil contaminated with PCBs, metals, VOCs, dioxins, furans, and petroleum exist on Parcel U-4412\_031 Schulhofer Property. The known areas of contamination are indicated on corresponding plans sheets. Information relating to these contaminated areas, sample locations, and investigation reports are available at the following web address by navigating to the correct letting year and month, then selecting, "Plans and Proposals", "Haywood U-4412", "GeoEnvironmental":

<http://dotw-xfer01.dot.state.nc.us/dsplan/>

The Contractor shall not excavate any contaminated soil from Parcel U-4412\_031 due to the potentially hazardous nature of the contaminants. In advance of construction, the Department's specialty contractor will have demarked contaminated areas with a horizontal visual barrier and will have placed clean, compacted fill above the contaminated soils within the slopestakes. If the Contractor inadvertently encounters soils below this horizontal visual barrier, or if the Contractor encounters soil with unusual odors or unusual soil staining, then the Contractor shall stop work in that area and contact the GeoEnvironmental Section to resolve the issue.

