TIP NO.	SHEET NO.
U-2579B	SIGN-4M

APPROVED: Charles A. Johnson III (DocuSigned by: 02A34B1AC09543B...)

DATE: 06/09/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20675 ENGINEER CHARLES A. JOHNSON III

(431) QUANTITY REQ'D 1

SCHOOL

24" X 8"
S4-3P

MOUNT ABOVE SIGN 418 IN 1 INSTALLATION
BACKGROUND SHEETING SHALL BE FLUORESCENT
YELLOW GRADE B SHEETING

(432) QUANTITY REQ'D 2

RAMP
25
MPH

36" X 48"
W13-3

TWO "U" POSTS PER SIGN

(433) QUANTITY REQ'D 2

EXIT
35
MPH

36" X 48"
W13-2

TWO "U" POSTS PER SIGN

(434) QUANTITY REQ'D 2

10
MPH

18" X 18"
W13-1P

MOUNT BELOW SIGN 441 AND 403
IN 1 INSTALLATION EACH

(435) QUANTITY REQ'D 4

48" X 48"
W4-1(R)

TWO "U" POSTS PER SIGN

(436) QUANTITY REQ'D 2

30" X 30"
W1-4R

ONE "U" POST PER SIGN

(437) QUANTITY REQ'D 1

CITY WIDE
SPEED LIMIT 35
UNLESS
OTHERWISE POSTED

42" X 30"
R2-27

MOUNT BELOW SIGN 307 IN 1 INSTALLATION

(438) QUANTITY REQ'D 1

36" X 36"
S1-1

ONE "U" POST PER SIGN
BACKGROUND SHEETING SHALL BE FLUORESCENT
YELLOW GRADE B SHEETING

(439) QUANTITY REQ'D 1

AHEAD

24" X 12"
W16-9P

MOUNT BELOW SIGN 438 IN 1 INSTALLATION
BACKGROUND SHEETING SHALL BE FLUORESCENT
YELLOW GRADE B SHEETING

(440) QUANTITY REQ'D 1

7:30-8:30 AM
2:30-3:30 PM

24" X 10"
S4-1P

MOUNT BELOW SIGN 418 IN 1 INSTALLATION
BACKGROUND SHEETING SHALL BE FLUORESCENT
YELLOW GRADE B SHEETING

(441) QUANTITY REQ'D 1

30" X 30"
W1-1(L)

ONE "U" POST PER SIGN

(442) QUANTITY REQ'D 1

40
MPH

18" X 18"
W13-1P

MOUNT BELOW SIGN 419 IN 1 INSTALLATION

HNTB
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

TYPE "E" SIGNS