STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
U-3465	3G-1

SUMMARY OF SUBSURFACE DRAINAGE

LINE	BEGIN STATION	END STATION	LOCATION	DRAIN TYPE * UD /BD /SD	LENGTH (FT.)
	CONTINGENCY			UD	1000
				TOTAL	1000

* UD = UNDERDRAIN
* BD = BLIND DRAIN
* SD = SUBSURFACE DRAIN

SUMMARY OF AGGREGATE SUBGRADE /STABILIZATION

LINE	STATION	STATION	AGGREGATE TYPE* ASU/AST	AGGREGATE THICKNESS INCHES	SHALLOW UNDERCUT CY	CLASS IV SUBGRADE STABILIZATION TONS	GEOTEXTILE FOR SOIL STABILIZATION SY	STABILIZER AGGREGATE TONS	CLASS IV AGGREGATE STABILIZATION TONS
-L-	110+80	112+70					} 3300		
-L-	184+90	190+70							
-Y4-	12+60	15+70							
PER EROSION CONTROL							400		
CONTINGENCY			ASU	3			3000	500	
			TOTAL CY/TONS/SY:				6700	500	

* ASU = AGGREGATE SUBGRADE
* AST = AGGREGATE STABILIZATION