PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
21+00.00	0	0	
21+50.00	23	25	
22+00.00	21	29	
22+50.00	19	38	
23+00.00	26	48	
23+50.00	29	49	
24+00.00	24	58	
24+50.00	26	67	
25+00.00	50	72	
25+50.00	229	53	
26+00.00	198	45	
26+50.00	14	52	
27+00.00	27	31	
27+50.00	44	19	
28+00.00	57	16	
28+50.00	70	8	
29+00.00	87	4	
29+50.00	91	4	
30+00.00	79	2	
30+50.00	56	7	
31+00.00	23	222	
31+50.00	2	462	
32+00.00	0	316	
32+50.00	1	87	
33+00.00	1	52	
33+50.00	0	74	
34+00.00	0	90	
34+50.00	2	78	
35+00.00	9	51	
35+50.00	27	38	
36+00.00	51	25	
36+50.00	69	19	
37+00.00	102	18	
37+50.00	158	18	
38+00.00	181	23	
38+50.00	126	30	
39+00.00	53	37	
39+50.00	16	69	
40+00.00	15	145	
40+50.00	19	244	
41+00.00	10	320	
41+50.00	10	375	
42+00.00	6	681	
42+50.00	0	1081	
43+00.00	0	1137	
43+50.00	0	817	
44+00.00	0	494	
44+50.00	0	391	
45+00.00	0	319	
45+50.00	0	267	
46+00.00	0	208	
46+50.00	0	130	
47+00.00	1	81	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
47+50.00	4	55	
48+00.00	5	42	
48+50.00	4	46	
49+00.00	3	52	
49+50.00	2	69	
50+00.00	2	92	
50+50.00	3	100	
51+00.00	4	100	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
21+00.00	0	0	
21+50.00	22	29	
22+00.00	19	31	
22+50.00	20	34	
23+00.00	24	44	
23+50.00	26	46	
24+00.00	28	50	
24+50.00	31	62	
25+00.00	37	70	
25+50.00	70	48	
26+00.00	91	33	
26+50.00	102	32	
27+00.00	83	17	
27+50.00	41	13	
28+00.00	38	12	
28+50.00	46	11	
29+00.00	51	12	
29+50.00	32	20	
30+00.00	12	28	
30+50.00	3	116	
31+00.00	0	467	
31+50.00	0	690	
32+00.00	0	481	
32+50.00	0	204	
33+00.00	0	110	
33+50.00	0	136	
34+00.00	0	130	
34+50.00	0	103	
35+00.00	3	73	
35+50.00	8	46	
36+00.00	20	33	
36+50.00	23	32	
37+00.00	19	38	
37+50.00	14	46	
38+00.00	4	92	
38+50.00	0	175	
39+00.00	0	285	
39+50.00	0	407	
40+00.00	0	599	
40+50.00	0	790	
41+00.00	0	861	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
41+50.00	0	1194	
42+00.00	0	2319	
42+50.00	0	3470	
43+00.00	0	3560	
43+50.00	0	2506	
44+00.00	0	1462	
44+50.00	0	1062	
45+00.00	0	729	
45+50.00	0	454	
46+00.00	0	321	
46+50.00	0	281	
47+00.00	0	231	
47+50.00	4	148	
48+00.00	9	95	
48+50.00	9	91	
49+00.00	6	109	
49+50.00	2	134	
50+00.00	0	211	
50+50.00	0	267	
51+00.00	2	266	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
51+00.00	0	0	
51+50.00	4	97	
52+00.00	4	77	
52+50.00	4	50	
53+00.00	11	32	
53+50.00	23	23	
54+00.00	17	44	
54+50.00	5	77	
55+00.00	4	96	
55+50.00	4	91	
56+00.00	3	132	
56+50.00	1	154	
57+00.00	0	134	
57+50.00	0	161	
58+00.00	0	185	
58+50.00	0	182	
59+00.00	0	156	
59+50.00	0	131	
60+00.00	0	106	
60+50.00	1	83	
61+00.00	3	64	
61+50.00	4	46	
62+00.00	9	39	
62+50.00	11	45	
63+00.00	7	50	
63+50.00	6	52	
64+00.00	15	39	
64+50.00	18	44	
65+00.00	24	56	