PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
65+50.00	26	40	
66+00.00	7	128	
66+50.00	7	342	
67+00.00	6	508	
67+50.00	0	470	
68+00.00	2	263	
68+50.00	5	101	
69+00.00	6	56	
69+50.00	6	41	
70+00.00	9	33	
70+50.00	14	38	
71+00.00	22	53	
71+50.00	24	65	
72+00.00	19	67	
72+50.00	12	91	
73+00.00	6	143	
73+50.00	4	194	
74+00.00	3	218	
74+50.00	2	225	
75+00.00	8	205	
75+50.00	11	206	
76+00.00	6	245	
76+50.00	3	256	
77+00.00	2	229	
77+50.00	4	163	
78+00.00	8	93	
78+50.00	17	48	
79+00.00	19	34	
79+50.00	11	36	
80+00.00	46	21	
80+50.00	47	6	
81+00.00	6	32	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
51+00.00	0	0	
51+50.00	4	306	
52+00.00	4	359	
52+50.00	4	387	
53+00.00	2	294	
53+50.00	0	199	
54+00.00	0	252	
54+50.00	0	487	
55+00.00	0	707	
55+50.00	0	769	
56+00.00	0	775	
56+50.00	0	715	
57+00.00	0	652	
57+50.00	0	578	
58+00.00	2	324	
58+50.00	2	133	
59+00.00	0	156	
59+50.00	0	160	
60+00.00	0	125	
60+50.00	2	75	
61+00.00	34	44	
61+50.00	99	19	
62+00.00	186	4	
62+50.00	241	0	
63+00.00	227	2	
63+50.00	217	2	
64+00.00	275	0	
64+50.00	328	0	
65+00.00	361	0	
65+50.00	315	0	
66+00.00	191	8	
66+50.00	101	9	
67+00.00	47	69	
67+50.00	19	219	
68+00.00	5	195	
68+50.00	16	74	
69+00.00	34	55	
69+50.00	41	43	
70+00.00	19	45	
70+50.00	1	107	
71+00.00	6	119	
71+50.00	14	71	
72+00.00	20	55	
72+50.00	58	31	
73+00.00	80	23	
73+50.00	74	24	
74+00.00	81	15	
74+50.00	63	8	
75+00.00	35	12	
75+50.00	23	15	
76+00.00	11	21	
76+50.00	7	23	
77+00.00	9	19	
77+50.00	7	22	
78+00.00	5	31	
78+50.00	8	41	
79+00.00	12	36	
79+50.00	11	20	
80+00.00	12	13	
80+50.00	6	7	
81+00.00	0	19	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
81+00.00	0	0	
81+50.00	6	65	
82+00.00	6	75	
82+50.00	4	69	
83+00.00	0	77	
83+50.00	0	111	
84+00.00	0	208	
84+50.00	0	319	
85+00.00	0	342	
85+50.00	0	339	
86+00.00	0	340	
86+50.00	0	300	
87+00.00	0	204	
87+50.00	6	98	
88+00.00	27	40	
88+50.00	69	15	
89+00.00	95	5	
89+50.00	78	8	
90+00.00	56	15	
90+50.00	44	21	
91+00.00	30	21	
91+50.00	11	23	
92+00.00	0	93	
92+50.00	0	191	
93+00.00	0	262	
93+50.00	0	291	
94+00.00	0	288	
94+50.00	0	270	
95+00.00	0	252	
95+50.00	0	232	
96+00.00	1	149	
96+50.00	27	61	
97+00.00	94	19	
97+50.00	83	16	
98+00.00	31	31	
98+50.00	31	38	
99+00.00	16	56	
99+50.00	1	118	
100+00.00	0	199	
100+50.00	0	288	
101+00.00	0	350	
101+50.00	0	311	
102+00.00	0	235	
102+50.00	19	116	
103+00.00	130	18	
103+50.00	192	7	
104+00.00	149	6	
104+50.00	144	4	
105+00.00	150	6	
105+50.00	121	7	
106+00.00	89	4	
106+50.00	81	5	
107+00.00	136	5	
107+50.00	167	6	
108+00.00	95	18	
108+50.00	25	80	
109+00.00	0	175	
109+50.00	0	239	