PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
110+00.00	0	284	
110+50.00	0	289	
111+00.00	0	276	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
81+00.00	0	0	
81+50.00	0	56	
82+00.00	1	75	
82+50.00	3	69	
83+00.00	6	52	
83+50.00	8	42	
84+00.00	8	44	
84+50.00	6	59	
85+00.00	9	39	
85+50.00	8	61	
86+00.00	2	91	
86+50.00	3	50	
87+00.00	3	31	
87+50.00	5	29	
88+00.00	6	38	
88+50.00	4	53	
89+00.00	4	47	
89+50.00	6	36	
90+00.00	6	48	
90+50.00	5	74	
91+00.00	4	48	
91+50.00	5	6	
92+00.00	4	79	
92+50.00	2	138	
93+00.00	1	108	
93+50.00	1	84	
94+00.00	2	78	
94+50.00	2	81	
95+00.00	3	80	
95+50.00	3	81	
96+00.00	2	75	
96+50.00	5	50	
97+00.00	9	31	
97+50.00	12	30	
98+00.00	13	28	
98+50.00	12	23	
99+00.00	12	18	
99+50.00	14	24	
100+00.00	13	44	
100+50.00	7	37	
101+00.00	7	31	
101+50.00	10	38	
102+00.00	9	25	
102+50.00	6	35	
103+00.00	2	73	
103+50.00	2	46	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
104+00.00	3	0	
104+50.00	2	51	
105+00.00	0	80	
105+50.00	2	56	
106+00.00	4	56	
106+50.00	3	73	
107+00.00	2	83	
107+50.00	2	82	
108+00.00	2	90	
108+50.00	2	93	
109+00.00	9	95	
109+50.00	15	94	
110+00.00	15	88	
110+50.00	19	69	
111+00.00	35	37	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
111+00.00	0	0	
111+50.00	0	241	
112+00.00	0	234	75
112+50.00	0	231	125
113+00.00	3	78	
113+50.00	20	42	
114+00.00	35	21	
114+50.00	36	17	
115+00.00	28	18	
115+50.00	16	22	
116+00.00	10	34	
116+50.00	7	50	
117+00.00	8	57	
117+50.00	8	78	
118+00.00	6	109	
118+50.00	4	119	
119+00.00	3	103	
119+50.00	3	91	
120+00.00	3	84	
120+50.00	6	62	
121+00.00	14	44	
121+50.00	15	47	
122+00.00	29	40	
122+50.00	48	22	
123+00.00	59	11	
123+50.00	82	7	
124+00.00	107	9	
124+50.00	162	8	
125+00.00	193	8	
125+50.00	118	7	
126+00.00	31	59	
126+50.00	3	329	
127+00.00	0	789	
127+50.00	0	1203	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
128+00.00	0	1501	
128+50.00	0	1592	
129+00.00	0	1545	
129+50.00	0	1369	
130+00.00	0	1024	
130+50.00	1	724	
131+00.00	7	328	
131+50.00	9	110	
132+00.00	6	141	
132+50.00	8	103	
133+00.00	9	69	
133+50.00	7	44	
134+00.00	5	40	
134+50.00	6	38	
135+00.00	8	36	
135+50.00	8	39	
136+00.00	6	51	
136+50.00	3	55	
137+00.00	6	36	
137+50.00	84	25	
138+00.00	169	30	
138+50.00	228	42	
139+00.00	319	54	
139+50.00	348	65	
140+00.00	282	70	
140+50.00	160	78	
141+00.00	54	81	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
111+00.00	5	20	20
111+50.00	83	92	70
112+00.00	138	97	75
112+50.00	124	108	85
113+00.00	42	117	
113+50.00	5	361	
114+00.00	2	456	
114+50.00	0	545	
115+00.00	0	853	
115+50.00	0	1066	
116+00.00	0	1284	
116+50.00	0	1445	
117+00.00	0	1463	
117+50.00	0	1423	
118+00.00	0	1361	
118+50.00	0	1184	
119+00.00	0	789	
119+50.00	0	455	
120+00.00	0	235	
120+50.00	1	98	
121+00.00	16	44	
121+50.00	41	19	