PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
167+50.00	4	99	
168+00.00	3	126	
168+50.00	4	115	
169+00.00	7	83	
169+50.00	7	69	
170+00.00	7	58	
170+50.00	8	59	
171+00.00	6	66	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
171+00.00	0	0	
171+50.00	0	585	
172+00.00	0	391	
172+50.00	5	206	
173+00.00	32	94	
173+50.00	121	37	
174+00.00	192	22	
174+50.00	249	19	
175+00.00	336	18	
175+50.00	354	16	
176+00.00	273	15	
176+50.00	139	73	
177+00.00	34	295	
177+50.00	0	642	
178+00.00	0	840	
178+50.00	0	798	
179+00.00	0	657	
179+50.00	0	618	
180+00.00	0	785	
180+50.00	0	1171	
181+00.00	0	1618	
181+50.00	0	1766	
182+00.00	0	1609	
182+50.00	0	1256	
183+00.00	0	792	
183+50.00	0	416	
184+00.00	21	156	
184+50.00	39	31	
185+00.00	93	35	25
185+50.00	175	185	185
186+00.00	221	161	160
186+50.00	238	142	140
187+00.00	239	126	125
187+50.00	242	90	90
188+00.00	223	125	125
188+50.00	319	216	215
189+00.00	549	263	260
189+50.00	571	254	250
190+00.00	386	237	225
190+50.00	232	236	205
191+00.00	172	81	45

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
191+50.00	146	25	
192+00.00	156	22	
192+50.00	147	29	
193+00.00	80	48	
193+50.00	46	50	
194+00.00	88	33	
194+50.00	60	89	
195+00.00	2	123	
195+50.00	18	58	
196+00.00	33	17	
196+50.00	51	18	
197+00.00	82	19	
197+50.00	95	12	
198+00.00	69	8	
198+50.00	38	15	
199+00.00	27	29	
199+50.00	17	56	
200+00.00	12	122	
200+50.00	13	181	
201+00.00	8	209	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
171+00.00	0	0	
171+50.00	4	61	
172+00.00	21	54	
172+50.00	48	56	
173+00.00	64	57	
173+50.00	70	59	
174+00.00	101	58	
174+50.00	118	56	
175+00.00	90	49	
175+50.00	43	44	
176+00.00	6	47	
176+50.00	3	56	
177+00.00	4	56	
177+50.00	4	51	
178+00.00	4	61	
178+50.00	4	68	
179+00.00	5	59	
179+50.00	6	44	
180+00.00	6	33	
180+50.00	6	40	
181+00.00	23	76	
181+50.00	76	122	
182+00.00	102	135	
182+50.00	74	122	
183+00.00	45	107	
183+50.00	29	93	
184+00.00	16	71	
184+50.00	8	33	
185+00.00	8	28	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
185+50.00	6	84	
186+00.00	6	108	
186+50.00	6	128	
187+00.00	8	223	
187+50.00	11	275	
188+00.00	9	222	
188+50.00	5	165	
189+00.00	2	153	
189+50.00	2	165	
190+00.00	2	196	
190+50.00	2	240	
191+00.00	3	220	
191+50.00	4	160	
192+00.00	4	108	
192+50.00	4	149	
193+00.00	4	225	
193+50.00	4	192	
194+00.00	4	140	
194+50.00	4	130	
195+00.00	4	109	
195+50.00	5	62	
196+00.00	5	42	
196+50.00	4	51	
197+00.00	4	70	
197+50.00	5	87	
198+00.00	6	93	
198+50.00	6	93	
199+00.00	6	77	
199+50.00	6	69	
200+00.00	3	63	
200+50.00	3	42	
201+00.00	6	31	

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
201+00.00	0	0	
201+50.00	4	254	
202+00.00	1	287	
202+50.00	0	264	
203+00.00	0	265	
203+50.00	0	193	
204+00.00	0	306	
204+50.00	0	582	
205+00.00	0	684	
205+50.00	0	631	
206+00.00	0	458	
206+50.00	0	314	
207+00.00	1	160	
207+50.00	7	55	
208+00.00	9	51	
208+50.00	8	81	
209+00.00	6	161	