PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1F

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
209+50.00	4	204	
210+00.00	6	193	
210+50.00	11	214	
211+00.00	19	236	
211+50.00	27	223	
212+00.00	33	181	
212+50.00	36	163	
213+00.00	38	148	
213+50.00	41	97	
214+00.00	46	58	
214+50.00	53	61	
215+00.00	59	59	
215+50.00	65	55	
216+00.00	73	51	
216+50.00	80	37	
217+00.00	78	24	
217+50.00	52	48	
218+00.00	17	136	
218+50.00	3	210	
219+00.00	0	216	
219+50.00	0	214	
220+00.00	0	162	
220+50.00	6	67	
221+00.00	21	24	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
201+00.00	0	0	
201+50.00	7	31	
202+00.00	6	39	
202+50.00	5	42	
203+00.00	5	39	
203+50.00	26	29	
204+00.00	40	10	
204+50.00	19	19	
205+00.00	6	40	
205+50.00	5	46	
206+00.00	4	49	
206+50.00	5	48	
207+00.00	6	41	
207+50.00	7	40	
208+00.00	6	48	
208+50.00	4	62	
209+00.00	7	65	
209+50.00	15	50	
210+00.00	22	65	
210+50.00	25	83	
211+00.00	25	84	
211+50.00	25	92	
212+00.00	19	98	
212+50.00	11	98	
213+00.00	19	93	

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
213+50.00	44	90	
214+00.00	71	86	
214+50.00	106	81	
215+00.00	118	93	
215+50.00	138	111	
216+00.00	196	109	
216+50.00	221	94	
217+00.00	196	63	
217+50.00	162	29	
218+00.00	106	12	
218+50.00	56	18	
219+00.00	39	30	
219+50.00	26	42	
220+00.00	25	32	
220+50.00	31	14	
221+00.00	26	17	

Station -Y-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
11+00.00	0	0	
11+50.00	15	288	
12+00.00	25	241	
12+50.00	22	267	
13+00.00	29	306	
13+50.00	157	331	
14+00.00	246	179	
14+50.00	149	6	
15+00.00	68	36	
15+50.00	70	53	
16+00.00	94	42	
16+50.00	193	30	
17+00.00	258	13	
17+50.00	194	9	
18+00.00	167	8	
18+50.00	157	7	
19+00.00	133	5	
19+50.00	72	2	

Station -Y1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+49.50	0	0	
10+75.00	0	167	
11+00.00	0	280	
11+25.00	1	183	
11+50.00	3	104	
11+75.00	7	51	
12+00.00	12	23	
12+25.00	14	14	

Station -Y2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+80.00	0	0	
11+00.00	13	3	
11+25.00	18	8	
11+44.04	6	5	

Station -Y2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
12+43.14	0	0	
12+50.00	19	1	
12+75.00	85	9	
13+00.00	22	8	
13+25.00	14	6	

Station -Y3-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+51.06	0	0	
10+75.00	0	48	
11+00.00	0	77	
11+25.00	1	45	
11+50.00	2	31	
11+75.00	3	25	
12+00.00	3	30	

Station -Y4-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+20.00	0	0	
10+50.00	10	5	
11+00.00	28	10	
11+50.00	74	3	
12+00.00	120	7	
12+50.00	114	9	
13+00.00	309	27	25
13+50.00	581	45	45
14+00.00	658	20	20
14+50.00	589	25	25
15+00.00	527	50	50
15+50.00	464	30	30
16+00.00	480	5	5
16+50.00	449	0	
16+88.46	160	0	

Station -Y4A-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+50.00	0	0	
10+75.00	5	15	
11+00.00	5	17	
11+25.00	2	31	
11+50.00	0	73	
11+68.43	0	39	