PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1H

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station -DRV1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
14+00.00	0	111	
14+25.00	0	78	
14+50.00	0	57	
14+75.00	0	33	
15+00.00	11	13	
15+25.00	37	4	
15+50.00	75	0	
15+75.00	120	0	
16+00.00	170	0	
16+25.00	219	0	
16+50.00	264	0	
16+75.00	302	0	
17+00.00	312	0	
17+25.00	293	0	
17+50.00	231	0	
17+75.00	129	2	
18+00.00	50	24	
18+25.00	19	62	
18+50.00	9	91	
18+75.00	9	119	
19+12.69	10	103	

Station -DRV2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
14+32.47	0	0	
14+50.00	2	6	
14+75.00	13	3	
15+00.00	10	16	
15+25.00	0	49	
15+50.00	0	79	
15+75.00	0	103	
16+00.00	0	137	
16+25.00	0	167	
16+50.00	0	184	
16+75.00	0	186	
17+00.00	0	178	
17+25.00	0	180	

Station -DRV3-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+60.00	0	0	
10+75.00	49	0	
11+00.00	131	1	
11+25.00	91	1	
11+50.00	50	0	
11+75.00	14	1	
11+82.00	2	0	