PROJ. REFERENCE NO.	SHEET NO.
U-3465	X-1G

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -Y5-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
11+50.00	0	0	
11+75.00	9	5	
12+00.00	9	8	
12+25.00	10	13	
12+50.00	9	11	
12+66.76	3	3	

Station -Y6-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
11+75.00	0	0	
12+00.00	16	2	
12+25.00	17	3	
12+50.00	19	5	
12+75.00	16	11	
13+00.00	12	14	
13+25.00	12	10	
13+50.00	17	5	
13+75.00	25	1	
14+00.00	67	1	
14+30.57	63	1	

Station -Y6A-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+37.50	0	0	
10+75.00	4	1	
11+00.00	3	4	
11+25.00	2	6	
11+50.00	2	8	
11+75.00	0	18	
12+00.00	0	28	
12+25.00	0	30	
12+50.00	0	24	
12+75.00	1	11	
13+07.13	2	1	

Station -Y6B-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+37.64	0	0	
11+00.00	0	10	
11+25.00	2	7	
11+50.00	10	4	
11+70.00	10	1	

Station -Y7-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+49.53	0	0	
10+75.00	12	16	
11+00.00	32	38	
11+25.00	66	31	
11+50.00	107	17	
11+75.00	105	39	
12+00.00	77	44	
12+25.00	60	24	
12+50.00	48	19	
12+75.00	42	14	
13+00.00	38	6	

Station -Y8-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
11+25.00	0	0	
11+50.00	13	13	
11+75.00	18	30	
12+00.00	16	35	
12+25.00	16	38	
12+50.00	19	40	
12+75.00	18	44	
13+00.00	15	51	
13+25.00	12	58	
13+50.00	10	80	
13+75.00	12	96	
14+00.00	7	162	
14+33.65	0	152	

Station -YA1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+70.00	0	0	
11+00.00	54	2	
11+50.00	126	0	
12+00.00	124	1	
12+50.00	137	6	
13+00.00	153	34	
13+50.00	71	130	
14+00.00	15	260	
14+28.06	8	90	

Station -YA2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+00.00	0	0	
10+50.00	25	295	
11+00.00	2	87	
11+50.00	25	33	
12+00.00	60	0	
12+50.00	84	0	
13+00.00	79	0	
13+50.00	47	4	
14+00.00	45	5	
14+50.00	48	23	
15+00.00	49	61	
15+50.00	56	62	
16+00.00	114	25	
16+50.00	188	2	
17+00.00	229	6	
17+50.00	319	6	
18+00.00	294	0	
18+50.00	112	89	
18+51.46	0	3	

Station -YB-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+24.07	0	0	
10+50.00	0	25	
10+75.00	0	57	
11+00.00	0	92	
11+25.00	16	192	
11+50.00	37	190	
11+75.00	36	86	
12+00.00	25	46	
12+25.00	19	28	
12+50.00	19	16	
12+75.00	20	9	
13+00.00	21	27	
13+27.04	23	45	

Station -YC-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+27.00	0	0	
10+50.00	28	2	
10+75.00	46	2	
11+00.00	27	0	
11+25.00	29	1	
11+35.00	15	0	

Station -DRV1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
10+43.45	0	0	
10+50.00	30	0	
10+75.00	25	3	
11+00.00	33	8	
11+25.00	19	77	
11+50.00	0	252	
11+75.00	0	364	
12+00.00	0	351	
12+25.00	0	315	
12+50.00	0	300	
12+75.00	0	305	
13+00.00	0	301	
13+25.00	0	268	
13+50.00	0	204	
13+75.00	0	152	