PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1G

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station	Uncl. Exc.	Embt
Y2	(cu. yd.)	(cu. yd.)
15+50.00	75	0
16+00.00	35	0

Station	Uncl. Exc.	Embt
Y3	(cu. yd.)	(cu. yd.)
11+00.00	0	0
11+25.00	36	267
11+50.00	69	151
11+75.00	93	62
12+00.00	86	18
12+25.00	25	2

Station	Uncl. Exc.	Embt
Y5	(cu. yd.)	(cu. yd.)
11+50.00	0	0
11+60.00	3	0
11+70.00	5	0
11+80.00	5	0
11+90.00	4	1
12+00.00	3	1
12+10.00	2	2
12+20.00	1	4
12+30.00	0	12

Station	Uncl. Exc.	Embt
Y6	(cu. yd.)	(cu. yd.)
11+00.00	0	0
11+50.00	104	10
12+00.00	221	9
12+50.00	242	18
13+00.00	131	102
13+50.00	21	236
14+00.00	0	320

Station	Uncl. Exc.	Embt
Y6	(cu. yd.)	(cu. yd.)
17+00.00	0	0
17+50.00	47	30
18+00.00	58	23
18+50.00	63	19
19+00.00	79	9
19+50.00	74	5

Station	Uncl. Exc.	Embt
Y7	(cu. yd.)	(cu. yd.)
10+25.00	0	0
10+50.00	197	0
11+00.00	382	0

Station	Uncl. Exc.	Embt
Y7	(cu. yd.)	(cu. yd.)
11+50.00	349	0
12+00.00	316	0
12+50.00	283	0
13+00.00	243	0
13+50.00	196	0
14+00.00	85	83
14+50.00	0	552
15+00.00	0	1114
15+50.00	0	1812
16+00.00	0	2644
16+50.00	0	2709
17+00.00	0	2128
17+50.00	0	1310
18+00.00	0	597
18+50.00	1	281
19+00.00	23	112
19+50.00	86	18
20+00.00	170	3
20+50.00	191	0
21+00.00	137	2
21+50.00	123	2
22+00.00	176	0
22+50.00	256	0
23+00.00	305	0
23+50.00	269	0
24+00.00	177	2
24+50.00	101	7
25+00.00	56	10

Station	Uncl. Exc.	Embt
Y7A	(cu. yd.)	(cu. yd.)
10+30.00	0	0
10+50.00	14	0
10+75.00	51	2
11+00.00	87	0
11+25.00	126	0
11+50.00	166	0
11+75.00	194	0

Station	Uncl. Exc.	Embt
Y8	(cu. yd.)	(cu. yd.)
11+60.00	0	0
12+00.00	44	0
12+50.00	147	1
13+00.00	206	0

Station	Uncl. Exc.	Embt
Y8	(cu. yd.)	(cu. yd.)
15+50.00	0	0
16+00.00	243	0

Station	Uncl. Exc.	Embt
Y8	(cu. yd.)	(cu. yd.)
16+50.00	160	13
17+00.00	105	32
17+50.00	91	30
18+00.00	48	10

Station	Uncl. Exc.	Embt	UnderCut
Y9	(cu. yd.)	(cu. yd.)	(cu. yd.)
11+50.00	0	0	0
12+00.00	41	4	0
12+50.00	98	13	0
13+00.00	151	28	0
13+50.00	202	26	0
14+00.00	275	126	114
14+50.00	412	229	225

Station	Uncl. Exc.	Embt	UnderCut
Y9	(cu. yd.)	(cu. yd.)	(cu. yd.)
16+00.00	0	0	0
16+50.00	367	0	0
17+00.00	313	1	0
17+50.00	272	10	0
18+00.00	296	21	0
18+50.00	556	12	0
19+00.00	1040	0	0
19+50.00	1590	0	0
20+00.00	2184	0	0
20+50.00	2777	0	0
21+00.00	3154	0	0
21+50.00	3227	0	0
22+00.00	3093	0	0
22+50.00	2767	0	0
23+00.00	2444	0	0

Station	Uncl. Exc.	Embt
Y10	(cu. yd.)	(cu. yd.)
14+00.00	0	0
14+50.00	30	25
15+00.00	11	44
15+50.00	1	131
16+00.00	0	378

Station	Uncl. Exc.	Embt
Y10	(cu. yd.)	(cu. yd.)
18+50.00	0	0
19+00.00	1577	0
19+50.00	1408	0
20+00.00	1201	0
20+50.00	1024	0
21+00.00	794	0

Station	Uncl. Exc.	Embt
Y10	(cu. yd.)	(cu. yd.)
21+50.00	542	0
22+00.00	311	0
22+50.00	168	0
23+00.00	90	2
23+50.00	19	0

Station	Uncl. Exc.	Embt
Y10A	(cu. yd.)	(cu. yd.)
10+50.00	0	0
10+75.00	151	0
11+00.00	116	0
11+25.00	72	0
11+50.00	34	0
11+75.00	18	0

Station	Uncl. Exc.	Embt
Y11	(cu. yd.)	(cu. yd.)
13+50.00	0	0
14+00.00	68	21
14+50.00	41	32
15+00.00	36	41
15+50.00	40	47
16+00.00	76	41
16+50.00	191	20
17+00.00	255	9
17+50.00	208	15
18+00.00	154	24
18+50.00	153	35
19+00.00	90	20
19+50.00	0	0
20+00.00	85	13
20+50.00	155	31
21+00.00	108	34
21+50.00	84	31
22+00.00	46	22
22+50.00	1	30
23+00.00	0	44
23+50.00	0	75
24+00.00	0	88
24+50.00	0	61
25+00.00	0	43
25+50.00	0	18

Station	Uncl. Exc.	Embt
Y12	(cu. yd.)	(cu. yd.)
15+00.00	0	0
15+50.00	9	3
16+00.00	3	12
16+50.00	0	64
17+00.00	0	204