PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
51+50.00	319	0	0
52+00.00	328	0	0
52+50.00	184	42	0
53+00.00	37	358	0
53+50.00	0	1172	105
54+00.00	0	1865	219
54+50.00	0	1909	115
55+00.00	6	1281	0
55+50.00	153	490	0
56+00.00	526	138	0
56+50.00	882	49	0
57+00.00	895	38	0
57+50.00	536	60	0
58+00.00	166	179	0
58+50.00	36	295	0
59+00.00	21	337	0
59+50.00	9	308	0
60+00.00	62	141	0
60+50.00	287	10	0
61+00.00	652	0	0
61+50.00	1000	0	0
62+00.00	1255	0	0
62+50.00	1421	0	0
63+00.00	1463	0	0
63+50.00	931	0	0
64+00.00	343	0	0
64+50.00	291	6	0
65+00.00	249	68	0
65+50.00	103	223	0
66+00.00	12	557	0
66+50.00	0	1102	0
67+00.00	0	1996	271
67+50.00	0	2558	406
68+00.00	0	2581	292
68+50.00	0	2660	375
69+00.00	0	2736	408
69+50.00	0	2743	351
70+00.00	0	2661	289
70+50.00	0	2676	307
71+00.00	0	2179	179
71+50.00	0	1777	0
72+00.00	0	1688	0
72+50.00	0	1550	0
73+00.00	0	1981	0
73+50.00	0	3565	484
74+00.00	0	3773	484
74+50.00	0	2084	0
75+00.00	0	1327	0
75+50.00	0	1447	0
76+00.00	0	2114	84

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
76+00.00	0	0	0
76+50.00	0	897	0
77+00.00	0	821	0
77+50.00	0	1124	0
78+00.00	0	1165	0
78+50.00	0	837	0
79+00.00	0	724	0
79+50.00	0	613	0
80+00.00	0	538	0
80+50.00	0	418	0
81+00.00	0	290	0
81+50.00	7	189	0
82+00.00	71	199	0
82+50.00	103	201	0
83+00.00	70	126	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
76+00.00	0	0	0
76+50.00	0	2803	348
77+00.00	0	3374	541
77+50.00	0	3589	432
78+00.00	0	3474	256
78+50.00	0	3358	316
79+00.00	0	2793	215
79+50.00	0	2127	0
80+00.00	0	1791	0
80+50.00	0	1544	0
81+00.00	0	1402	0
81+50.00	0	1367	0
82+00.00	0	1452	69
82+50.00	0	1725	69
83+00.00	0	1668	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
83+00.00	0	0	0
83+50.00	131	1114	0
84+00.00	365	559	0
84+50.00	651	473	0
85+00.00	821	613	0
85+50.00	815	702	0
86+00.00	690	679	0
86+50.00	559	329	0
87+00.00	512	35	0
87+50.00	405	57	0
88+00.00	224	213	0
88+50.00	106	301	0
89+00.00	83	124	0
89+50.00	86	15	0
90+00.00	26	337	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
90+50.00	0	1150	0
91+00.00	0	2199	0
91+50.00	0	3290	0
92+00.00	0	4843	0
92+50.00	0	5981	0
93+00.00	0	5898	0
93+50.00	0	5605	0
94+00.00	0	5183	0
94+50.00	0	4095	0
95+00.00	0	2678	0
95+50.00	48	1744	0
96+00.00	187	1102	0
96+50.00	518	392	0
97+00.00	1490	24	0
97+50.00	3326	0	0
98+00.00	5902	0	0
98+50.00	8652	0	0
99+00.00	10686	0	0
99+50.00	10611	0	0
100+00.00	8254	0	0
100+50.00	5520	0	0
101+00.00	3483	0	0
101+50.00	2061	0	0
102+00.00	1013	0	0
102+50.00	289	261	0
103+00.00	11	1163	0
103+50.00	0	2262	0
104+00.00	0	3008	0
104+50.00	0	3499	0
105+00.00	0	3871	0
105+50.00	0	4405	0
106+00.00	0	3490	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
106+00.00	0	0	0
106+50.00	69	1395	0
107+00.00	677	290	0
107+50.00	2016	0	0
108+00.00	3621	0	0
108+50.00	5369	0	0
109+00.00	7283	0	0
109+50.00	9035	0	0
110+00.00	10809	0	0
110+50.00	12954	0	0
111+00.00	15287	0	0
111+50.00	17655	0	0
112+00.00	20026	0	0
112+50.00	22155	0	0
113+00.00	23994	0	0
113+50.00	25770	0	0
114+00.00	27226	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
114+50.00	28074	0	0
115+00.00	27448	0	0
115+50.00	25593	0	0
116+00.00	23681	0	0
116+50.00	21905	0	0
117+00.00	20123	0	0
117+50.00	18241	0	0
118+00.00	16364	0	0
118+50.00	14309	0	0
119+00.00	12172	0	0
119+50.00	9487	0	0
120+00.00	6016	3	3
120+50.00	2876	736	3
121+00.00	867	3006	204
121+50.00	87	6627	894
122+00.00	0	9049	691
122+50.00	0	7156	0
122+55.29	0	4676	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
125+00.00	0	7210	0
125+50.00	0	9813	0
126+00.00	0	12946	0
126+50.00	0	12194	0
127+00.00	0	11495	0
127+50.00	0	10664	0
128+00.00	0	9561	0
128+50.00	0	8525	0
129+00.00	0	7649	0
129+50.00	0	6842	0
130+00.00	0	6181	0
130+50.00	0	5740	0
131+00.00	0	6140	0
131+50.00	0	7000	0
132+00.00	0	7414	0
132+50.00	0	7499	0
133+00.00	0	7739	0
133+50.00	0	7719	0
134+00.00	0	7131	0
134+50.00	0	6981	0
135+00.00	0	7038	0
135+50.00	0	6698	0
136+00.00	0	6006	0
136+50.00	0	4784	0
137+00.00	0	3284	0
137+50.00	45	1394	0
138+00.00	943	131	0
138+50.00	2490	0	0
139+00.00	4088	0	0
139+50.00	5612	0	0
140+00.00	6918	0	0