PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1H

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y12		
17+50.00	0	371

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y13		
10+50.00	0	0
11+00.00	70	0
11+50.00	126	4
12+00.00	99	15
12+50.00	81	24
13+00.00	75	43
13+50.00	80	76
14+00.00	106	100
14+50.00	142	96
15+00.00	98	53
15+50.00	24	102
16+00.00	3	232
16+50.00	0	307
17+00.00	3	299
17+50.00	19	188
18+00.00	93	63
18+50.00	200	7
19+00.00	305	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y13		
21+50.00	0	0
22+00.00	41	14
22+50.00	49	3
23+00.00	31	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Drv1		
10+25.00	0	0
10+50.00	38	123
10+75.00	20	206
11+00.00	7	189
11+25.00	4	174
11+50.00	4	177
11+75.00	5	156
12+00.00	16	88
12+25.00	16	29
12+50.00	6	8
12+86.32	4	2

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Dr4A		
10+04.00	0	0
10+25.00	0	2
10+50.00	2	25
10+75.00	10	81
11+00.00	16	159
11+25.00	8	273

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Dr8A		
10+40.00	0	0
10+50.00	3	0
10+75.00	8	8
11+00.00	1	32
11+25.00	0	95
11+50.00	0	239

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Dr11A		
11+50.00	0	0
11+75.00	861	0
12+00.00	772	0
12+25.00	707	0
12+50.00	632	0
12+75.00	550	0
13+00.00	449	0
13+25.00	321	0
13+50.00	239	0
13+75.00	191	0
14+00.00	114	0
14+25.00	46	0
14+30.00	2	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET1)		
34+37.96	0	0
34+50.00	1	1
35+00.00	7	9
35+50.00	10	18
36+00.00	13	19
36+50.00	12	13
37+00.00	8	17
37+50.00	32	14
38+00.00	82	3
38+50.00	89	0
39+00.00	35	0
39+50.00	2	0
40+00.00	5	11
40+50.00	3	60
41+00.00	0	185
41+50.00	0	392
42+00.00	0	535
42+50.00	0	564
43+00.00	0	556

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET1)		
43+50.00	0	479
44+00.00	0	356
44+50.00	0	260
44+88.62	0	172

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET2)		
50+00.00	0	0
50+25.00	11	0
50+50.00	13	0
50+75.00	12	2
51+00.00	9	6
51+25.00	8	9
51+50.00	6	11
51+75.00	2	13
52+00.00	3	13
52+25.00	6	10
52+50.00	10	8
52+75.00	10	6
53+00.00	11	3
53+25.00	11	1
53+50.00	10	1
53+75.00	6	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET3)		
307+63.33	0	0
308+00.00	5	0
308+50.00	13	0
309+00.00	14	0
309+50.00	14	0
310+00.00	14	4
310+50.00	44	4
311+00.00	50	0
311+50.00	15	6
312+00.00	6	24
312+50.00	16	30
313+00.00	11	12

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Det3A		
10+25.00	0	0
10+50.00	6	0
10+75.00	12	0
11+00.00	11	3
11+25.00	8	17
11+50.00	8	32
11+75.00	7	18
12+00.00	10	0
12+25.00	7	25
12+50.00	1	88
12+75.00	6	182
13+00.00	8	130

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET4)		
322+49.59	0	0
323+00.00	0	5
323+50.00	0	15
324+00.00	7	22
324+50.00	10	26
325+00.00	6	23
325+50.00	8	14
326+00.00	27	31
326+50.00	38	43
327+00.00	47	28
327+47.97	60	21

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(DET5)		
371+50.00	0	0
372+00.00	3	4
372+50.00	5	4
373+50.00	17	0
374+00.00	7	1
374+50.00	3	2
375+00.00	1	1

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L1(shift)		
22+00.00	0	0
22+50.00	7	4
23+00.00	8	6
23+50.00	9	11
24+00.00	15	8
24+50.00	26	6
25+00.00	54	8
25+50.00	68	30
26+00.00	31	220
26+50.00	0	520
27+00.00	0	799
27+50.00	0	706
28+00.00	0	342
28+50.00	37	119

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
L(shift)		
29+00.00	0	0
29+50.00	65	1