PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
239+00.00	59	893	0
239+50.00	5	1666	0
240+00.00	0	2434	0
Station L	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**
240+00.00	0	0	0
240+50.00	0	3022	0
241+00.00	0	3936	0
241+50.00	0	5154	0
242+00.00	0	6283	0
242+50.00	0	6729	0
243+00.00	0	6249	0
243+50.00	0	5320	0
244+00.00	0	4748	0
244+50.00	0	4850	0
245+00.00	0	4608	0
245+50.00	0	3536	0
246+00.00	0	2156	0
246+50.00	48	871	0
247+00.00	165	161	0
247+50.00	194	0	0
248+00.00	156	72	0
248+50.00	121	335	0
249+00.00	57	868	0
249+50.00	14	1556	0
250+00.00	0	2463	0
250+50.00	0	4175	0
251+00.00	0	6392	0
251+50.00	0	7148	0
252+00.00	0	5684	0
252+50.00	0	3702	0
253+00.00	0	2282	0
253+50.00	0	1477	0
254+00.00	8	1308	0
254+50.00	19	1681	0
255+00.00	11	2745	0
255+50.00	5	2901	0
256+00.00	161	1422	0
256+50.00	823	261	0
257+00.00	1926	0	0
257+50.00	2911	0	0
258+00.00	3489	0	0
258+50.00	3844	0	0
259+00.00	3733	0	0
259+50.00	3169	0	0
260+00.00	2469	0	0
260+50.00	1554	0	0
261+00.00	656	44	0
261+50.00	149	556	0
262+00.00	22	2103	0
262+50.00	0	4496	656

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
263+00.00	0	6213	1652
263+50.00	0	5517	1215
264+00.00	0	4285	291
264+50.00	0	4432	71
265+00.00	0	5787	69
265+50.00	0	6581	112
266+00.00	0	4813	43
266+50.00	0	2668	0
267+00.00	46	1784	0
267+50.00	85	1694	0
268+00.00	67	1905	0
268+50.00	48	2014	0
269+00.00	25	2142	0
269+50.00	5	2358	0
270+00.00	0	2353	0
Station L	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**
270+00.00	0	0	0
270+50.00	0	2240	0
271+00.00	0	1990	0
271+50.00	144	1158	0
272+00.00	1134	295	0
272+50.00	3145	0	0
273+00.00	5439	0	0
273+50.00	7790	0	0
274+00.00	10099	0	0
274+50.00	11893	0	0
275+00.00	12968	0	0
275+50.00	13174	0	0
276+00.00	12460	0	0
276+50.00	11022	0	0
277+00.00	9519	0	0
277+50.00	8353	0	0
278+00.00	7111	0	0
278+50.00	6111	0	0
279+00.00	5565	0	0
279+50.00	5480	0	0
280+00.00	5888	0	0
280+50.00	6381	0	0
281+00.00	6564	0	0
281+50.00	5909	0	0
282+00.00	4272	0	0
282+50.00	1705	15	0
283+00.00	87	1072	0
283+50.00	0	2605	0
284+00.00	0	2848	0
284+50.00	0	2436	0
285+00.00	31	1776	0
285+50.00	130	944	0
286+00.00	480	331	0
286+50.00	1231	29	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
287+00.00	1785	2	0
287+50.00	1659	39	0
288+00.00	1179	502	125
288+50.00	701	1052	206
289+00.00	330	1588	268
289+50.00	106	2115	378
290+00.00	22	2174	294
290+50.00	0	2306	306
291+00.00	0	2392	265
291+50.00	0	2436	278
292+00.00	0	2535	311
292+50.00	0	2318	95
293+00.00	0	1987	0
293+50.00	0	1451	0
294+00.00	69	625	0
294+50.00	685	87	0
295+00.00	1769	0	0
295+50.00	2602	0	0
296+00.00	2886	0	0
296+50.00	2009	0	0
297+00.00	746	55	0
297+50.00	239	320	0
298+00.00	485	442	0
298+50.00	893	255	0
299+00.00	986	136	0
299+50.00	878	151	0
300+00.00	497	363	0
300+50.00	158	941	0
301+00.00	26	1657	0
301+50.00	0	2141	0
302+00.00	0	2566	0
302+50.00	0	3301	0
303+00.00	0	4233	0
303+50.00	0	4566	0
304+00.00	0	4351	0
304+50.00	0	4297	0
305+00.00	0	4193	0
305+50.00	0	3578	0
306+00.00	0	2728	0
306+50.00	0	2147	0
307+00.00	0	2019	0
307+50.00	0	2283	0
308+00.00	0	2629	0
308+50.00	0	2685	0
309+00.00	81	2444	0
309+50.00	194	2115	0
310+00.00	169	1999	0
310+50.00	281	1856	0
311+00.00	518	1454	0
311+50.00	744	1126	0
312+00.00	869	1067	0
312+50.00	787	939	0
313+00.00	994	744	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
313+00.00	0	0	0
313+50.00	332	785	0
314+00.00	414	828	0
314+50.00	460	844	0
315+00.00	451	816	0
315+50.00	320	787	0
316+00.00	126	884	0
316+50.00	11	894	0
317+00.00	6	808	0
317+50.00	15	638	0
318+00.00	9	394	0
318+50.00	0	175	0
319+00.00	0	45	0
319+50.00	0	158	0
320+00.00	103	312	0
320+50.00	204	340	0
321+00.00	197	281	0
321+50.00	170	219	0
322+00.00	139	203	52
322+50.00	174	155	77
323+00.00	310	75	48
323+50.00	427	31	23
324+00.00	457	4	0
324+50.00	470	2	0
325+00.00	516	1	0
325+50.00	609	0	0
326+00.00	687	0	0
326+50.00	735	2	0
327+00.00	644	8	0
327+47.97	504	12	0
Station L RT	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	**UnderCut (cu. yd.)**
313+00.00	0	0	0
313+50.00	1344	0	0
314+00.00	1871	0	0
314+50.00	2199	0	0
315+00.00	2233	0	0
315+50.00	1824	0	0
316+00.00	1226	0	0
316+50.00	615	407	0
317+00.00	250	1090	0
317+50.00	110	1608	0
318+00.00	112	1406	0
318+50.00	142	800	0
319+00.00	84	555	0
319+50.00	215	369	0
320+00.00	1055	135	0
320+50.00	2122	0	0
321+00.00	2414	0	0
321+50.00	2457	0	0
322+00.00	2797	212	212