PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1I

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L(shift)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
30+00.00	35	0
30+50.00	19	6
31+00.00	11	12
31+50.00	9	6
32+00.00	6	0
32+50.00	5	0
33+00.00	4	0