PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1F

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
322+50.00	3050	377	377
323+00.00	2960	350	350
323+50.00	2586	185	185
324+00.00	1984	1	0
324+50.00	1185	4	0
325+00.00	571	7	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
327+50.00	14	0	0
328+00.00	258	17	0
328+50.00	112	76	0
329+00.00	33	194	0
329+50.00	10	286	0
330+00.00	7	306	0
330+50.00	6	282	0
331+00.00	6	234	0
331+50.00	6	209	0
332+00.00	94	180	0
332+50.00	293	114	0
333+00.00	414	80	0
333+50.00	386	90	0
334+00.00	224	162	0
334+50.00	64	290	0
335+00.00	14	494	0
335+50.00	0	1102	218
336+00.00	0	1740	424
336+50.00	0	2030	398
337+00.00	0	2169	354
337+50.00	0	2575	348
338+00.00	0	2405	459

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
341+00.00	0	1787	0
341+50.00	0	4554	487
342+00.00	0	3953	457
342+50.00	0	3567	541
343+00.00	0	3186	605
343+50.00	0	2769	559
344+00.00	0	2134	268
344+50.00	0	1341	0
345+00.00	0	617	0
345+50.00	54	231	0
346+00.00	476	113	0
346+50.00	1383	5	0
347+00.00	2208	0	0
347+50.00	2673	0	0
348+00.00	2918	0	0
348+50.00	2984	0	0
349+00.00	2754	0	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
349+50.00	2017	0	0
350+00.00	1074	0	0
350+50.00	365	225	0
351+00.00	374	568	0
351+50.00	500	642	0
352+00.00	263	557	0
352+50.00	96	451	0
353+00.00	91	229	0
353+50.00	338	82	0
354+00.00	627	95	0
354+50.00	852	99	0
355+00.00	1027	102	0
355+50.00	1123	109	0
356+00.00	1230	118	0
356+50.00	1351	124	0
357+00.00	1359	126	0
357+50.00	1216	118	0
358+00.00	876	133	0
358+50.00	405	242	0
359+00.00	94	319	0
359+50.00	49	255	0
360+00.00	159	173	0
360+50.00	185	124	0
361+00.00	228	119	0
361+50.00	348	143	0
362+00.00	397	145	0
362+50.00	402	139	0
363+00.00	326	139	0
363+50.00	238	144	0
364+00.00	166	139	0
364+50.00	119	121	0
365+00.00	94	98	0
365+50.00	93	70	0
366+00.00	106	40	0
366+50.00	106	25	0
367+00.00	109	15	0
367+50.00	114	3	0
368+00.00	88	0	0
368+50.00	33	0	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
325+00.00	0	0	0
325+50.00	869	6	0
326+00.00	1713	1	0
326+50.00	2164	0	0
327+00.00	2223	0	0
327+50.00	2051	0	0
328+00.00	1719	0	0
328+50.00	1421	0	0
329+00.00	1213	0	0
329+50.00	1059	0	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
330+00.00	885	0	0
330+50.00	690	0	0
331+00.00	534	0	0
331+50.00	362	0	0
332+00.00	197	8	0
332+50.00	100	54	0
333+00.00	48	122	0
333+50.00	22	212	0
334+00.00	4	346	0
334+50.00	0	535	0
335+00.00	0	751	0
335+50.00	0	893	0
336+00.00	0	998	0
336+50.00	0	1146	0
337+00.00	0	1256	0
337+50.00	0	1358	0
338+00.00	0	1881	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
341+00.00	0	452	0
341+50.00	0	1386	231
342+00.00	0	2377	214
342+50.00	0	2008	196
343+00.00	0	1344	82
343+50.00	94	785	0
344+00.00	195	578	0
344+50.00	240	431	0
345+00.00	319	304	0
345+50.00	480	181	0
346+00.00	684	69	0
346+50.00	844	9	0
347+00.00	962	0	0
347+50.00	934	0	0
348+00.00	836	0	0
348+50.00	741	0	0
349+00.00	600	0	0
349+50.00	451	0	0
350+00.00	296	0	0
350+50.00	165	0	0
351+00.00	86	4	0
351+50.00	54	19	0
352+00.00	32	35	0
352+50.00	17	44	0
353+00.00	14	50	0
353+50.00	14	62	0
354+00.00	13	69	0
354+50.00	15	75	0
355+00.00	18	106	0
355+50.00	19	102	0
356+00.00	19	113	0
356+50.00	17	144	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
357+00.00	18	149	0
357+50.00	19	169	0
358+00.00	18	184	0
358+50.00	15	199	0
359+00.00	15	228	0
359+50.00	15	234	0
360+00.00	13	204	0
360+50.00	13	159	0
361+00.00	11	131	0
361+50.00	9	99	0
362+00.00	8	63	0
362+50.00	8	56	0
363+00.00	13	424	0
363+50.00	13	886	0
364+00.00	10	742	0
364+50.00	15	258	0
365+00.00	64	6	0
365+50.00	137	6	0
366+00.00	252	11	0
366+50.00	419	6	0
367+00.00	520	4	0
367+50.00	523	4	0
368+00.00	444	4	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	11	8
15+00.00	22	12
15+50.00	46	14
16+00.00	80	31

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+50.00	0	0
19+00.00	85	34
19+50.00	96	12
20+00.00	37	6

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+50.00	552	0
12+00.00	532	0
12+50.00	457	0
13+00.00	308	0
13+50.00	172	0
14+00.00	99	0
14+50.00	77	0
15+00.00	80	0