PROJ. REFERENCE NO.	SHEET NO.
R-0623	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
140+50.00	8156	0	0
141+00.00	9279	0	0
141+50.00	10630	0	0
142+00.00	12307	0	0
142+50.00	13838	0	0
143+00.00	14872	0	0
143+50.00	15883	0	0
144+00.00	18137	0	0
144+50.00	20455	0	0
145+00.00	21438	0	0
145+50.00	21506	0	0
146+00.00	21108	0	0
146+50.00	21043	0	0
147+00.00	21560	0	0
147+50.00	21382	0	0
148+00.00	19915	0	0
148+50.00	17720	0	0
149+00.00	14923	0	0
149+50.00	12354	0	0
150+00.00	9720	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
150+00.00	0	0	0
150+50.00	6786	0	0
151+00.00	4130	0	0
151+50.00	2119	0	0
152+00.00	1528	138	0
152+50.00	1139	393	0
153+00.00	310	756	0
153+50.00	19	734	0
154+00.00	6	294	0
154+50.00	83	72	0
155+00.00	460	11	0
155+50.00	758	0	0
156+00.00	1369	0	0
156+50.00	3038	0	0
157+00.00	5463	0	0
157+50.00	8113	0	0
158+00.00	10581	0	0
158+50.00	12352	0	0
159+00.00	13473	0	0
159+50.00	14433	0	0
160+00.00	15194	0	0
160+50.00	16176	0	0
161+00.00	17814	0	0
161+50.00	19592	0	0
162+00.00	20641	0	0
162+50.00	18909	0	0
163+00.00	15879	0	0
163+50.00	13645	0	0
164+00.00	11196	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
164+50.00	8953	0	0
165+00.00	6993	0	0
165+50.00	5421	0	0
166+00.00	4274	0	0
166+50.00	3446	0	0
167+00.00	3187	0	0
167+50.00	3835	0	0
168+00.00	5019	0	0
168+50.00	5316	0	0
169+00.00	4417	0	0
169+50.00	3246	0	0
170+00.00	2036	0	0
170+50.00	754	42	0
171+00.00	69	693	0
171+50.00	0	2331	0
172+00.00	0	4102	0
172+50.00	0	4693	0
173+00.00	14	3822	0
173+50.00	110	2186	0
174+00.00	385	856	0
174+50.00	823	346	0
175+00.00	1083	212	0
175+50.00	909	199	0
176+00.00	568	296	0
176+50.00	306	508	0
177+00.00	118	823	0
177+50.00	20	1088	0
178+00.00	1	1240	0
178+50.00	0	1589	0
179+00.00	0	2146	0
179+50.00	0	2561	0
180+00.00	0	2823	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
180+00.00	0	0	0
180+50.00	0	2889	0
181+00.00	0	2808	0
181+50.00	0	2791	0
182+00.00	0	2638	0
182+50.00	0	2120	0
183+00.00	0	1389	0
183+50.00	29	709	0
184+00.00	175	232	0
184+50.00	476	29	0
185+00.00	563	0	0
185+50.00	268	103	0
186+00.00	34	537	0
186+50.00	0	1389	0
187+00.00	0	3179	0
187+50.00	0	6537	416
188+00.00	0	9458	778

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
188+50.00	0	9791	362
189+00.00	0	8346	0
189+50.00	0	6123	0
190+00.00	18	3799	0
190+50.00	240	2158	0
191+00.00	793	1180	0
191+50.00	1611	598	0
192+00.00	2357	265	0
192+50.00	3149	65	0
193+00.00	4168	0	0
193+50.00	4881	0	0
194+00.00	5275	0	0
194+50.00	5834	0	0
195+00.00	6556	0	0
195+50.00	6949	0	0
196+00.00	6668	0	0
196+50.00	6140	0	0
197+00.00	5519	0	0
197+50.00	5001	0	0
198+00.00	4804	0	0
198+50.00	4465	0	0
199+00.00	3813	0	0
199+50.00	2816	0	0
200+00.00	1467	155	0
200+50.00	766	381	0
201+00.00	1498	226	0
201+50.00	2369	0	0
202+00.00	2351	2	0
202+50.00	1967	2	0
203+00.00	1576	59	0
203+50.00	1050	394	0
204+00.00	441	1547	0
204+50.00	66	3159	0
205+00.00	0	3898	0
205+50.00	0	3743	0
206+00.00	0	3420	0
206+50.00	0	3102	0
207+00.00	0	2756	0
207+50.00	0	2460	0
208+00.00	0	2187	0
208+50.00	0	1860	0
209+00.00	0	1489	0
209+50.00	38	1191	0
210+00.00	156	995	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
210+00.00	0	0	0
210+50.00	316	949	0
211+00.00	356	1305	0
211+50.00	247	1534	0
212+00.00	169	1304	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
212+50.00	165	954	0
213+00.00	181	758	0
213+50.00	160	748	0
214+00.00	122	859	0
214+50.00	148	1030	0
215+00.00	219	1119	0
215+50.00	267	1150	0
216+00.00	244	1347	0
216+50.00	169	1865	0
217+00.00	110	2338	0
217+50.00	90	2355	0
218+00.00	71	2177	0
218+50.00	46	2093	0
219+00.00	17	2061	0
219+50.00	0	2097	0
220+00.00	0	2529	0
220+50.00	0	3062	0
221+00.00	0	3276	0
221+50.00	0	3482	0
222+00.00	0	3640	0
222+50.00	0	3752	0
223+00.00	0	3776	0
223+50.00	0	3602	0
224+00.00	0	3400	0
224+50.00	0	3187	0
225+00.00	0	2832	0
225+50.00	0	2406	0
226+00.00	0	1869	0
226+50.00	0	1424	0
227+00.00	0	1371	0
227+50.00	0	1598	0
228+00.00	0	1927	0
228+50.00	0	2253	0
229+00.00	0	2370	0
229+50.00	0	2339	0
230+00.00	0	2234	0
230+50.00	19	1841	0
231+00.00	39	1174	0
231+50.00	151	464	0
232+00.00	413	133	0
232+50.00	678	123	0
233+00.00	854	133	0
233+50.00	928	131	0
234+00.00	923	120	0
234+50.00	904	300	0
235+00.00	968	274	0
235+50.00	1092	46	0
236+00.00	1221	19	0
236+50.00	1261	6	0
237+00.00	1026	1	0
237+50.00	611	75	0
238+00.00	270	266	0
238+50.00	126	512	0