T.I.P.: R-34463AA

CONTRACT: C203520

23-SEP-2014 08:59
R:\TIPP-Projects\R-R4463AA\Traffic\Signing\CADD\Quantities & GM Signs\r4463aa_titledgn
meaton AT TE274922

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

TIP NO.	SHEET NO.
R-4463AA	SIGN-1

APPROVED: DocuSigned by: Ayman Alqudwah F32AC5CAF965472...

DATE: 9/23/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 028387 ENGINEER AYMAN I. ALQUDWAH

SIGNING PLAN
CRAVEN COUNTY

LOCATION: NC 43 CONNECTOR FROM SOUTH OF US 70 TO US 70

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.10	TYPE 'A' SIGNS
901.20	TYPE 'B' SIGNS
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
901.80	SIGN MOUNTING DETAILS - FOR TYPE A AND TYPE B SIGNS
903.10	GROUND MOUNTED SIGN SUPPORTS (SHEET 3 OF 3)
903.20	WOOD SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS
1264.01	OBJECT MARKERS - TYPES
1264.02	OBJECT MARKERS - INSTALLATION

GENERAL NOTES

. SIGNS FURNISHED BY STATE

. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO WOOD POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4054000000	902	PLAIN CONCRETE SIGN FOUNDATION	1	C.Y.
4060000000	903	SUPPORTS, BREAKAWAY STEEL BEAM	334	LB.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL (X-BRACING)	38	L.F.
4082000000	903	SUPPORTS, WOOD	307	L.F.
4102000000	904	SIGN ERECTION, TYPE E	14	EA.
4108000000	904	SIGN ERECTION, TYPE F	3	EA.
4110000000	904	SIGN ERECTION, TYPE A (GROUND MOUNTED)	1	EA.
4110000000	904	SIGN ERECTION, TYPE B (GROUND MOUNTED)	1	EA.
4236000000	907	DISPOSAL OF SIGN, TYPE A (GROUND MOUNTED)	1	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	7	EA.
4158000000	907	DISPOSAL OF SIGN SYSTEM, WOOD	3	EA.
4237000000	907	STOCKPILE SIGN, D, E OR F	28	EA.
4520000000	1266	TUBULAR MARKERS (FIXED), STOCKPILE	29	EA.

PAY ITEM NOTES

1. DISPOSAL SIGN SYSTEM, U-CHANNEL
2. DISPOSAL SIGN SYSTEM, WOOD
3. DISPOSAL OF SIGN, TYPE A (GROUND-MOUNTED)
4. SIGN ERECTION, TYPE A (GROUND-MOUNTED)
5. STOCKPILE SIGN SYSTEM , TYPE D, E, OR F
6. STOCKPILE TUBULAR MARKERS

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-1A & 1B	REVISED ROADWAY STANDARD DRAWINGS
SIGN-2	SIGN SUPPORT CHART
SIGN-3 & 3A	SIGN DESIGNS, TYPE E AND F SIGNS
SIGN-4 Thru 6	SIGNING PLAN SHEETS

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

A. I. ALQUDWAH, P.E. SIGNING & DELINEATION REGIONAL ENGINEER

D. M. EATON SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

3-Way Checked
09/23/2014
DME,EEW,BN