PROJ. REFERENCE NO.	SHEET NO.
B-4803	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00	0	0
10+50.00	20	7
10+75.00	67	12
11+00.00	133	12
11+25.00	205	12
11+50.00	251	9
11+75.00	291	6
12+00.00	329	4
12+25.00	320	5
12+50.00	312	6
12+75.00	364	7
13+00.00	385	9
13+25.00	318	11
13+50.00	201	19
13+75.00	109	57
14+00.00	42	121
14+25.00	0	227
14+50.00	0	364
14+75.00	0	474
15+00.00	0	555
15+06.31	0	149

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+03.69	0	0
17+25.00	0	533
17+50.00	0	472
17+75.00	148	164
18+00.00	453	5
18+25.00	684	12
18+50.00	784	20
18+75.00	872	15
19+00.00	940	13
19+25.00	942	12
19+50.00	929	6
19+75.00	937	1
20+00.00	940	0
20+25.00	888	0
20+50.00	789	0
20+75.00	683	4
21+00.00	596	11
21+25.00	525	11
21+50.00	455	7
21+75.00	380	10
22+00.00	314	14
22+25.00	246	17
22+50.00	227	16
22+75.00	239	10
23+00.00	206	9
23+25.00	163	8
23+50.00	123	10
23+75.00	98	11

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+00.00	79	9
24+25.00	57	6
24+50.00	44	6
24+75.00	45	8
25+00.00	52	7
25+25.00	49	6
25+50.00	45	15
25+75.00	44	28
26+00.00	47	31
26+25.00	25	15

Station Drv1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+15.00	0	0
10+40.00	3	5
10+50.00	6	1
10+60.00	12	0
10+63.67	4	0
10+65.00	1	0

Station Drv2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+15.00	0	0
10+30.00	7	3
10+40.00	6	1
10+50.00	7	1
10+57.42	4	0
10+60.00	1	0