

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

SUMMARY OF PAVEMENT REMOVAL

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	SY
-TIE-	17+91.00	25+18.64	CL	636
-L-	467+12.00	471+45.00	RT	188
-L-	472+32.00	474+71.00	LT	31
-Y27-	16+14.50	18+10.00	RT	456
-Y27B-	11+34.00	12+70.00	RT	177
-Y27C-	10+36.50	11+33.50	RT	180
-L-	478+51.00	484+50.25	RT	316
-L-	490+53.00	498+20.00	RT	269
-L-	500+35.00	506+35.95	RT	135
-Y28-	17+00.00	17+68.00	LT	110
-Y29-	10+35.00	12+04.00	RT	602
-L-	512+45.00	513+40.00	CL	243
-L-	515+33.00	523+47.50	RT	375
-L-	529+53.00	553+20.80	RT	1862
-L-	563+94.15	577+73.00	LT	1880
-L-	579+66.00	585+07.10	RT	211
-L-	591+03.00	625+08.00	CL	3739
-L-	630+90.95	648+85.00	LT	1229
-L-	654+66.50	660+09.45	LT	327
-Y32-	22+83.50	28+56.00	CL	1283
-L-	666+68.00	669+48.25	CL	199
-L-	670+36.55	676+29.00	LT	302
TEMP. PAVEMENT	FROM TRAFFIC CONTROL UNIT			3750
TOTAL:				18,500
SAY:				18,500

**SUMMARY OF WOVEN WIRE FENCE
 & BARBED WIRE FENCE**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	LENGTH (FT)	END BRACE (EACH)	CORNER BRACE (EACH)	LINE BRACE (EACH)	4" POSTS (EACH)	5" POSTS (EACH)
-TIE- /-Y27C-	17+07.48	12+74.99	RT	2,126.20	2	5	7	131	39
-L-	459+27.60	475+10.61	LT	1,650.20	2	7	5	96	40
-L- /-Y28-	476+44.54	16+95.27	LT	3,522.50	2	10	11	215	67
-Y27C- /-L-	12+53.88	510+72.45	RT	3,300.40	2	3	10	212	44
-L-	512+37.02	569+41.02	LT	5,704.00	2	23	18	339	126
-L-	515+47.40	577+57.25	RT	6,209.85	2	6	19	400	79
-L-	569+73.55	659+63.04	LT	8,989.50	2	18	28	565	141
-L-	578+26.15	625+02.45	RT	4,676.30	2	8	14	295	71
-L-	626+47.45	648+66.80	RT	2,219.35	2	4	7	139	37
-L-	650+46.84	662+42.16	RT	1,195.30	2	5	4	69	30
-L-	662+65.00	663+78.08	RT	113.10	2	1	0	4	8
-L-	660+18.02	664+93.78	LT	545.75	2	3	2	29	18
-Y32- /-L-	24+24.18	679+81.92	RT	1,418.85	2	3	4	87	26
-L-	668+34.86	680+45.00	LT	1,210.15	2	2	4	75	21
TOTAL:				42,881.45				2,655	747
SAY:				42,900				2,660	750
ADDITIONAL BARBED WIRE (CONTINGENCY)				2,000					
TEMP. 4 STRAND BARBED WIRE FENCE (CONTINGENCY)									
-L-	472+00	473+00	LT	100					
-L-	539+00	545+00	LT	600					
TOTAL:				700					
SAY:				1,000					

SUMMARY OF EXPRESSWAY GUTTER

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	LENGTH (FT)
-L-	514+00.00	516+00.00	LT	200.0
TOTAL:				200.0
SAY:				200

SUMMARY OF SHOULDER BERM GUTTER

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	LENGTH (FT)
-L-	535+95.00	545+75.00	LT	980.0
-L-	562+25.00	565+95.00	RT	370.0
-L-	584+50.00	588+71.00	LT	421.0
-L-	610+65.00	624+82.00	RT	1,417.0
-L-	660+00.00	665+00.00	LT	500.0
TOTAL:				3,688.0
SAY:				3,690

5/28/99
 24-NOV-2014 08:52
 K:\2014\11\07\2915D\Roadway\Proj\R2915D_Rdwy_sum.dgn