PROJ. REFERENCE NO.	SHEET NO.
R2915-D	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

The cross sections reflect the aggregate base course alternate 1

Note: Embankment column does not include backfill for undercut

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Station -L- LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
670+00.00	61	29
670+50.00	73	32
671+00.00	162	29
671+50.00	291	30
672+00.00	382	44
672+50.00	393	55
673+00.00	329	51
673+50.00	231	52
674+00.00	101	53
674+50.00	22	46
675+00.00	9	40
675+50.00	7	26
676+00.00	7	11
676+29.00	4	3

Station -L- RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
661+00.00	0	0
661+50.00	0	2935
662+00.00	0	2074
662+50.00	0	2027
663+00.00	0	1901
663+50.00	1	1662
664+00.00	1	1568
664+50.00	0	1208
665+00.00	1	499
665+50.00	3	44
666+00.00	3	33
666+50.00	17	219
667+00.00	180	310
667+50.00	299	262
668+00.00	232	371
668+50.00	97	544
669+00.00	0	628
669+50.00	0	544
670+00.00	0	413
670+50.00	0	312
671+00.00	0	264
671+50.00	0	223
672+00.00	27	149
672+50.00	122	85
673+00.00	282	65
673+50.00	494	59
674+00.00	697	59
674+50.00	769	57
675+00.00	506	65
675+50.00	134	106
676+00.00	7	180
676+29.00	1	129

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
676+29.00	0	0
676+50.00	2	152
677+00.00	22	239
677+50.00	39	94
678+00.00	67	69
678+50.00	115	73
679+00.00	155	78
679+50.00	179	54
679+90.00	80	19

Station -Y27-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+65.00	0	0
15+00.00	5	5
15+50.00	6	15
16+00.00	22	38
16+50.00	19	87
17+00.00	0	116
17+50.00	0	257
18+00.00	0	695
18+50.00	0	819
18+53.39	0	44

Station -Y27A-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+50.00	0	108
11+00.00	0	104
11+50.00	1	34
11+70.00	1	1

Station -Y27B-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+90.00	0	0
11+00.00	0	0
11+50.00	686	3
12+00.00	1747	4
12+50.00	1649	17
12+83.78	793	20

Station -Y27C-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+36.83	0	0
10+50.00	0	3
11+00.00	0	13
11+50.00	7	12
12+00.00	8	7

Station -Y28-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+15.00	0	0
16+50.00	1	30
17+00.00	1	219
17+50.00	0	936
17+82.70	0	976

Station -Y29-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+36.03	0	0
10+50.00	0	6
11+00.00	0	69
11+50.00	0	77
12+00.00	6	20
12+50.00	7	4
12+60.00	0	1

Station -Y30-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+35.51	0	0
10+50.00	5	211
11+00.00	10	368

Station -Y31-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+35.98	0	0
10+50.00	0	7
11+00.00	1	16
11+50.00	2	7
11+65.00	1	3

Station -Y32-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+45.00	0	0
15+50.00	0	1
16+00.00	0	91
16+30.00	5	143
16+50.00	6	134
17+00.00	14	419
17+50.00	16	453
18+00.00	16	449
18+50.00	15	519
19+00.00	19	724
19+50.00	19	978
20+00.00	12	1147
20+50.00	4	1214
21+00.00	8	1056
21+50.00	17	900

Station -Y32-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+50.00	0	0
23+00.00	6	857
23+50.00	51	1182
24+00.00	129	1184
24+50.00	209	1165
25+00.00	244	1013
25+50.00	315	807
26+00.00	214	655
26+50.00	24	606
27+00.00	7	514
27+50.00	7	379
28+00.00	19	296
28+50.00	30	248
29+00.00	34	144
29+50.00	30	46
29+90.00	15	10

Station -Drv1-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+47.50	0	0
10+50.00	0	3
11+00.00	0	31
11+50.00	1	9
11+80.00	1	3