STANDARD MILEMARKER DESIGN



INSTALLATION NOTE:
INSTALL ON 3 LB. U-CHANNEL POST 4' ABOVE EDGE OF TRAVEL LANE (EDGELINE) ELEVATION. INSTALL AT SHOULDER POINT OR MAX OF 15' FROM EDGE OF TRAVEL LANE, UNLESS OTHERWISE APPROVED BY ENGINEER.

TIP NO.	SHEET NO.
I-0914BA	SIGN-4KK

APPROVED: DocuSigned by: Charles A. Johnson, III 59A15658B47F54A8...

DATE: 11/4/2014

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20675 ENGINEER CHARLES A. JOHNSON III

SOUTH 1 MILE 147 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 150 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 152 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 155 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 148 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 150 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 153 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 155 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 148 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 151 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 153 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 149 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 151 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 154 — 18" X 54" — ONE "U" POST PER SIGN

NOTE: NCDOT TO FIELD LOCATE MILEMARKERS ALONG US-1

SOUTH 1 MILE 149 .5 — 18" X 60" — ONE "U" POST PER SIGN

SOUTH 1 MILE 152 — 18" X 54" — ONE "U" POST PER SIGN

SOUTH 1 MILE 154 .5 — 18" X 60" — ONE "U" POST PER SIGN

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

US-1 MILEMARKERS (SOUTHBOUND DIRECTION)