PROJ. REFERENCE NO.	SHEET NO.
I-0914BB	TMP-1A

NCDOT ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.01	WORK ZONE WARNING SIGNS
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.04	TEMPORARY SHOULDER CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1115.01	FLASHING ARROW BOARDS
1130.01	DRUMS
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGING DEVICES
1160.01	TEMPORARY CRASH CUSHION
1165.01	WORK VEHICLE LIGHTING SYSTEMS AND TMA DELINEATION
1170.01	POSITIVE PROTECTION
1180.01	SKINNY - DRUM
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS
1205.03	PAVEMENT MARKINGS - EXITS AND ENTRANCE RAMPS
1205.06	PAVEMENT MARKINGS - LANE DROPS
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.12	PAVEMENT MARKINGS - BRIDGES
1205.13	PAVEMENT MARKINGS - LANE REDUCTIONS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - (PERMANENT AND TEMPORARY)
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

VDOT TRAFFIC CONTROL STANDARD DRAWINGS

THE FOLLOWING TRAFFIC CONTROL STANDARD DRAWINGS AS SHOWN IN THE "VIRGINIA WORK AREA PROTECTION MANUAL" ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS: (REFER TO THE ROADWAY DESIGN PLANS FOR STANDARD DRAWINGS APPLICABLE TO ROADWAY DESIGN)

STD. NO.	TITLE
TTC - 16.0	OUTSIDE LANE CLOSURE OPERATION ON A FOUR-LANE ROADWAY
TTC - 17.0	INSIDE LANE CLOSURE OPERATION ON A FOUR-LANE ROADWAY
TTC - 19.0	LANE CLOSURE OPERATION WITH LANE WEAVE
TTC - 44.0	MEDIAN CROSS-OVER OPERATION ON A MULTI-LANE ROADWAY
TTC - 52.0	SIGNING FOR SPEED LIMIT AND FINE SIGNS IN WORK ZONES

LEGEND

GENERAL

- DIRECTION OF TRAFFIC FLOW
- DIRECTION OF PEDESTRIAN TRAFFIC FLOW
- EXIST. PVMT.
- NORTH ARROW
- PROPOSED PVMT.
- TEMP. SHORING (LOCATION PURPOSES ONLY)
- WORK AREA
- ONGOING CONSTRUCTION
- REMOVAL
- TEMPORARY PAVEMENT
- PAVEMENT WEDGING

PAVEMENT MARKINGS

- EXISTING LINES
- TEMPORARY LINES

TRAFFIC CONTROL DEVICES

- BARRICADE (TYPE III)
- CONE
- DRUM — SKINNY DRUM — TUBULAR MARKER
- TEMPORARY CRASH CUSHION
- FLASHING ARROW BOARD
- FLAGGER
- LAW ENFORCEMENT
- TRUCK MOUNTED ATTENUATOR (TMA)
- CHANGEABLE MESSAGE SIGN

TEMPORARY SIGNING

- PORTABLE SIGN
- STATIONARY SIGN
- STATIONARY OR PORTABLE SIGN

PAVEMENT MARKERS

- CRYSTAL/CRYSTAL
- CRYSTAL/RED
- YELLOW/YELLOW

PAVEMENT MARKING SYMBOLS

- PAVEMENT MARKING SYMBOLS

TEMPORARY PAVEMENT MARKING

PAVEMENT MARKINGS-PAINT(6")
P6 WHITE EDGE LINE
P7 YELLOW EDGELINE
PJ 10 FT. WHITE SKIP
PK 3 FT. - 9 FT./SP WHITE MINISKIP

PAVEMENT MARKINGS-PAINT(12")
PS WHITE GORELINE

COLD APPLIED PLASTIC-(6")
C6 WHITE EDGE LINE
C7 YELLOW EDGELINE
CJ 10 FT. WHITE SKIP
CK 3 FT. - 9 FT./SP WHITE MINISKIP

COLD APPLIED PLASTIC-(12")
CS WHITE GORELINE

COLD APPLIED PLASTIC-(24")
C2 WHITE STOP BAR

MARKING SYMBOLS-PAINT
QP MERGE ARROW

MARKING SYMBOLS-COLD APPLIED PLASTIC
DP MERGE ARROW

APPROVED DocuSigned by: James Parker DATE: 12/19/2014
SEAL COMMONWEALTH OF VIRGINIA JAMES W. PARKER, JR. Lic.No. 041505 PROFESSIONAL ENGINEER

APPROVED DocuSigned by: Tim Arey DATE: 12/18/2014
SEAL NORTH CAROLINA PROFESSIONAL SEAL 025465 ENGINEER TIM AREY

PLAN PREPARED IN THE OFFICE OF:
PROGRESSIVE DESIGN GROUP, INC.
ENGINEERS • CONSULTANTS

DIVISION OF HIGHWAYS • STATE OF NORTH CAROLINA • DEPARTMENT OF TRANSPORTATION • WORK ZONE TRAFFIC CONTROL

ROADWAY STANDARD DRAWINGS & LEGEND