PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10911.14	6	
5CR.20911.14		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	1.25" MILLING SY	0" TO 1.5" MILLING SY	0" TO 1.25" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
5CR.10911.14	Vance	1	US 158 BYP	I-85 TO GRANVILLE CO LINE	1,4	2		NO	NO	4.7	24-78	940	235	11.00	625		845		2,470	9,253		555	100		2	820	2,050	8.20	6,000
5CR.10911.14	Vance	2	US 158 BUS	GRANVILLE CO LINE TO BEGINNING OF CURB AND GUTTER	1	2		NO	NO	4.5	24-60	900	270	9.00					2,150	6,214		373	150	4	6	652	1,630	6.53	1,195
TOTAL FOR PROJ NO. 5CR.10911.14										**9.2**		**1,840**	**505**	**20.00**	**625**		**845**		**4,620**	**15,467**		**928**	**250**	**4**	**8**	**1,472**	**3,680**	**14.73**	**7,195**
5CR.20911.14	Vance	3	SR 1549 - BOBBITT RD	SR 1548 - PETER GILL RD TO FRANKLIN CO LINE	3	2	2WU	NO	NO	4.4	22	880	220	8.80	56,789				600	5,037		302	65			638	1,600	6.38	
5CR.20911.14	Vance	4	SR 1595 - EASTERN MINERALS RD	US 1 BUS - RALEIGH RD TO SR 1609 - COMMERCE RD	1	2	2WU	NO	NO	0.3	24	60	15	0.60					200	374		22	40			44	110	0.44	
5CR.20911.14	Vance	5	SR 1609 - COMMERCE RD	SR 1115 - BEARPOND RD TO SR 1548 - PETER GILL RD	1	2	2WU	NO	NO	1	28	200	50	2.00					400	1,455		87	75			145	370	1.45	
5CR.20911.14	Vance	6	SR 1001 - WARRENTON RD	WARREN CO LINE TO US-1 BUS	2	2	2WU	NO	NO	5.4	22-36	1,080	270	10.80		314		267	1,484		5,530	370	50			841	2,110	7.83	
TOTAL FOR PROJ NO. 5CR.20911.14										**11.1**		**2,220**	**555**	**22.20**	**56,789**	**314**		**267**	**2,684**	**6,866**	**5,530**	**781**	**230**			**1,668**	**4,190**	**16.10**	
GRAND TOTAL										**20.3**		**4,060**	**1,060**	**42.20**	**57,414**	**314**	**845**	**267**	**7,304**	**22,333**	**5,530**	**1,709**	**480**	**4**	**8**	**3,140**	**7,870**	**30.83**	**7,195**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	4721000000-E THERMO RXR 120 M EA	4721000000-E THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO MERGE ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4900000000-N YELLOW & YELLOW MARKERS EA	4900000000-N CRYSTAL & RED MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS EA
5CR.10911.14	Vance	1	US 158 BYP	I-85 TO GRANVILLE CO LINE	1,4	2		4.7	24-78	527	0.23	50,572	9,440	40,967	3,820	995			735	4			31	30	6	15	4			25	60	535
5CR.10911.14	Vance	2	US 158 BUS	GRANVILLE CO LINE TO BEGINNING OF CURB AND GUTTER	1	2		4.5	24-60	504	0.22	48,420		29,700	1,820		276		275				12	6		7	2					440
TOTAL FOR PROJ NO. 5CR.10911.14								**9.2**		**1,031**	**0.45**	**98,992**	**9,440**	**70,667**	**5,640**	**995**	**276**		**1,010**	**4**			**43**	**36**	**6**	**22**	**6**			**25**	**60**	**975**
												108,432		**76,307**		**1,271**				**4**			**113**							**85**		
5CR.20911.14	Vance	3	SR 1549 - BOBBITT RD	SR 1548 - PETER GILL RD TO FRANKLIN CO LINE	3	2	2WU	4.4	22	493	0.21	47,344		29,040	45													47,389	29,040			
5CR.20911.14	Vance	4	SR 1595 - EASTERN MINERALS RD	US 1 BUS - RALEIGH RD TO SR 1609 - COMMERCE RD	1	2	2WU	0.3	24	56	0.01	3,228		1,980	15			100	50		4											
5CR.20911.14	Vance	5	SR 1609 - COMMERCE RD	SR 1115 - BEARPOND RD TO SR 1548 - PETER GILL RD	1	2	2WU	1	28	112	0.05	10,760		6,600	30			100	50		4											
5CR.20911.14	Vance	6	SR 1001 - WARRENTON RD	WARREN CO LINE TO US-1 BUS	2	2	2WU	5.4	22-36	650	0.28	58,104		35,640	105		135	100	150		4	12	8							420		
TOTAL FOR PROJ NO. 5CR.20911.14								**11.1**		**1,311**	**0.55**	**119,436**		**73,260**	**195**		**135**	**300**	**250**		**12**	**12**	**8**					**47,389**	**29,040**	**420**		
												119,436		**73,455**		**135**				**24**			**8**					**76,429**		**420**		
GRAND TOTAL								**20.3**		**2,342**	**1.00**	**218,428**	**9,440**	**143,927**	**5,835**	**995**	**411**	**300**	**1,260**	**4**	**12**	**12**	**51**	**36**	**6**	**22**	**6**	**47,389**	**29,040**	**445**	**60**	**975**
												227,868		**149,762**		**1,406**				**28**			**121**					**76,429**		**505**		