PROJ. REFERENCE NO.	SHEET NO.
U-5305	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, Borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
9+00.00	0	0
9+50.00	2	12
9+75.00	3	11
10+00.00	12	20
10+50.00	47	84
11+00.00	29	89
11+50.00	17	47
12+00.00	34	20
12+20.00	21	2
12+50.00	65	2
13+00.00	97	5
13+50.00	45	5
14+00.00	43	0
14+50.00	44	0
15+00.00	104	0
15+50.00	283	0
16+00.00	426	0
16+50.00	405	3
17+00.00	281	7
17+50.00	133	6
18+00.00	36	25
18+50.00	5	116
19+00.00	3	157
19+50.00	1	99
20+00.00	20	66
20+50.00	24	71
21+00.00	16	41
21+50.00	11	0
22+00.00	0	0
22+50.00	7	6
22+68.54	4	7

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+80.00	0	0
11+00.00	3	12
11+50.00	22	27
12+00.00	25	25
12+50.00	19	20
13+00.00	26	4
13+50.00	82	1
14+00.00	121	3
14+50.00	87	5
15+00.00	111	2
15+50.00	156	0
16+00.00	86	2
16+50.00	12	9
17+00.00	9	29
17+35.00	6	43
17+50.00	2	19
17+75.00	3	89
18+00.00	4	144

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+50.00	6	343
19+00.00	6	499
19+50.00	6	454
20+00.00	6	298
20+50.00	6	135
21+00.00	6	17
21+50.00	10	22
22+00.00	17	21
22+50.00	27	26
23+00.00	46	28
23+50.00	31	15
24+00.00	4	0
24+50.00	3	0
25+00.00	4	36
25+50.00	6	101
26+00.00	7	120
26+50.00	8	83
27+00.00	10	81
27+29.50	5	47

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+60.00	0	0
18+00.00	24	100
18+50.00	27	103
19+00.00	26	98
19+50.00	25	47
20+00.00	22	0
20+50.00	18	0
21+00.00	19	55
21+50.00	28	107
22+00.00	33	58
22+50.00	29	26
23+00.00	20	29
23+50.00	25	77
24+00.00	30	119
24+50.00	28	119
25+00.00	36	116
25+50.00	12	86
26+00.00	11	51
26+50.00	11	20
27+00.00	15	11
27+10.00	5	2

Station Ey1A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+25.00	37	0
10+50.00	59	16
10+75.00	21	30
11+00.00	19	28
11+25.00	18	26
11+50.00	8	25
11+75.00	0	45
12+00.00	0	94
12+25.00	0	153
12+50.00	0	231
12+75.00	0	317
13+00.00	0	420
13+25.00	0	575
13+50.00	0	682
13+75.00	0	562
14+00.00	0	322