PROJECT REFERENCE NO.	SHEET NO.
I-5308	1A

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 016378 ENGINEER REKHA V. PATEL

1/30/2015

DocuSigned by:

Rekha V. Patel

1BCF DEA8A8A0DE...

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A	INDEX OF SHEETS
2A-1 THRU 2A-2	TYPICAL SECTIONS
2B-1	DETAIL NO. 6 FOR PAVING LIMITS AT RAMPS DETAIL NO. 7 FOR PAVING LIMITS AT LOOPS
2C-1	SHOULDER WEDGE DETAILS
TMP-1 THRU TMP-6	TRANSPORTATION MANAGEMENT PLANS
PMP-1	PAVEMENT MARKING PLANS
EC-1 THRU EC-2	EROSION CONTROL PLANS
S-1 THRU S-23	BRIDGE PRESERVATION PLANS

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012
REVISED: 10-31-2014

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

EFF. 01-17-2012
REV. 10-30-2012

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
	DIVISION 6 - ASPHALT BASES AND PAVEMENTS
665.01	Asphalt Shoulders - Milled Rumble Strips
	DIVISION 8 - INCIDENTALS
866.01	Chain Link Fence - 4', 5' and 6' High Fence
866.02	Woven Wire Fence - with Wood Post

5/28/99

30-JAN-2015 14:02
R:\CERROPL\Proj\15308_rdy_tsh.dgn
$$$$USERNAME$$$$