PROJECT REFERENCE NO.	SHEET NO.
B-4972	EC-3A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	26+00	29+00	RT	415
4	-L-	27+00	29+00	LT	165
				SUBTOTAL	580
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					5850
				TOTAL	6430
				SAY	6500

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	17+00	15+50	LT	205
4	-L-	16+00	15+50	RT	90
4	-L-	25+50	27+00	LT	135
				SUBTOTAL	430
		ADDITIONAL PSRM TO BE INSTALLED			75
				TOTAL	505
				SAY	550