

†2:1 SLOPE—

*78M STONE —— BACKFILL

CEOTEXTILE -

3'-0"

BARS

11/2:1 SLOPE
OR STEEPER
(TO BE DETERMINED
BY THE CONTRACTOR)

4" Ø PERFORATED —

SCHEDULE 40 PVC PIPE

SECTION THROUGH SLAB

ROCK PLATED REINFORCED SOIL SLOPE IS REQUIRED BELOW CAP AT END BENT 1. SEE PROJECT SPECIAL PROVISIONS AND REINFORCED SOIL SLOPE DRAWINGS IN ROADWAY PLANS.

-2 LAYERS OF 30 LB. __ ROOFING FELT TO __ PREVENT BOND

11/2" FORMED OPENING

NOTES

APPROACH SLABS SHALL BE POURED AFTER CONCRETE WEARING SURFACE IS POURED.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE JOINT SHALL BE SAWED AFTER THE CASTING OF THE BARRIER RAIL. FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, 4" Ø DRAINAGE PIPE, AND *78M STONE BACKFILL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.

*78M STONE BACKFILL (CLASS V SELECT MATERIAL) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

*78M STONE BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB. FOR THE 4" Ø DRAINAGE PIPE OUTLET(S), SEE ROADWAY STANDARD DRAWINGS.

FOR FOAM JOINT SEALS, SEE SPECIAL PROVISIONS.


WITH FOAM JOINT SEAL

THE NOMINAL UNCOMPRESSED SEAL WIDTH OF THE FOAM JOINT SEAL SHALL SHALL BE 2"@ END BENT 1 AND @ END BENT 2 AND $2\frac{1}{2}$ "@ BENT 2.

ARC OFFSETS ARE NEGLIGIBLE AND NOT SHOWN AT END BENT 2.

BILL OF MATERIAL								
APPROACH SLAB AT EB 1								
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT			
* A1	24	# 4	STR	18'-3"	293			
A2	26	* 4	STR	18'-2"	316			
∗ B1	70	# 5	STR	10'-10"	791			
B2	70	#6	STR	11'-8"	1227			
REINF	ORCIN	G STEE	L	LBS.	1543			
* EPOXY COATED REINFORCING STEEL LBS. 108								
CLASS AA CONCRETE C.Y. 18.2								
APPROACH SLAB AT EB 2								
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT			
* A1	24	#4	STR	18'-3"	293			
A2	26	#4	STR	18'-2"	316			
∗ B1	70	# 5	STR	10'-10"	791			
B2	70	#6	STR	11'-8"	1227			
REINF	ORCIN	G STEE	LBS.	1543				
	XY CO NFORC	ATED ING ST	LBS.	1084				
CLASS AA CONCRETE C. Y. 18.2								

SPLICE LENGTHS					
BAR SIZE	EPOXY COATED	UNCOATE			
#4	2'-0"	1'-9"			



—Docusigned by: Vipul d. Patel

-339B086CBE1C486... 4/22/2015

PROJECT NO. B-4972 CABARRUS COUNTY 22+55.00 -L-STATION:

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD

BRIDGE APPROACH SLAB FOR PRESTRESSED CONCRETE BOX BEAM UNIT (SUB-REGIONAL TIER)

	SHEET NO.					
NO.	BY:	DATE:	NO.	BY:	DATE:	S-30
1			3			TOTAL SHEETS
2			4			31

21-APR-2015 09:25 R:\Structures\Plans\B4972_SD_AS_01.dgn

-APPROVED WIRE BAR SUPPORTS @ 3'-0"CTS.

† NORMAL TO END BENT

ROADWAY

DATE : 7-3-14

MAA/GM

MAA/GM MAA/GM

DATE : 7-10-14

ASSEMBLED BY : N.D'AIUTO CHECKED BY : P.S. ADKINS

DRAWN BY: KMM 3-08 REV.10/1/11 REV.12/21/11 REV. 6/13