

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

**SHOULDER BERM
 GUTTER SUMMARY**

SURVEY LINE	LOC.	STATION	STATION	LENGTH
-L-	LT	317+37.00	319+30.20	193.20
-L-	LT	321+02.42	-Y3LPA- 11+26	126.60
-L-	LT	356+61.00	362+83.73	622.73
-L-	LT	364+25.63	370+41.00	615.37
-L-	LT	375+64.00	383+04.95	740.95
-L-	LT	395+90.00	399+20.00	330.00
-L-	LT	420+42.00	427+98.35	756.35
-L-	LT	429+42.29	442+24.00	1,281.71
-L-	LT	519+30.00	524+24.40	494.40
-L-	LT	526+95.00	535+32.00	837.00
-L-	RT	311+54.00	319+76.71	822.71
-L-	RT	321+45.89	321+80.00	34.11
-L-	RT	356+12.00	362+52.37	640.37
-L-	RT	363+94.37	370+41.00	646.63
-L-	RT	375+64.00	383+04.95	740.95
-L-	RT	395+90.00	403+55.00	765.00
-L-	RT	419+95.00	427+68.41	773.41
-L-	RT	429+12.35	442+14.00	1,301.65
-L-	RT	518+15.00	526+47.07	832.07
-L-	RT	529+17.66	536+50.00	732.34
-L-	RT	553+15.00	560+49.67	734.67
-L-	RT	561+85.38	569+06.00	720.62
-L-	RT	620+60.00	623+57.80	297.80
-L-	RT	626+55.30	628+05.00	149.70
-Y10-	LT	26+80.00	27+13.57	33.57
-Y10-	LT	29+47.11	30+00.00	52.89
-Y10-	RT	26+42.00	27+17.90	75.90
-Y10RPA-	RT	15+72.00	18+11.76	239.76
-Y10RPA-	RT	37+51.38	38+02.02	50.64
TOTAL:				15643.10
SAY:				15700

**SUMMARY OF REMOVAL
 EXISTING ASPHALT PAVEMENT**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	SY
-Y3A- TO -Y3RPA-	14+86	25+68	LT/RT	348.67
-Y3LPA-	17+51	20+90	LT/RT	607.78
-Y8-	29+93	31+13	LT/RT	237.89
-Y10-	17+00	18+34	LT	606.44
TOTAL:				1,800.78
SAY:				1,810

**PRECAST REINFORCED
 CONCRETE BARRIER, SINGLE FACED**

SURVEY LINE	LOCATION LT/RT/CL	STATION	STATION	LENGTH
-L-	RT	611+19.00	612+19.00	100.00
-L-	LT	611+19.00	612+19.00	100.00
-Y6-	RT	14+40.00	16+96.00	256.00
-Y6-	LT	15+20.00	17+75.00	255.00
TOTAL:				711.00
SAY:				720

5/28/99
 3/17/2015
 P:\62501\Cadd\2514D\Roadway\Proj\2514D_Rdy_sum.dgn
 thurman