PROJ. REFERENCE NO.	SHEET NO.
R-2514D	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
598+50.00	0	1240	0
599+00.00	0	1265	0
599+21.00	0	540	0
599+50.00	0	749	0
600+00.00	0	1276	0
600+18.45	0	458	0
600+50.00	0	739	0
601+00.00	0	1100	0
601+50.00	0	1045	0
602+00.00	0	965	0
602+50.00	0	858	0
603+00.00	0	832	0
603+50.00	0	1121	0
604+00.00	0	1658	0
604+50.00	0	2096	0
605+00.00	0	2061	0
605+50.00	0	1853	0
605+86.33	0	1294	0
606+00.00	0	467	0
606+50.00	0	1604	0
607+00.00	0	1671	0
607+50.00	0	1836	0
608+00.00	0	1732	0
608+50.00	0	1701	0
609+00.00	0	1808	0
609+50.00	0	1911	0
610+00.00	0	2050	0
610+50.00	0	2218	0
611+00.00	0	2383	0
611+50.00	0	2462	0
612+00.00	0	2307	0
612+50.00	0	2031	0
613+00.00	0	1833	0
613+50.00	0	1739	0
613+68.45	0	649	0
614+00.00	0	1169	0
614+50.00	0	2099	0
615+00.00	0	2414	0
615+50.00	229	2496	0
616+00.00	604	2489	0
616+50.00	791	1963	0
617+00.00	842	1312	0
617+50.00	1191	1106	0
618+00.00	1409	854	0
618+50.00	1167	628	0
619+00.00	943	448	0
619+50.00	754	277	0
620+00.00	591	220	0
620+50.00	497	155	0
620+95.72	358	145	0
621+50.00	358	145	0
622+00.00	267	248	0
622+50.00	213	286	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
623+00.00	181	266	0
623+50.00	8	59	0
623+92.45	28	347	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
626+41.79	0	0	0
626+75.72	23	240	0
627+00.00	16	117	0
627+50.00	35	198	0
628+00.00	34	122	0
628+50.00	31	56	0
629+00.00	32	33	0
629+50.00	31	212	0
629+75.72	9	185	0
630+06.50	4	198	0
630+50.00	13	266	0
631+00.00	22	272	0
631+50.00	21	214	0
632+00.00	21	176	0
632+50.00	20	172	0
633+00.00	20	169	0
633+50.00	20	154	0
634+00.00	20	120	0
634+50.00	21	89	0
635+00.00	23	66	0
635+50.00	24	57	0
635+62.27	6	13	0
636+00.00	11	36	0
636+50.00	7	38	0
636+95.00	3	13	0

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+50.00	0	0	0
15+00.00	0	0	0
15+50.00	0	0	0
16+00.00	0	0	0
16+50.00	0	0	0
17+00.00	0	0	0
17+50.00	0	0	0
18+00.00	0	0	0
18+50.00	0	0	0
19+00.00	0	0	0
19+50.00	1	3	0
19+94.00	8	24	10
20+50.00	8	19	35
21+00.00	2	0	37
21+50.00	3	0	12
22+02.00	8	44	18
22+50.00	10	78	19

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
23+02.00	17	71	66
23+50.00	19	43	77
24+02.00	10	15	63
28+00.00	0	0	0
28+50.00	155	7	0
29+00.00	155	1	0
29+50.00	131	0	0
30+00.00	114	0	0
30+50.00	56	1	0
30+65.00	1	0	0
31+00.00	5	1	25
31+22.56	5	3	8
31+25.00	1	1	2
31+50.00	6	2	15
32+00.00	11	0	25
32+50.00	15	0	24
33+00.00	15	0	25
33+34.00	29	2	55
33+50.00	21	2	44
33+94.00	45	3	103
34+34.00	58	0	117
34+50.00	8	0	29
35+00.00	38	5	64
35+34.00	9	5	27
35+50.00	1	1	0
36+00.00	0	2	0
36+50.00	0	5	0
37+00.00	4	3	0
37+50.00	9	0	0
38+00.00	4	8	0

Station Y3A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
13+75.00	0	0	0
14+25.00	19	0	149
14+75.00	75	14	253
15+00.00	25	4	198

Station Y3B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+13.55	0	0	0
10+25.00	30	0	107
10+75.00	174	2	448
11+16.00	50	13	264
11+75.00	47	36	183
12+25.00	64	19	160
12+74.19	95	11	161
13+25.00	110	13	166
13+75.00	119	11	164
14+25.00	115	10	164
14+48.13	27	3	68

Station Y3B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+75.00	45	0	78
15+25.00	175	0	163
15+50.00	109	0	82
15+75.00	129	0	87
15+90.93	98	0	61
16+25.00	232	0	144

Station Y3Lpa	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+98.42	0	0	0
12+50.00	0	4113	0
13+00.00	0	4027	0
13+50.00	0	4031	0
14+00.00	0	3779	0
14+50.00	0	3286	0
15+00.00	0	2661	0
15+50.00	0	2029	0
15+98.94	0	1707	0

Station Y3Lpd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+94.78	0	0	0
12+50.00	0	2526	0
13+06.00	0	2465	0
13+50.00	0	1659	0
14+00.00	0	1373	0
14+50.00	0	911	0
15+00.00	0	532	26
15+50.00	12	198	152
15+74.22	6	15	122

Station Y3Rpa	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
14+26.44	0	0	0
14+50.00	0	312	0
15+00.00	0	653	0
15+50.00	0	675	0
16+00.00	0	751	0
16+50.00	0	838	0
17+00.00	0	1033	231
17+50.00	0	1421	257
18+00.00	0	1717	237
18+48.13	0	1343	120
19+00.00	0	827	1
19+50.00	0	638	0
20+00.00	0	721	0
20+58.13	0	871	0
21+00.00	0	652	0
21+50.00	0	813	0
22+00.00	0	829	0