

DB3C8E45B06D499

DESIGN ENGINEER OF RECORD:


DRAWN BY : R. J. FLORY

CHECKED BY : R. C. LARSON

DATE : 2/12/2015

DATE: 1/27/14

__ DATE : 2/06/14



BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

R-2514D PROJECT NO. __ JONES . COUNTY STATION: 363+38.90 -L-

SHEET 3 OF 3

SEAL 14114

2/12/2015

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

> SUBSTRUCTURE END BENT 1

			L	_EF	T LA	NE	STR-#3
ENGINEERS & PLANNERS & ECOLOGISTS LICENSE MUMBER: C-0764	REVISIONS						SHEET NO.
KCI Associates of North Carolina, P.A.	NO.	BY:	DATE:	NO.	BY:	DATE:	S03-I7
SLITE 220, LANDMARK CENTER 14601SIX FORKS RD. RALEIGH, N.C. 27609-5210 (989) 783-924				3			TOTAL SHEETS
DWG.REF.NO. 17 OF 23	2			4			S03-23

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER.

TEMPORARY DRAINAGE AT END BENT