PROJECT NO.	SHEET NO.	TOTAL NO.
8CR.10531.27, 8CR.20531.27	9	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4688000000-E 6" X 90 M WHITE THERMO LF	4688000000-E 6" X 90 M YELLOW THERMO LF	4690000000-E 6" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4700000000-E 12" X 90 M WHITE THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO MERGE ARROW 90 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4815000000-E 6" YELLOW PAINT LF	4900000000-N YELLOW & YELLOW MARKERS EA	4900000000-N CRYSTAL & RED MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS C & R MARKERS EA
8CR.10531.27	Lee	1	US 1 NBL & SBL	FROM NC 42 TO CONST. JT NORTH OF US 421 BUS.	1	4	MD	1.84	72	158		40					19,475	19,475	6,715		4,260				6									600
TOTAL FOR MAP NO. 1								**1.84**		**158**		**40**					**19,475**	**19,475**	**6,715**		**4,260**				**6**									**600**
8CR.10531.27	Lee	2	NC 87	FROM SR 1290 (COMMERCE DR) TO HARNETT CO LINE	2	5	M2	2.64	60	296		80	27,925		33,625	7,895							225			85	5	8				465	400	
TOTAL FOR MAP NO. 2								**2.64**		**296**		**80**	**27,925**		**33,625**	**7,895**							**225**			**85**	**5**	**8**				**465**	**400**	
8CR.10531.27	Lee	6	US 421 BYP. NB & SB (16 SECTIONS)	FROM SR 1406 (COLON RD) TO NC 42	4-9	2	MD	0.3	37	316	*		2,060	2,060		890													2,950	2,100	2,100			20
TOTAL FOR MAP NO. 6								**0.3**		**316**	*		**2,060**	**2,060**		**890**													**2,950**	**2,100**	**2,100**			**20**
TOTAL FOR PROJ NO. 8CR.10531.27								**4.78**		**770**	**1***	**120**	**29,985**	**2,060**	**33,625**	**8,785**	**19,475**	**19,475**	**6,715**		**4,260**		**225**		**6**	**85**	**5**	**8**	**2,950**	**2,100**	**2,100**	**465**	**400**	**620**
													32,045		**42,410**		**38,950**								**104**				**5,050**			**865**		
8CR.20531.27	Lee	3	SR 1182 (CEDAR LN)	FROM PVMT JT AT US 15-501 TO PVMT JT AT US 1	3	2	2WU	3.03	22	340																			63,985	59,935				
TOTAL FOR MAP NO. 3								**3.03**		**340**																			**63,985**	**59,935**				
8CR.20531.27	Lee	4	SR 1415 (COLON RD)	FROM PVMT JT AT US 421 BYPASS THENCE SOUTH TO CL AT FAIRGROUNDS	3	2	2WU	0.81	24	91			8,465		8,295																	53		
TOTAL FOR MAP NO. 4								**0.81**		**91**			**8,465**		**8,295**																	**53**		
8CR.20531.27	Lee	5	SR 1415 (COLON RD)	FROM PVMT JT 700'+- NORTH OF US 421 BYPASS TO SR 1422 (OSGOOD RD)	3	2	2WU	3.65	24	409			38,710		34,650	220				100		160	168	6		2						255		
TOTAL FOR MAP NO. 5								**3.65**		**409**	*		**38,710**		**34,650**	**220**				**100**		**160**	**168**	**6**		**2**						**255**		
TOTAL FOR PROJ NO. 8CR.20531.27								**7.49**		**840**	**1***		**47,175**		**42,945**	**220**				**100**		**160**	**168**	**6**		**2**			**63,985**	**59,935**		**308**		
													47,175		**43,165**										**2**				**123,920**			**308**		
GRAND TOTAL								**12.27**		**1,610**	**1**	**120**	**77,160**	**2,060**	**76,570**	**9,005**	**19,475**	**19,475**	**6,715**	**100**	**4,260**	**160**	**393**	**6**	**6**	**87**	**5**	**8**	**66,935**	**62,035**	**2,100**	**773**	**400**	**620**
													79,220		**85,575**		**38,950**								**106**				**128,970**			**1,173**		