PROJECT NO.	SHEET NO.	TOTAL NO.
8CR.10771.27, 8CR.20771.27	15	
8SP.20775.1,		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4688000000-E 6" X 90 M WHITE THERMO LF	4688000000-E 6" X 90 M YELLOW THERMO LF	4690000000-E 6" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO MERGE ARROW 90 M EA	4770000000-E COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II (4") LF	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4815000000-E 6" WHITE PAINT LF	4815000000-E 6" YELLOW PAINT LF	4835000000-E 24" WHITE PAINT LF	4900000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS Y & Y MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS C & R MARKERS EA
8CR.10771.27	Richmond	1	US 1	FROM SC LINE TO SR 1105 (HAMMER MILL RD.)	1	2	2WU	7.27	24	815			76,253		58,279	243																	10	500	
TOTAL FOR MAP NO. 1								**7.27**		**815**			**76,253**		**58,279**	**243**																	**10**	**500**	
8CR.10771.27	Richmond	2	NC 177	FROM PVT. JT. 0.18 MI. SOUTH OF SR 1900 TO CSX RR BRIDGE	2,3, & 4	2	2WU	1.06	26	119		40	11,406		9,591	134				71							21,100				71	2	72	
TOTAL FOR MAP NO. 2								**1.06**		**119**		**40**	**11,406**		**9,591**	**134**				**71**							**21,100**				**71**	**2**	**72**	
8CR.10771.27	Richmond	3	US 74 BUS EBL	FROM PVT. JT. 0.18 MI WEST OF SR 1847 TO GORE AT US 74 BYPASS EBL	5	2	MD	0.72	32	239			1,567	958	160	304	2,710	2,780	530	66		3	4	1	5		1,900	1,200	3,150	2,300	66		2	62
TOTAL FOR MAP NO. 3								**0.72**		**239**			**1,567**	**958**	**160**	**304**	**2,710**	**2,780**	**530**	**66**		**3**	**4**	**1**	**5**		**1,900**	**1,200**	**3,150**	**2,300**	**66**		**2**	**62**
8CR.10771.27	Richmond	4	US 74 BUS WBL	FROM GORE @ US 74 BYPASS WBL TO PAVT. JT. 0.09 MI WEST OF SR 1725	5	2	MD	0.48	32	158			400	523	246	200	1,847	1,542	426	40		3	4	1			522	240	2,275	1,550	40	2	4	43
TOTAL FOR MAP NO. 4								**0.48**		**158**			**400**	**523**	**246**	**200**	**1,847**	**1,542**	**426**	**40**		**3**	**4**	**1**			**522**	**240**	**2,275**	**1,550**	**40**	**2**	**4**	**43**
TOTAL FOR PROJ NO. 8CR.10771.27								**9.53**		**1,331**	*	**40**	**89,626**	**1,481**	**68,276**	**881**	**4,557**	**4,322**	**956**	**177**		**6**	**8**	**2**	**5**		**23,522**	**1,440**	**5,425**	**3,850**	**177**	**14**	**578**	**105**
													91,107		**69,157**		**8,879**					**21**					**24,962**		**9,275**				**683**	
8CR.20771.27	Richmond	5	SR 1450	FROM US 220 BUS. TO SR 1441	6,7	2	2WU	3.06	22	377										100	12		2			732	63,820	48,816				210		
TOTAL FOR MAP NO. 5								**3.06**		**377**										**100**	**12**		**2**			**732**	**63,820**	**48,816**				**210**		
8CR.20771.27	Richmond	6	SR 1713	FROM SR 1615 TO SR 1714	8,9	2	2WU	0.3	26-30																	1,206	5,524	5,100						
TOTAL FOR MAP NO. 6								**0.3**																		**1,206**	**5,524**	**5,100**						
TOTAL FOR PROJ NO. 8CR.20771.27								**3.36**		**377**	*									**100**	**12**		**2**			**1,938**	**69,344**	**53,916**				**210**		
																							2				**123,260**							
8SP.20775.1	Richmond	7	SR 1551	FROM SR 1436 TO DEAD END	10	2	2WU	0.44	20	50																								
TOTAL FOR MAP NO. 7								**0.44**		**50**																								
8SP.20775.1	Richmond	8	SR 1569	FROM SR 1551 TO DEAD END	10	2	2WU	0.2	22	23																								
TOTAL FOR MAP NO. 8								**0.2**		**23**																								
TOTAL FOR PROJ NO. 8SP.20775.1								**0.64**		**73**	*																							
GRAND TOTAL								**13.53**		**1,781**	**1**	**40**	**89,626**	**1,481**	**68,276**	**881**	**4,557**	**4,322**	**956**	**277**	**12**	**6**	**10**	**2**	**5**	**1,938**	**92,866**	**55,356**	**5,425**	**3,850**	**177**	**224**	**578**	**105**
													91,107		**69,157**		**8,879**					**23**					**148,222**		**9,275**				**683**	