



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	34429.3.S9 (R-2413CA)	1	12

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 34429.3.S9 (R-2413CA) F.A. PROJ. NA
COUNTY ROCKINGHAM
PROJECT DESCRIPTION US 220 /FUTURE I-73 FROM NORTH OF
NC 65 TO NORTH OF SR 2338 (NEWMAN RD.)
SITE DESCRIPTION PROPOSED BRIDGE ON -LREV SB- (US 220 SB)
OVER -NC68 NB- (NC 68 NB) AT -LREV SB- STA. 90+64.5

INVENTORY

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5,6	CROSS SECTION(S)
7-10	BORE LOG(S)
11	SOIL TEST RESULTS
12	SITE PHOTOGRAPH

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

ID: R-2413CA

PROJECT: 34429.3.S9

PERSONNEL

O. B. OTI

H. R. CONLEY

D. G. PINTER

J. R. MATULA

INVESTIGATED BY J. L. PEDRO

CHECKED BY N. T. ROBERSON

SUBMITTED BY N. T. ROBERSON

DATE FEBRUARY 2015



DocuSigned by:

Jaime Love Pedro

93571039B884B5...

2/4/2015

DRAWN BY: J. L. PEDRO, T. T. WALKER

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT



PROJECT REFERENCE NO. 34429.3.S9 (R-2413CA) SHEET NO. 2


SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS


SOIL DESCRIPTION		GRADATION		ROCK DESCRIPTION		TERMS AND DEFINITIONS																																																																																																																																											
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER 30 CM ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: VERY STIFF, GRAY, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6		WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES. ANGULARITY OF GRAINS THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: <u>ANGULAR</u> , <u>SUBANGULAR</u> , <u>SUBROUNDED</u> , OR <u>ROUNDED</u> .		HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 3 CM PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: WEATHERED ROCK (WR) NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER 30 CM IF TESTED. CRYSTALLINE ROCK (CR) FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC. NON-CRYSTALLINE ROCK (NCR) FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC. COASTAL PLAIN SEDIMENTARY ROCK (CP) COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.		ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 10 CM DIVIDED BY THE TOTAL LENGTH AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N) OF A 63.5 KG HAMMER FALLING 0.76 M REQUIRED TO PRODUCE A PENETRATION OF 30 CM INTO SOIL WITH A 5 CM OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 3 CM PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 10 CM DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.																																																																																																																																											
SOIL LEGEND AND AASHTO CLASSIFICATION <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th rowspan="2">GENERAL CLASS.</th> <th colspan="6">GRANULAR MATERIALS (<= 35% PASSING #200)</th> <th colspan="6">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="3">ORGANIC MATERIALS</th> </tr> <tr> <th>A-1</th> <th>A-3</th> <th colspan="2">A-2</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-7-5</th> <th>A-7-6</th> <th>A-1, A-2</th> <th>A-4, A-5</th> <th colspan="2"></th> </tr> </thead> <tbody> <tr> <td>GROUP CLASS.</td> <td>A-1-a</td> <td>A-1-b</td> <td>A-2-4</td> <td>A-2-5</td> <td>A-2-6</td> <td>A-2-7</td> <td></td> <td></td> <td></td> <td></td> <td>A-3</td> <td>A-6, A-7</td> <td colspan="2"></td> </tr> <tr> <td>SYMBOL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td colspan="2"></td> </tr> <tr> <td>% PASSING</td> <td>50 MX</td> <td>30 MX</td> <td>50 MX</td> <td>50 MX</td> <td>51 MN</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>GRANULAR SOILS</td> <td>SILT-CLAY SOILS</td> <td>MUCK, PEAT</td> </tr> <tr> <td>LIQUID LIMIT PLASTIC INDEX</td> <td>6 MX</td> <td>NP</td> <td>40 MX</td> <td>41 MN</td> <td>40 MX</td> <td>41 MN</td> <td>40 MX</td> <td>41 MN</td> <td>40 MX</td> <td>41 MN</td> <td>40 MX</td> <td>41 MN</td> <td colspan="2">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td>HIGHLY ORGANIC SOILS</td> </tr> <tr> <td>GROUP INDEX</td> <td>0</td> <td>0</td> <td>0</td> <td>4 MX</td> <td>8 MX</td> <td>12 MX</td> <td>16 MX</td> <td>No MX</td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td></td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td>STONE FRAGS. GRAVEL AND SAND</td> <td>FINE SAND</td> <td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="2">CLAYEY SOILS</td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td></td> </tr> <tr> <td>GEN. RATING AS A SUBGRADE</td> <td colspan="6">EXCELLENT TO GOOD</td> <td colspan="3">FAIR TO POOR</td> <td>FAIR TO POOR</td> <td>POOR</td> <td colspan="2">UNSUITABLE</td> <td colspan="2"></td> </tr> </tbody> </table>		GENERAL CLASS.	GRANULAR MATERIALS (<= 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS			A-1	A-3	A-2		A-4	A-5	A-6	A-7	A-7-5	A-7-6	A-1, A-2	A-4, A-5			GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7					A-3	A-6, A-7			SYMBOL															% PASSING	50 MX	30 MX	50 MX	50 MX	51 MN								GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT	LIQUID LIMIT PLASTIC INDEX	6 MX	NP	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS	GROUP INDEX	0	0	0	4 MX	8 MX	12 MX	16 MX	No MX								USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS									GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR			FAIR TO POOR	POOR	UNSUITABLE				MINERALOGICAL COMPOSITION MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.		WEATHERING FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE. VERY SLIGHT (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE. SLIGHT (SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.	
GENERAL CLASS.	GRANULAR MATERIALS (<= 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS																																																																																																																																				
	A-1	A-3	A-2		A-4	A-5	A-6	A-7	A-7-5	A-7-6	A-1, A-2	A-4, A-5																																																																																																																																					
GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7					A-3	A-6, A-7																																																																																																																																					
SYMBOL																																																																																																																																																	
% PASSING	50 MX	30 MX	50 MX	50 MX	51 MN								GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT																																																																																																																																		
LIQUID LIMIT PLASTIC INDEX	6 MX	NP	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS																																																																																																																																		
GROUP INDEX	0	0	0	4 MX	8 MX	12 MX	16 MX	No MX																																																																																																																																									
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS																																																																																																																																										
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR			FAIR TO POOR	POOR	UNSUITABLE																																																																																																																																					
CONSISTENCY OR DENSENESS <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (kN/m²)</th> </tr> </thead> <tbody> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td> <td><4 4 TO 10 10 TO 30 30 TO 50 >50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td> <td><2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30</td> <td><25 25 TO 50 50 TO 100 100 TO 200 200 TO 400 >400</td> </tr> </tbody> </table>		PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (kN/m ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<25 25 TO 50 50 TO 100 100 TO 200 200 TO 400 >400	MISCELLANEOUS SYMBOLS ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY DIP & DIP DIRECTION OF ROCK STRUCTURES TEST BORING AUGER BORING CORE BORING MONITORING WELL PIEZOMETER INSTALLATION SLOPE INDICATOR INSTALLATION CONE PENETROMETER TEST SOUNDING ROD																																																																																																																																			
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (kN/m ²)																																																																																																																																														
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A																																																																																																																																														
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<25 25 TO 50 50 TO 100 100 TO 200 200 TO 400 >400																																																																																																																																														
TEXTURE OR GRAIN SIZE <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> </thead> <tbody> <tr> <td></td> <td>4.76</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </tbody> </table>		U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.76	2.00	0.42	0.25	0.075	0.053	ABBREVIATIONS AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED, FRACTURES FRAGS. - FRAGMENTS HI. - HIGHLY MED. - MEDIUM MICA. - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT V - VERY VST - VANE SHEAR TEST WEA. - WEATHERED W - UNIT WEIGHT W _c - DRY UNIT WEIGHT SAMPLE ABBREVIATIONS S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO																																																																																																																																	
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																																											
	4.76	2.00	0.42	0.25	0.075	0.053																																																																																																																																											
SOIL MOISTURE - CORRELATION OF TERMS <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </tbody> </table>		SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	EQUIPMENT USED ON SUBJECT PROJECT DRILL UNITS: <input type="checkbox"/> MOBILE B- <input type="checkbox"/> BK-51 <input type="checkbox"/> CME-45C <input checked="" type="checkbox"/> CME-550 <input type="checkbox"/> PORTABLE HOIST ADVANCING TOOLS: <input type="checkbox"/> CLAY BITS <input type="checkbox"/> 152mm CONTINUOUS FLIGHT AUGER <input checked="" type="checkbox"/> 203mm HOLLOW AUGERS <input type="checkbox"/> HARD FACED FINGER BITS <input checked="" type="checkbox"/> TUNG.-CARBIDE INSERTS <input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER <input type="checkbox"/> TRICONE _____mm STEEL TEETH <input type="checkbox"/> TRICONE _____mm TUNG.-CARB. <input type="checkbox"/> CORE BIT HAMMER TYPE: <input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL CORE SIZE: <input type="checkbox"/> -B <input type="checkbox"/> -N <input type="checkbox"/> -H HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST																																																																																																																																
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																															
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																															
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																															
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																															
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																															
PLASTICITY <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> </thead> <tbody> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </tbody> </table>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	FRACTURE SPACING <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>TERM</th> <th>SPACING</th> </tr> </thead> <tbody> <tr> <td>VERY WIDE</td> <td>MORE THAN 3 M</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 M</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>30 TO 100 CM</td> </tr> <tr> <td>CLOSE</td> <td>5 TO 30 CM</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 5 CM</td> </tr> </tbody> </table>		TERM	SPACING	VERY WIDE	MORE THAN 3 M	WIDE	3 TO 10 M	MODERATELY CLOSE	30 TO 100 CM	CLOSE	5 TO 30 CM	VERY CLOSE	LESS THAN 5 CM	BEDDING <table border="1" style="width: 100%; border-collapse: collapse; font-size: 6px;"> <thead> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> </thead> <tbody> <tr> <td>VERY THICKLY BEDDED</td> <td>> 1 M</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>0.5 - 1 M</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.05 - 0.5 M</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>10 - 50 MM</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>2.5 - 10 MM</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>< 2.5 MM</td> </tr> </tbody> </table>		TERM	THICKNESS	VERY THICKLY BEDDED	> 1 M	THICKLY BEDDED	0.5 - 1 M	THINLY BEDDED	0.05 - 0.5 M	VERY THINLY BEDDED	10 - 50 MM	THICKLY LAMINATED	2.5 - 10 MM	THINLY LAMINATED	< 2.5 MM																																																																																																			
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																																															
LOW PLASTICITY	0-5	VERY LOW																																																																																																																																															
MED. PLASTICITY	6-15	SLIGHT																																																																																																																																															
HIGH PLASTICITY	16-25	MEDIUM																																																																																																																																															
	26 OR MORE	HIGH																																																																																																																																															
TERM	SPACING																																																																																																																																																
VERY WIDE	MORE THAN 3 M																																																																																																																																																
WIDE	3 TO 10 M																																																																																																																																																
MODERATELY CLOSE	30 TO 100 CM																																																																																																																																																
CLOSE	5 TO 30 CM																																																																																																																																																
VERY CLOSE	LESS THAN 5 CM																																																																																																																																																
TERM	THICKNESS																																																																																																																																																
VERY THICKLY BEDDED	> 1 M																																																																																																																																																
THICKLY BEDDED	0.5 - 1 M																																																																																																																																																
THINLY BEDDED	0.05 - 0.5 M																																																																																																																																																
VERY THINLY BEDDED	10 - 50 MM																																																																																																																																																
THICKLY LAMINATED	2.5 - 10 MM																																																																																																																																																
THINLY LAMINATED	< 2.5 MM																																																																																																																																																
COLOR DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.		INDURATION FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC. FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																															
NOTES: BENCH MARK: BL-48 AT -NC68-NB- STA. 15+16.7, OFFSET - 3.7m LT ELEVATION: 264.46 M		NOTES:																																																																																																																																															




SITE PLAN




SKREW ANGLE = 70°





PROJECT REFERENCE NO.	SHEET
34429.3.S9 (R-2413CA)	4
FENCE DIAGRAM THROUGH BORINGS PROJECTED ALONG -LREV_SB-	



NOTE: GROUNDLINE DRAWN USING TIN FILE DATED 4/21/2014

90+40

90+60

90+80

EBI-A
90 + 35.9
7.2m LT

EBI-B
90 + 39.0
6.6m RT

⊕

272
270

272
270

268
266

268
266

264
262

264
262

260
258

260
258

256
254

256
254

252
250

252
250

248
246




248
246

244
242

244
242

240
238

240
238



RESIDUAL, TAN-BROWN AND ORANGE,

MOIST, SILTY CLAY AND HIGHLY PLASTIC,

TAN-BROWN AND WHITE WITH SOME

BLACK AND ORANGE, MEDIUM STIFF

TO STIFF, MOIST, SAPROLITIC,

SANDY SILT WITH TRACE TO

ABUNDANT MICA AND SOME SILTY SAND

TAN-BROWN, WHITE, BROWN, AND ORANGE,

LOOSE TO VERY DENSE, MOIST,

SAP., SILTY SAND WITH SOME MICA

WEATHERED ROCK (GNEISS)

9
11
14
11

9
11
7
5
11

9
13
29
18
21

100/0.19
100/0.29
100/0.27

13
8
9

8
7
6
5
6
7

11
15
22
58


100/0.11
100/0.28
91
100/0.20

CAVED
04/14

CAVED
05/14


WEATHERED ROCK (GNEISS)

Ⓐ RESIDUAL, BROWN AND WHITE, V. DENSE,
MOIST, SAPROLITIC, MICACEOUS, SILTY SAND




PROJECT REFERENCE NO.	SHEET
34429.3.S9 (R-2413CA)	5
CROSS SECTION THROUGH END BENT 1	

14 12 10 8 6 4 2 0 2 4 6 8 10



PROJECT REFERENCE NO.	SHEET
34429.3.S9 (R-2413CA)	6
CROSS SECTION THROUGH END BENT 2	





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 34429.3.S9	TIP R-2413CA	COUNTY ROCKINGHAM	GEOLOGIST Pedro, J. L.	
SITE DESCRIPTION PROPOSED BRIDGE ON -LREV_SB- (US 220 SB) OVER -NC68_NB- (NC 68 NB)				GROUND WTR (m)
BORING NO. EB1-B	STATION 90+39.0	OFFSET 6.6 m RT	ALIGNMENT -LREV_SB-	0 HR. Caved
COLLAR ELEV. 268.55 m	TOTAL DEPTH 25.53 m	NORTHING 281,529.6	EASTING 525,179.7	24 HR. Caved
DRILL RIG/HAMMER EFF./DATE RFO0067 CME-550X 77% 03/15/2010		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic	
DRILLER Conley, H. R.	START DATE 05/19/14	COMP. DATE 05/19/14	SURFACE WATER DEPTH N/A	

WBS 34429.3.S9	TIP R-2413CA	COUNTY ROCKINGHAM	GEOLOGIST Pedro, J. L.	
SITE DESCRIPTION PROPOSED BRIDGE ON -LREV_SB- (US 220 SB) OVER -NC68_NB- (NC 68 NB)				GROUND WTR (m)
BORING NO. EB1-B	STATION 90+39.0	OFFSET 6.6 m RT	ALIGNMENT -LREV_SB-	0 HR. Caved
COLLAR ELEV. 268.55 m	TOTAL DEPTH 25.53 m	NORTHING 281,529.6	EASTING 525,179.7	24 HR. Caved
DRILL RIG/HAMMER EFF./DATE RFO0067 CME-550X 77% 03/15/2010		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic	
DRILLER Conley, H. R.	START DATE 05/19/14	COMP. DATE 05/19/14	SURFACE WATER DEPTH N/A	

ELEV (m)	DRIVE ELEV (m)	DEPTH (m)	BLOW COUNT			BLOWS PER 30 CM					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (m)	
			15cm	15cm	15cm	0	25	50	75	100						
269																
268	267.54	1.01	3	5	8											
267	266.02	2.53	3	4	4											
266	264.50	4.05	2	4	5											
265	262.98	5.57	2	3	5											
264	261.46	7.09	3	3	4											
263	259.94	8.61	1	3	3											
262	258.42	10.13	2	2	3											
261	256.90	11.65	1	3	3											
260	255.38	13.17	2	2	5											
259	253.86	14.69	4	5	6											
258	252.34	16.21	2	6	9											
257	250.82	17.73	6	8	14											
256	249.30	19.25	18	31	27											

ELEV (m)	DRIVE ELEV (m)	DEPTH (m)	BLOW COUNT			BLOWS PER 30 CM					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (m)	
			15cm	15cm	15cm	0	25	50	75	100						
249																
248	247.78	20.77	100	0	11											
247	246.26	22.29	28	72	13											
246	244.74	23.81	28	29	62											
245	243.22	25.33	70	80	05											

NCDOT BORE DOUBLE R2413C_GEO_BRDGNW_BH.GPJ_NC_DOT.GDT 2/3/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34429.3.S9	TIP R-2413CA	COUNTY ROCKINGHAM	GEOLOGIST Oti, O. B.
SITE DESCRIPTION PROPOSED BRIDGE ON -LREV_SB- (US 220 SB) OVER -NC68_NB- (NC 68 NB)			GROUND WTR (m)
BORING NO. EB2-B	STATION 90+81.9	OFFSET 4.8 m RT	ALIGNMENT -LREV_SB-
COLLAR ELEV. 268.30 m	TOTAL DEPTH 24.35 m	NORTHING 281,568.4	EASTING 525,161.2
DRILL RIG/HAMMER EFF./DATE RFO0067 CME-550X 77% 03/15/2010		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER Conley, H. R.	START DATE 05/05/14	COMP. DATE 05/05/14	SURFACE WATER DEPTH N/A

ELEV (m)	DRIVE ELEV (m)	DEPTH (m)	BLOW COUNT			BLOWS PER 30 CM					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (m)	
			15cm	15cm	15cm	0	25	50	75	100					
269															
268	268.30	0.00	3	4	6									268.30	GROUND SURFACE
267	267.20	1.10	4	6	7										RESIDUAL RED-BROWN, HIGHLY PLASTIC, SILTY CLAY
266	265.68	2.62	4	5	7										
265															
264	264.16	4.14	3	4	4									264.30	TAN-BROWN, SAPROLITIC, CLAYEY SILT WITH TRACE MICA
263	262.64	5.66	3	3	4										
262															
261	261.12	7.18	3	3	4										
260															
259	259.60	8.70	1	2	3										
258	258.08	10.22	2	4	5										
257	256.56	11.74	1	2	3										
256															
255	255.04	13.26	2	4	5									255.60	TAN-BROWN, SAPROLITIC, SANDY SILT
254															
253	253.52	14.78	1	3	4										
252	252.00	16.30	2	4	5										
251															
250	250.48	17.82	11	13	13										
249	248.96	19.34	10	15	38									249.50	TAN-BROWN, SAPROLITIC, SILTY SAND WITH TRACE MICA

WBS 34429.3.S9	TIP R-2413CA	COUNTY ROCKINGHAM	GEOLOGIST Oti, O. B.
SITE DESCRIPTION PROPOSED BRIDGE ON -LREV_SB- (US 220 SB) OVER -NC68_NB- (NC 68 NB)			GROUND WTR (m)
BORING NO. EB2-B	STATION 90+81.9	OFFSET 4.8 m RT	ALIGNMENT -LREV_SB-
COLLAR ELEV. 268.30 m	TOTAL DEPTH 24.35 m	NORTHING 281,568.4	EASTING 525,161.2
DRILL RIG/HAMMER EFF./DATE RFO0067 CME-550X 77% 03/15/2010		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER Conley, H. R.	START DATE 05/05/14	COMP. DATE 05/05/14	SURFACE WATER DEPTH N/A

ELEV (m)	DRIVE ELEV (m)	DEPTH (m)	BLOW COUNT			BLOWS PER 30 CM					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (m)	
			15cm	15cm	15cm	0	25	50	75	100					
249															
248	247.44	20.86	10	13	16										TAN-BROWN, SAPROLITIC, SILTY SAND WITH TRACE MICA (continued)
247															
246	245.92	22.38	23	28	30										
245															
244	244.40	23.90	30	37	46									243.95	Boring Terminated at Elevation 243.95 m IN RESIDUAL (SILTY SAND)

NCDOT BORE DOUBLE R2413C_GEO_BRDGNW_BH.GPJ NC_DOT.GDT 2/3/15

PROJ. NO. - 34429.3.S9
ID NO. - R-2413CA
COUNTY - ROCKINGHAM

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	6.6M RT	90+39.0	1.01-1.46	A-7-6(21)	56	31	8.7	26.0	17.1	48.3	100	96	70	-	-
SS-2	6.6M RT	90+39.0	2.53-2.98	A-7-6(15)	48	24	8.2	29.6	19.9	42.3	100	97	67	-	-
SS-3	6.6M RT	90+39.0	4.05-4.50	A-4(0)	39	NP	22.7	44.7	24.5	8.0	100	89	41	-	-
SS-4	6.6M RT	90+39.0	10.13-10.58	A-2-5(0)	47	NP	16.1	58.6	19.3	6.0	100	96	33	-	-
SS-5	6.6M RT	90+39.0	11.65-12.10	A-4(0)	33	NP	18.9	50.9	22.1	8.0	100	95	39	-	-
SS-6	6.6M RT	90+39.0	14.69-15.14	A-4(0)	34	NP	14.1	55.7	24.1	6.0	98	94	40	-	-
SS-7	6.6M RT	90+39.0	19.25-19.70	A-2-4(0)	29	NP	32.4	41.4	20.1	6.0	100	86	33	-	-
SS-8	6.6M RT	90+39.0	23.81-24.26	A-2-4(0)	32	NP	19.9	49.7	24.3	6.0	95	87	35	-	-

EB2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-9	5.6M LT	90+39.0	1.09-1.54	A-7-6(17)	51	28	10.7	28.2	12.9	48.3	99	95	65	-	-
SS-10	5.6M LT	90+75.0	7.17-7.62	A-5(0)	41	NP	13.7	45.5	30.8	10.1	100	96	51	42.1	-
SS-11	5.6M LT	90+75.0	13.25-13.70	A-4(0)	30	NP	20.5	45.5	26.0	8.0	99	92	42	-	-
ST-1	5.6M LT	90+75.0	13.70-14.30	A-4(0)	35	3	15.5	48.6	29.9	6.0	10	96	48	-	-
SS-12	5.6M LT	90+75.0	19.33-19.78	A-4(0)	34	NP	20.7	44.7	26.6	8.0	100	93	42	-	-

SITE PHOTOGRAPH

Proposed Bridge on -LREV_SB- (US 220 SB) over -NC68_NB- (NC 68 NB)



Looking Northwest towards End Bent 2