



MAP 2
 Long St. SR 2100
 Mill and Pave approximately 75 feet southwest of stop bar on Long St. at Innes St. intersection to replace Loops. (Loops by NCDOT)
 From Innes St. edge of pavement to Council St. Mill Curb 0-1½" a 12 foot width each side. Tie into new surface at Innes St.

From Council St. through Bringle Ferry Rd. Intersection Mill entire width a 1½" Depth to expose gutter, then Mill Curb 0-1½" at face of gutter a 12 foot width each side. Pave back flush to top of gutter.

From Bringle Ferry Rd. to Long Ferry Rd. Mill full width 1½" Depth.

Map 3
 Innes St. SR 2200
 Mill entire width a 1½" Depth to expose gutter, then Mill Curb 0-1½" at face of gutter a 12 foot width each side. Pave back flush to top of gutter.