

PROJECT NO.	SHEET NO.	TOTAL NO.
9CR.10851.160, 9CR.20851.160	6	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW EXCAVATION CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	TEMPORARY SILT FENCE LF	WATTLE LF
9CR.10851.160	Stokes	1	NC 8	FROM NC 89 TO VIRGINIA STATE LINE	1	2	2WU	NO	NO	8.719	20	1,046	765	17.44		2,178	10,118	607	3,487	349
TOTAL FOR MAP NO. 1										8.719		1,046	765	17.44		2,178	10,118	607	3,487	349
TOTAL FOR PROJ NO. 9CR.10851.160										8.719		1,046	765	17.44		2,178	10,118	607	3,487	349
9CR.20851.160	Stokes	2	SR 1136 VOLUNTEER RD.	FROM HIGH BRIDGE RD. (SR 1157) TO CHESTNUT GROVE RD. (SR 1136)	1	2	2WU	NO	NO	3.628	22	435	165	7.26	288	2,210	4,351	261	1,451	145
TOTAL FOR MAP NO. 2										3.628		435	165	7.26	288	2,210	4,351	261	1,451	145
9CR.20851.160	Stokes	3	SR 1157 HIGH BRIDGE RD.	FROM OLD US 52 RD. (SR 1236) TO NORTH EAST SIDE OF VOLUNTEER RD. (SR 1136)	1	2	2WU	NO	NO	2.92	20	350	231	5.84		659	3,344	201	1,168	117
TOTAL FOR MAP NO. 3										2.92		350	231	5.84		659	3,344	201	1,168	117
TOTAL FOR PROJ NO. 9CR.20851.160										6.548		785	396	13.10	288	2,869	7,695	462	2,619	262
GRAND TOTAL										15.267		1,831	1,161	30.54	288	5,047	17,813	1,069	6,106	611

NOTE: All Quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received.